



LE GOUVERNEMENT
DU GRAND-DUCHÉ DE LUXEMBOURG
Ministère de la Mobilité
et des Travaux publics

Département de la mobilité
et des transports

SOCIÉTÉ NATIONALE DE
CERTIFICATION ET D'HOMOLOGATION
S.A.

Registre de Commerce: B 27180



L-8070 Bertrange

Référence: e13*168/2013*02582*00

Annexes: - Rapport technique
- Fiche de renseignements du constructeur

Bertrange, le 03 juin 2025

FICHE DE RÉCEPTION UE PAR TYPE D'UN VÉHICULE ENTIER

EU WHOLE-VEHICLE TYPE-APPROVAL CERTIFICATE

Communication concernant:

Communication concerning:

- la réception UE par type d'un véhicule entier
EU whole-vehicle type-approval
- ~~l'extension de la réception UE par type d'un véhicule entier~~
~~extension of EU whole-vehicle type approval~~
- ~~le refus de la réception UE par type d'un véhicule entier~~
~~refusal of EU whole-vehicle type approval~~
- ~~le retrait de la réception UE par type d'un véhicule entier~~
~~withdrawal of EU whole-vehicle type approval~~

pour un type de véhicule complet
of a complete vehicle type

en vertu du règlement (UE) N° 168/2013,
modifié en dernier lieu par le règlement (délégué de la Commission) (UE) N° 2024/2847
with regard to Regulation (EU) N° 168/2013,-as last amended by (Commission Delegated) Regulation (EU) N° 2024/2847

Numéro de réception UE par type:

EU type-approval number:

e13*168/2013*02582*00

Raison de l'extension:

Reason for extension:

not applicable

SECTION I

SECTION I

- | | | |
|---------------|--|--|
| 0.1. | Marque (dénomination commerciale du constructeur):
Make (trade name of manufacturer): | RJTech, manufacturer's logo refer to manufacturer's |
| 0.2. | Type:
Type: | Steinadler Pro |
| 0.2.1. | Variante(s):
Variant(s): | 00 |
| 0.2.2. | Version(s):
Version(s): | 00 |
| 0.2.3. | Appellation(s) commerciale(s) (le cas échéant):
Commercial name(s) (if available): | Steinadler Pro (L7e) |
| 0.3. | Catégorie, sous-catégorie et sous-sous-catégorie du véhicule:
Category, subcategory and sub-subcategory of vehicle: | L7e-A1 |
| 0.4. | Raison sociale et adresse du constructeur du véhicule complet:
Company name and address of manufacturer of the complete vehicle: | Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Zone B, 528, Huilong South Rd, Rucheng Street, Rugao City,
Jiangsu Province, China |
| 0.4.1 | Nom(s) et adresse(s) de(s) usines d'assemblage:
Name(s) and adresse(s) of assembly plant(s): | Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Building 1, No. 1289, Duhui Rd, Minhang District,
Shanghai, China |
| 0.4.2. | Nom et adresse du mandataire du constructeur (le cas échéant):
Name and address of manufacturer's authorised representative, if any: | Benlinq
Henegouwenlaan 28, 1966RK Heemskerk, Netherlands |

SECTION II

SECTION II

- | | | |
|-----------|---|--------------------------------|
| 1. | Service technique responsable de la réalisation des essais:
Technical service responsible for carrying out the tests: | CETOC Technical Service s.r.l. |
| 2. | Date du rapport d'essais:
Date of test report: | 23.04.2025 |
| 3. | Numéro du rapport d'essais:
Number of test report: | CN-117-2-196-WHO25-26174-IR |

SECTION III

SECTION III

Le soussigné certifie l'exactitude de la description, faite par le constructeur dans la fiche de renseignements jointe, du type de véhicule décrit ci-dessus, dont un ou plusieurs échantillons représentatifs, sélectionnés par l'autorité compétente en matière de réception UE par type, ont été présentés en tant que prototypes du type de véhicule, et que les résultats d'essais joints s'appliquent au type de véhicule.

The undersigned hereby certifies the accuracy of the manufacturer's description in the attached information document of the vehicle type described above, for which one or more representative samples, selected by the EU type-approval authority, have been submitted as prototypes of the vehicle type and that the attached test results apply to the vehicle type.

- | | | |
|--------|---|---|
| 1. | <p>Le type de véhicule complet satisfait/
ne satisfait pas à l'ensemble des prescriptions
pertinentes énumérées dans l'annexe II du
règlement (UE) N° 168/2013.</p> <p>The complete vehicle type meets/does not meet all relevant requirements as listed in Annex II to Regulation (EU) N° 168/2013.</p> | <p>The complete vehicle type meets all relevant requirements as listed in Annex II to Regulation (EU) N° 168/2013</p> |
| 1.1. | <p>Restrictions de validité:</p> <p>Restrictions of validity:</p> | <p>not applicable</p> |
| 1.2. | <p>Dérogations accordées:</p> <p>Waivers applied:</p> | <p>not applicable</p> |
| 1.2.1. | <p>Raisons des dérogations:</p> <p>Reasons for the waivers:</p> | <p>not applicable</p> |
| 1.2.2. | <p>Autres exigences applicables:</p> <p>Alternative requirements:</p> | <p>not applicable</p> |
| 2. | <p>La réception est accordée/étendue/refusée/
retirée:</p> <p>The approval is granted/extended/refused/withdrawn:</p> | <p>the approval is granted</p> |
| 2.1. | <p>La réception est accordée conformément à
l'article 40 du règlement (UE) N° 168/2013 et
sa validité expire, par conséquent, le
jj/mm/aaaa.</p> <p>The approval is granted in accordance with Article 40 of Regulation (EU) N° 168/2013 and the validity of the approval is thus limited to dd/mm/yyyy.</p> | <p>not applicable</p> |

Lieu:
Place:

Bertrange

Date:
Date:

03 juin 2025

Signature:
Signature:

**Pour la Ministre de la Mobilité
et des Travaux publics**



Iliass ZERKTOUNI
Attaché

Pour la SNCH



Laurent LINDEN
Directeur opérationnel



Pièces jointes:
Attachments:

- **Dossier de réception**
Information package
- **Résultats d'essai**
Test results
- **Nom(s) et spécimen(s) de signature de la ou des personnes autorisées à signer les certificats de conformité et indication de leurs fonctions dans la société**
Name(s) and specimen(s) of the signature(s) of the person(s) authorised to sign certificates of conformity and a statement of their position in the company
- **Spécimen complété du certificat de conformité**
A completed specimen of the certificate of conformity

NB:
NB:

not applicable

Addendum à la fiche de réception UE par type

Addendum to the EU type-approval certificate

Liste des actes réglementaires aux prescriptions desquels le type de véhicule satisfait

List of regulatory acts with which the type of vehicle complies

refer to Appendix 3 - Page(s) 6 to 10 of inspection report N° CN-117-2-196-WHO25-26174-IR



Référence: e13*168/2013*02582*00

Annexes: - Rapport technique
- Fiche de renseignements du constructeur

Bertrange, le 03 juin 2025

Index du dossier de réception

Index to type-approval report

Numéro de réception UE par type:

EU type approval number:

e13*168/2013*02582*00

Révision:

Revision:

00

Marque de fabrique ou de commerce:

Trade name or mark:

RJTech, manufacturer's logo refer to manufacturer's

Type:

Type:

Steinadler Pro

1. Procès-verbal d'essai:

Test report:

N° CN-117-2-196-WHO25-26174-IR

- Inspection report:
- Addenda of inspection report:

Page(s) 1 to 10;
Page(s) 11 to 114.

2. Dossier du constructeur:

Report of the manufacturer:

N° Steinadler Pro-00

- List of content:
- Information folder sheet:
- Information document:
- Drawings list:
- Technical description of the vehicle type and its components:

Page(s) 1;
Page(s) 1 & 2;
Page(s) 1 to 29;
Page(s) 30;
refer to drawing list.

3. Autres documents annexés:

Other documents annexed:

not applicable

4. Date de délivrance de la réception initiale:

Date of issue of initial type approval:

03.06.2025

5. Date de la dernière délivrance de pages révisées:

Date of last issue of revised pages:

not applicable

6. Date de la dernière délivrance d'une réception révisée:

Date of last extension:

not applicable



LE GOUVERNEMENT
DU GRAND-DUCHÉ DE LUXEMBOURG
Ministère de la Mobilité
et des Travaux publics

Département de la mobilité
et des transports

SOCIÉTÉ NATIONALE DE
CERTIFICATION ET D'HOMOLOGATION
S.A.

Registre de Commerce: B 27180



L-8070 Bertrange

Référence: e13*168/2013*02582*00

Annexes: - Rapport Technique
- Fiche de Renseignements du constructeur

Bertrange, le 03 juin 2025

Annexe VIII Annex VIII

Fiche des résultats d'essais Test results sheet

refer to Appendix 3 of inspection report N° CN-117-2-196-WHO25-26174-IR

Approval and Market Surveillance of Two or Three Wheel Vehicles and Quadricycles

0. Legislation

- 0.1. Requirements according to : Reg. (EU) 168/2013 amended by Reg. (EU) 134/2014, Reg. (EU) 2019/129, Reg. (EU) 2020/1694, Reg. (EU) 2024/1252, Reg. (EU) 2024/1689, Reg. (EU) 2024/2847
Including Delegated act (EU) 3/2014 amended (EU) 2016/1824
Including Delegated act (EU) 44/2014 amended (EU) 2018/295
Including Delegated act (EU) 134/2014 amended (EU) 2023/2724
Including Delegated act (EU) 901/2014 amended (EU) 2020/239

1. General


- 1.1. Reason for Inspection Report : New approval / ~~Extension of approval / Revision of approval / Test report only / COP~~
1.1.1. Previous type approval number : Not applicable
1.2. Manufacturer's Representative(s) : Ms. Shanshan Wang
1.3. CETOC TS Representative(s) : Wang Liming
1.4. Location of test : See Appendixes
1.5. Date of test : See Appendixes

2. Manufacturer Details

- 2.1. Make :  (RJTech)
2.2. Type : Steinadler Pro
2.3. Variant/Version : 00/00
2.4. Commercial Name : Steinadler Pro (L7e)
2.5. Category : L7e-A1
2.6. Name and Address of manufacturer : Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Zone B, 528, Huilong South Rd, Rucheng Street, Rugao City,
Jiangsu Province, China

3. Conclusion

- 3.1. Final conclusion of the inspection : The above mentioned type was tested in accordance with the above mentioned legislation and was found to comply in all respects. This Inspection report relates only to the items tested.

Signature: :  
Name: : Wang Liming Marco Pagliari
Position: : Type Approval Engineer Technical Manager
Place and date: : Hangzhou, 23/04/2025 Roma, 23/04/2025

4. List of Appendixes

- Appendix 1 : Test report history
Appendix 2.1 : Vehicle specification of tested if equipped with combustion engine.
Appendix 2.2 : Vehicle specification of tested vehicle if equipped with electric motor.
Appendix 3 : Addendum to the EU type approval certificate

APPENDIX 1 - TEST REPORT HISTORY

List this report and previous reports, with extension details.

Inspection Report Number	Reason for Extension / Revision / Correction	Date of Issue
CN-117-2-196-WHO25-26174-IR	- New approval	23/04/2025

APPENDIX 2.1 – VEHICLE SPECIFICATION OF TESTED VEHICLE IF EQUIPPED WITH COMBUSTION ENGINE

1.1.	Variant/Version	:	Not applicable
1.2.	Vehicle Identification Number	:	Not applicable
1.3.	Engine Type	:	Not applicable
1.3.1.	Engine family	:	Not applicable
1.4.	Engine Capacity (cm3)	:	Not applicable
1.5.	No. of Cylinders	:	Not applicable
1.6.	Engine Layout	:	Not applicable
1.7.	Engine Cooling	:	Not applicable
1.8.	Reference Fuels	:	Not applicable
1.9.	Fuel Tank	:	Not applicable
1.10.	Canister	:	Not applicable
1.11.	Fuel Feed	:	Not applicable
1.12.	Spark Plug	:	Not applicable
1.13.	Intake System	:	Not applicable
1.14.	Exhaust System	:	Not applicable
1.14.1.	Lambda Sensor	:	Not applicable
1.14.2.	Secondary Air	:	Not applicable
1.14.3.	Catalyst	:	Not applicable
1.15.	ECU	:	Not applicable
1.16.	OBD	:	Not applicable
1.17.	Maximum Power (kW)	:	Not applicable
1.18.	Maximum Torque(Nm)	:	Not applicable
1.19.	Idle Speed	:	Not applicable
1.20.	Transmission	:	Not applicable
1.20.1.	Primary	:	Not applicable
1.20.2.	Secondary	:	Not applicable
1.20.3.	Final	:	Not applicable
1.21.	Actual mass (kg)	:	Not applicable
1.22.	Inertial Mass (kg)	:	Not applicable
1.23.	Vehicle Length	:	Not applicable
1.24.	Maximum Design Speed / Declared maximum vehicle speed (km/h)	:	Not applicable
1.25.	PMR	:	Not applicable
1.26.	$a_{Wot,ref}$	:	Not applicable
1.27.	a_{Urban}	:	Not applicable
1.28.	Reference Length (l_{Ref})	:	Not applicable
1.29.	Gear Weighting Factor (K)	:	Not applicable

1.30.	Partial Power Factor (Kp)	:	Not applicable	
1.31.	Tyre		Front Tyre	Rear Tyre
1.31.1.	Dimension	:	Not applicable	Not applicable
1.31.2.	Pressure (kPa)	:	Not applicable	Not applicable
1.31.3.	Rolling Circ. (mm)	:	Not applicable	Not applicable

APPENDIX 2.2 – VEHICLE SPECIFICATION OF TESTED VEHICLE IF EQUIPPED WITH ELECTRIC MOTOR

1.1.	Variant/Version	:	00/00
1.2.	Vehicle Identification Number	:	Prototype
1.3.	Type of propulsion	:	Pure electric
1.4.	Electric motor code	:	QS60V1500W (Each motor)
1.5.	Electric motor layout	:	Hub-motor mounted on each wheel, total four electric motors Refer to Drawing No. Steinadler Pro-05-01
1.6.	Electric motor cooling	:	Air
1.7.	ECU Electric motor control unit	:	Main controller: Make: YUNGUAN, Type: RJ-VCU-EVA20 Four sub-controller: Make: DUNEN, Type: DEMCS0604QS05L Refer to Drawing No. Steinadler Pro-06-01, Steinadler Pro-06-02
1.8.	OBD	:	OBD Stage I
1.9.	Propulsion battery	:	55Ah, Refer to Drawing No. Steinadler Pro-08-01
1.9.1.	Kind of electrochemical couple	:	Lithium battery
1.9.2.	Battery voltage	:	74.4 V
1.9.3.	Battery capacity	:	55 Ah
1.10.	Charger	:	On-board external/without
1.11.	Maximum continuous-rated power electric motor (15/30 minutes power)	:	1.5 kW at 785 min ⁻¹ (Each motor) 6.0 kW at 785 min ⁻¹ (Total)
1.12.	Maximum continuous-rated torque electric motor	:	18.3 N.m at 785 min ⁻¹ (Each motor) 73.2 N.m at 785 min ⁻¹ (Total)
1.13.	Transmission	:	Other (Hub-motor)
1.13.1.	Internal ratio / primary ratio / secondary ratio	:	Not applicable
1.13.2.	Final	:	Not applicable
1.14.	Actual mass (kg)	:	280
1.14.1.	Inertial Mass (kg)	:	280
1.15.	Maximum Design Speed / Declared maximum vehicle speed (km/h)	:	70
1.16.	Tyres		Front Tyre Rear Tyre
	Dimension	:	AT22 × 7-10 35L AT22 × 7-10 35L
1.16.1.	Pressure (kPa)	:	45 45
1.16.2.	Rolling Circ. (mm)	:	1755 1755

APPENDIX 3 - ADDENDUM TO THE EU TYPE- APPROVAL CERTIFICATE

A. ENVIRONMENTAL AND PROPULSION UNIT PERFORMANCE REQUIREMENTS (EPPR)

Nr.	Subject	Commission Delegated Regulation (EU) No Including last amendment	PASS	FAIL	N/A	COVER BY PREVIOUS EXTENSION	Inspection report / certificate Nr.	Page Nr.
A1	Tailpipe emissions after cold start	134/2014 Annex II (EU) 2023/2724	☐	☐	☒	☐	/	/
	Tailpipe emissions at (increased) idle/ free acceleration	134/2014 Annex III (EU) 2023/2724	☐	☐	☒	☐	/	/
	Durability of pollution-Control devices	134/2014 Annex VI (EU) 2023/2724	☐	☐	☒	☐	/	/
	CO ₂ emissions, fuel consumption, electric energy consumption and electric range	134/2014 Annex VII (EU) 2023/2724	☒	☐	☐	☐	CN-117-2-196-SYS25-26175-IR	11 - 22
A2	Emissions crankcase gases	134/2014 Annex IV (EU) 2023/2724	☐	☐	☒	☐	/	/
A3	Evaporative emissions	134/2014 Annex V (EU) 2023/2724	☐	☐	☒	☐	/	/
A4	OBD environmental tests	134/2014 Annex VIII (EU) 2023/2724	☐	☐	☒	☐	/	/
A5	Sound level	134/2014 Annex IX (EU) 2023/2724	☐	☐	☒	☐	/	/
A6	Procedures and technical requirements on maximum vehicle design speed, maximum torque, maximum continuous Total power and maximum peak power	134/2014 Annex X (EU) 2023/2724 UNECE R85.00	☒	☐	☐	☐	CN-117-2-196-SYS25-26176-IR	23 - 29
A7	Vehicle propulsion family definition	134/2014 Annex XI (EU) 2023/2724	☐	☐	☒	☐	/	/

B. VEHICLE FUNCTIONAL SAFETY REQUIREMENTS (VFSR)

Nr.	Subject	Commission Delegated Regulation (EU) No Including last amendment	PASS	FAIL	N/A	COVER BY PREVIOUS EXTENSION	Inspection report / certificate Nr.	Page Nr.
B1	Audible warning devices	3/2014 Annex II (EU) 2016/1824 UNECE R28.00	☒	☐	☐	☐	CN-117-2-196-SYS25-26177-IR	30
B2	Braking, including anti- lock and combined brake systems	3/2014 Annex III (EU) 2016/1824 UNECE R78.06	☒	☐	☐	☐	CN-117-2-196-SYS25-26178-IR	31 - 37
B3	Electrical safety	3/2014 Annex IV (EU) 2016/1824	☒	☐	☐	☐	CN-117-2-196-SYS25-26179-IR	38 - 42
B4	Endurance Testing of Functional Safety Critical Systems, Parts and Equipment	3/2014 Annex V (EU) 2016/1824	☒	☐	☐	☐	CN-117-2-196-SYS25-26180-IR	43
B5	Front and rear protective structures	3/2014 Annex VI (EU) 2016/1824 UNECE R26.04	☒	☐	☐	☐	CN-117-2-196-SYS25-26181-IR	44 - 46
B6	Glazing, windscreen wipers and washers, and defrosting and demisting systems	3/2014 Annex VII (EU) 2016/1824 UNECE R122.00 UNECE R43.01	☐	☐	☒	☐	/	/
B7	Driver-operated controls including identification of controls, tell-tales and indicators	3/2014 Annex VIII (EU) 2016/1824 UNECE R121.01 UNECE R39.01	☒	☐	☐	☐	CN-117-2-196-SYS25-26182-IR	47 - 49
B8	Installation of lighting and light- signalling devices, including automatic switching of lighting	3/2014 Annex IX (EU) 2016/1824	☒	☐	☐	☐	CN-117-2-196-SYS25-26183-IR	50 - 51
B9	Rearward visibility	3/2014 Annex X (EU) 2016/1824 UNECE R46.06	☒	☐	☐	☐	CN-117-2-196-SYS25-26184-IR	52

Nr.	Subject	Commission Delegated Regulation (EU) No Including last amendment	PASS	FAIL	N/A	COVER BY PREVIOUS EXTENSION	Inspection report / certificate Nr.	Page Nr.
B10	Rollover protective structure (ROPS)	3/2014 Annex XI (EU) 2016/1824	☐	☐	☒	☐	/	/
B11	Safety-belt anchorages and safety- belts	3/2014 Annex XII (EU) 2016/1824	☐	☐	☒	☐	/	/
B12	Seating positions (saddles and seats)	3/2014 Annex XIII (EU) 2016/1824	☒	☐	☐	☐	CN-117-2-196-SYS25-26185-IR	53 - 54
B13	Steer-ability, cornering properties and turn-ability	3/2014 Annex XIV (EU) 2016/1824	☒	☐	☐	☐	CN-117-2-196-SYS25-26186-IR	55
B14	Installation of tyres	3/2014 Annex XV (EU) 2016/1824 UNECE R75.00	☒	☐	☐	☐	CN-117-2-196-SYS25-26187-IR	56 - 58
B15	Vehicle maximum speed limitation plate and its location on the vehicle	3/2014 Annex XVI (EU) 2016/1824	☐	☐	☒	☐	/	/
B16	Vehicle occupant protection, including interior fittings and vehicle doors	3/2014 Annex XVII (EU) 2016/1824	☐	☐	☒	☐	/	/
B17	Maximum continuous total power and/or maximum vehicle speed limitation by design	3/2014 Annex XVIII (EU) 2016/1824	☒	☐	☐	☐	CN-117-2-196-SYS25-26189-IR	59 - 61
B18	Vehicle structure integrity	3/2014 Annex XIX (EU) 2016/1824	☒	☐	☐	☐	CN-117-2-196-SYS25-26190-IR	62

C. VEHICLE CONSTRUCTION AND GENERAL TYPE-APPROVAL REQUIREMENTS (VCR)

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

Nr.	Subject	Commission Delegated Regulation (EU) No Including last amendment	PASS	FAIL	N/A	COVER BY PREVIOUS EXTENSION	Inspection report / certificate Nr.	Page Nr.
C1	Powertrain tampering prevention (anti-tampering) measures	44/2014 Annex II (EU) 2018/295	☒	☐	☐	☐	CN-117-2-196-SYS25-26191-IR	63 - 67
C2	Arrangements for type-approval	44/2014 Annex III (EU) 2018/295	☒	☐	☐	☐	CN-117-2-196-SYS25-26192-IR	68
C3	Conformity of production (CoP)	44/2014 Annex IV (EU) 2018/295	☒	☐	☐	☐	CN-117-2-196-SYS25-26193-IR	69
C4	Coupling devices and attachments	44/2014 Annex V (EU) 2018/295	☐	☐	☒	☐	/	/
C5	Devices to prevent unauthorised use	44/2014 Annex VI (EU) 2018/295 UNECE R62.01	☒	☐	☐	☐	CN-117-2-196-SYS25-26194-IR	70 - 72
C6	Electromagnetic compatibility (EMC)	44/2014 Annex VII (EU) 2018/295 UNECE R10.06	☒	☐	☐	☐	CN-117-2-196-SYS25-26195-IR	73 - 98
C7	External projections	44/2014 Annex VIII (EU) 2018/295 UNECE R26.04	☒	☐	☐	☐	CN-117-2-196-SYS25-26196-IR	99 - 103
C8	Fuel storage	44/2014 Annex IX (EU) 2018/295	☐	☐	☒	☐	/	/
C9	Load platforms	44/2014 Annex X (EU) 2018/295	☐	☐	☒	☐	/	/
C10	Masses and dimensions	44/2014 Annex XI (EU) 2018/295	☒	☐	☐	☐	CN-117-2-196-SYS25-26197-IR	104
C11	Functional on-board diagnostics (OBD)	44/2014 Annex XII (EU) 2018/295	☒	☐	☐	☐	CN-117-2-196-SYS25-26198-IR	105 - 107
C12	Passenger handholds and footrests	44/2014 Annex XIII (EU) 2018/295	☒	☐	☐	☐	CN-117-2-196-SYS25-26199-IR	108 - 109

Nr.	Subject	Commission Delegated Regulation (EU) No Including last amendment	PASS	FAIL	N/A	COVER BY PREVIOUS EXTENSION	Inspection report / certificate Nr.	Page Nr.
C13	Registration plate space	44/2014 Annex XIV (EU) 2018/295	☒	☐	☐	☐	CN-117-2-196-SYS25-26200-IR	110 - 112
C14	Access to repair and maintenance information	44/2014 Annex XV (EU) 2018/295	☒	☐	☐	☐	CN-117-2-196-SYS25-26201-IR	113
C15	Stands	44/2014 Annex XVI (EU) 2018/295	☐	☐	☒	☐	/	/

D. VEHICLE CONSTRUCTION AND GENERAL TYPE-APPROVAL REQUIREMENTS (VCR)

Nr.	Subject	Commission Delegated Regulation (EU) No Including last amendment	PASS	FAIL	N/A	COVER BY PREVIOUS EXTENSION	Inspection report / certificate Nr.	Page Nr.
D1	Statutory plate	901/2014 Annex V (EU) 2020/239	☒	☐	☐	☐	CN-117-2-196-SYS25-26202-IR	114

APPENDIX 3 A1

~~Test Type I Requirements Tailpipe Emissions after Cold Start~~

~~Test Type II Requirements Tailpipe Emissions at (increased) Idle and Free Acceleration~~

~~Test Type V Requirements Durability of Pollution control Devices~~

Test Type VII Requirements Energy efficiency: CO₂ emissions, fuel consumption, electric energy consumption and electric range

0. Main Requirements

0.1. Requirements according to : Reg. (EU) 134/2014, Annex II, III, VI, VII
Including amendment (EU) 2023/2724

1. Witness details

1.1. Witness : Wang Liming
1.2. Location of test : Jinhua Customs Comprehensive Technical Service
Center
Huachuan & Muchangjiang, Xicheng Street, Yongkang,
Jinhua, Zhejiang, China
1.3. Date of test : 04/03/2025 - 07/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

1.6. Facility and Equipment Checks

1.6.1. Calibration certificates checked and valid,
recorded in the following table : Conform
1.6.2. All instruments are equipped with identification
label : Yes
1.6.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Dynamometer	- / J202410182157A-0054	04/11/2025
Dynamometer	- / J202403201896A-0002	28/03/2025

*Specify calibrated date + (interval) or calibration due date.

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

2. Annex II - Test results sheet

2.2.1. (A) Environmental and propulsion unit performance

2.2.1.1. Generic information on environmental performance

2.2.1.1.1. Description of propulsion, propulsion family
and drive-train of test vehicle(s) : See appendix 2-2 and manufacturer information
document
2.2.1.1.2. Environmental step of test vehicle: : Euro 4 / Euro 5 / Euro 5+
2.2.1.1.3. Description of emission test bench(es),
specifications and settings : Not applicable
2.2.1.1.4. Chassis/engine dynamometer(s)
specifications : Dynamometer 1 Type: MN400-1
Dynamometer 2 Type: MN400-2

2.2.1.1.5.	Inertia (reference) mass and running resistance settings for single/dual roll chassis dynamometer	:	Inertia = 280 kg a= 24.6 N b= 0.0242 N/(km/h) ² c= 0
2.2.1.1.6.	Comprehensive report of road test results for the determination of test bench settings, including coast down times for single/dual roll chassis dynamometer	:	Not applicable
2.2.1.1.7.	Applicable test type I driving schedule: (ECE R40 (with/without EUDC), ECE R47, WMTC stage 1, WMTC stage 2, revised WMTC)	:	WMTC stage 3 (Revised WMTC)
2.2.1.1.8.	Description gearshift prescriptions for environmental testing	:	Not applicable

2.2.1.2. Test type I: requirements: tailpipe emissions after cold start
The following items specific to test type I shall be provided

2.2.1.2.1.	Description of tested vehicle(s) (prototype(s) or series production, hardware and software levels, VIN)	:	Not applicable
2.2.1.2.2.	Any deviations by test vehicle(s) from data provided in information document, Annex I If yes, please provide list with deviations.	:	Not applicable
2.2.1.2.3.	Type-approval number if not parent vehicle:	:	Not applicable
2.2.1.2.4.	Mileage(s) of test vehicle(s)	:	Not applicable
2.2.1.2.5.	Test fuel(s) used	:	Not applicable
2.2.1.2.6.	Description of test type I measurement methods for hybrid L-category vehicles referred to in Appendix 11 to Annex II to Commission Delegated Regulation (EU) No 134/2014	:	Not applicable
2.2.1.2.7.	Description of test type I measurement methods for gas-fuelled vehicles referred to in Appendix 12 to Annex II to Commission Delegated Regulation (EU) No 134/2014	:	Not applicable
2.2.1.2.8.	Description of test type I measurement methods for vehicles equipped with a periodically regenerating system referred to in Appendix 13 to Annex II to Commission Delegated Regulation (EU) No 134/2014	:	Not applicable
2.2.1.2.9.	Information on regeneration strategy	:	
	D (number of operating cycles between 2 cycles when regenerative phases occur)	:	Not applicable
	d (number of operating cycles required for regeneration)	:	Not applicable
2.2.1.2.10.	Description of weighting of type I test results as referred to in point 6.1.1.5. of Annex II to Commission Delegated Regulation (EU) No 134/2014 including equation number and weighting factors	:	Not applicable
2.2.1.2.11.	Number of type I operating cycles between two cycles where regenerative phases occur under the conditions equivalent to type I test (Distance 'D' in Figure Ap13-1 in Appendix 13 to Annex II to Commission Delegated Regulation (EU) No 134/2014)	:	Not applicable

- 2.2.1.2.12. Description of method employed to determine the number of cycles between two cycles where regenerative phases occur : Not applicable
- 2.2.1.2.13. Parameters to determine the level of loading required before regeneration occurs (i.e. temperature, pressure etc.) : Not applicable
- 2.2.1.2.14. Description of method used to load system in the test procedure described in point 3.1. of Appendix 13 to Annex II to Commission Delegated Regulation (EU) No 134/2014 : Not applicable
- 2.2.1.2.15. Test records according to point 7 of Annex II to Commission Delegated Regulation (EU) No 134/2014 : Not applicable
- 2.2.1.2.16. Type I test results : Not applicable

Euro 5 limit

Table 5-1 Test type I results							
Test Type I Test Results (TR _{TTIx})	Test No.	CO	THC	NMHC	NOx	THC+ NOx	PM
TR TTI Measured x (i) (iv) (mg/km)	1	--	--	--	--	--	--
	2	--	--	--	--	--	--
	3	--	--	--	--	--	--
TR TTI Measured x Mean (i) (iv) (mg/km)		--	--	--	--	--	--
Ki (i) (v) (vii)		--	--	--	--	--	--
TR TTIx (i) (iv) = Ki · TR _{TTI Measured x Mean} (mg/km)		--	--	--	--	--	--
(% of L x)		--	--	--	--	--	--
Limit value L x (viii) (mg/km)		--	--	--	--	--	--

2.2.1.3. Test type II requirements: tailpipe emissions at (increased idle)/free acceleration

- 2.2.1.3.1. Details of test vehicle(s) if different from vehicle used for type I testing:
(items 2.1.2.1.1. to 2.1.2.1.4. where different) : Not applicable
- 2.2.1.3.2. Description of propulsion idling activation method in case of stop-start system: : Not applicable

Table 5-2 Test type II results							
Test	HC	CO	O ₂	CO ₂	Engine speed	Engine oil temperature	Particulate matter
	(ppm)	(% vol.)	(% vol.)	(% vol.)	(min ⁻¹)	(K)	(m ⁻¹)
PI: Low idle test							--
PI: High idle test							--
CI — Free acceleration test / Smoke opacity test results	--	--	--	--	--	--	--

2.2.1.6. Test type V requirements: durability of pollution-control devices

- | | | | |
|----------------|--|---|----------------|
| 2.2.1.6.1. | Details of test vehicle(s), its powertrain and pollution-control devices explicitly documented and listed, emission test laboratory equipment and settings, if different from data reported under items listed in Appendix 2.1 | : | Not applicable |
| 2.2.1.6.2. | Test type V carried out on | : | Not applicable |
| 2.2.1.6.3. | The test type V data outcome and the correspondent test report shall vary in relation with the chosen durability procedure set out in Article 23(3) of Regulation (EU) No 168/2013, established as follows | : | Not applicable |
| 2.2.1.6.3.1. | Test type V conducted according to Article 23(3a) (full mileage accumulation) | : | Not applicable |
| 2.2.1.6.3.1.1. | Test cycle used | : | Not applicable |
| 2.2.1.6.3.1.2. | In the case of SRC-LeCV, applicable durability test cycle vehicle group, refer to Appendix 1 to Annex V to Commission Delegated Regulation (EU) No 134/2014 | : | Not applicable |
| 2.2.1.6.3.1.3. | In the case of SRC-LeCV, amount of test type V soak procedures | : | Not applicable |
| 2.2.1.6.3.1.4. | In the case of US EPA AMA cycle, classification according to Appendix 2 to Annex V to Commission Delegated Regulation (EU) No 134/2014 | : | Not applicable |
| 2.2.1.6.3.1.5. | Mileage test vehicle(s) | : | Not applicable |
| 2.2.1.6.3.1.6. | Catalyst time-at-temperature data histogram | : | Not applicable |
| | List of maintenance and adjustments over mileage accumulation | : | Not applicable |
| 2.2.1.6.3.1.7. | The collection of test type I results (1 to n), (see 2.2.1.2.16.), the calculated slopes and offsets, and the calculated test type V results shall be entered in the table below | : | Not applicable |

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Table 5-5															
Test type V results in case of compliance with Article 23(3a) of Regulation (EU) No 168/2013															
Test Type V Test Results (TR TTVx)	Test No.	Accumulated mileage	CO		THC		NMHC		NOx		THC+NOx		PM		
		(km)	mg/km	% of Lx	mg/km	% of Lx	mg/km	% of Lx	mg/km	% of Lx	mg/km	% of Lx	mg/km	% of Lx	
TR TTVx	1														
TR TTVx	2														
TR TTVx	3														
TR TTVx	N														
Limit value L x															

2.2.1.6.3.2.	Test type V conducted according to Article 23(3b) (partial mileage accumulation)	: Not applicable
2.2.1.6.3.2.1.	Test cycle used (SRC-LeCV)	: Not applicable
2.2.1.6.3.2.2.	Applicable SRC-LeCV durability test cycle vehicle group: refer to Commission Delegated Regulation (EU) No 134/2014	: Not applicable
2.2.1.6.3.2.3.	Amount of SRC-LeCV soak procedures	: Not applicable
2.2.1.6.3.2.4.	Mileage test vehicle(s)	: Not applicable
2.2.1.6.3.2.5.	Applied stop criteria	: Not applicable
2.2.1.6.3.2.6.	List of 'golden components' complete with series, part and marking number	: Not applicable
2.2.1.6.3.2.7.	List of 'new components' complete with series, part and marking number	: Not applicable
2.2.1.6.3.2.8.	Catalyst time-at-temperature data histogram	: Not applicable
2.2.1.6.3.2.9.	List of maintenance and adjustments over mileage accumulation	: Not applicable
2.2.1.6.3.2.10	The collection of test type I results (1 to n), (see 2.2.1.2.16.), the calculated slopes and offsets, and the calculated test type V results shall be entered in the table below	: Not applicable

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Table 5-6

Test type V results in case of compliance with Article 23(3b) of Regulation (EU) No 168/2013

Test Type V Test Results (TR TTVx)	Test No.	Accumulated mileage (km)	CO		THC		NMHC		NOx		THC+NOx		PM	
			mg/km	% of Lx	mg/km	% of Lx	mg/km	% of Lx	mg/km	% of Lx	mg/km	% of Lx	mg/km	% of Lx
TR TTVx	1	100												
Slope a														
Offset b														
Final calculated TR TTVFin = a · TR TTVnx + b	N													
Limit value Lx														

2.2.1.6.3.3.	Test type V is conducted according to annex VI, paragraph 3.6 of Regulation (EU) No. 134/2014, as an alternative to points 2.2.1.6.3.1., 2.2.1.6.3.2.	: Not applicable
2.2.1.6.3.3.1.	Test cycle used Standard bench cycle (SBC).	: Not applicable
2.2.1.6.3.3.2.	BAT equation.	: Not applicable
2.2.1.6.3.3.2.1.	The vehicle has driven more than 100 accumulated kilometres after it was first started at the end of the production line.	: Not applicable
2.2.1.6.3.3.2.2.	The fuel used during the test shall be the one of the specified fuels in Appendix 2 of Annex II of Regulation (EU) No. 134/2014.	: Not applicable
2.2.1.6.3.3.2.3.	Catalyst time-at-temperature data. Catalyst temperature shall be measured during at least two full cycles of the SRC-LeCV cycle.	: Not applicable
2.2.1.6.3.3.2.4.	Catalyst temperature shall be measured at the highest temperature location in the hottest catalyst on the test vehicle. Alternatively, the temperature may be measured at another location providing that it is adjusted to represent the temperature measured at the hottest location using good engineering judgement.	: Not applicable
2.2.1.6.3.3.2.5.	Catalyst temperature shall be measured at a minimum rate of one hertz (one measurement per second).	: Not applicable
2.2.1.6.3.3.2.6.	Bench-ageing time. Bench ageing time shall be calculated using the bench ageing time (BAT) equation BAT = A (Total te)	: Not applicable
2.2.1.6.3.3.3.	SBC described in Appendix 4 of annex VI of Regulation (EU) No. 134/2014 shall be run for the period of time calculated from the BAT equation.	: Not applicable
2.2.1.6.3.3.4.	For calculating deterioration factors at least two Type 1 tests before bench ageing of the emission control hardware and at least two Type 1 tests after the bench-aged emission hardware is reinstalled have to be performed on the test vehicle.	: Not applicable

- 2.2.1.6.3.3.5. A multiplicative exhaust emission deterioration factor shall be calculated for each pollutant as follows: $D: E: F: Mi2/Mi1$
 Where
 $Mi1$ = mass emission of the pollutant in g/km after the type 1 test.
 $Mi2$ = mass emission of the pollutant i in g/km after the type test 1 of an aged vehicle. : Not applicable
- 2.2.1.6.3.3.6. At the request of a manufacturer, an additive exhaust emission deterioration can be used, the factor shall be calculated for each pollutant as follows:
 $D: E: F: = Mi2 - Mi1$: Not applicable
- 2.2.1.6.3.3.7. The emission results of the vehicle that has accumulated more than 100 km after it was first started at the end of the production line, the deterioration factors as determined using the procedure as set out in Appendix 3 to this Annex, the total emissions (calculated with the multiplication or additive equations), and the emission limit set out in Annex VI to Regulation (EU) No 168/2013 shall be entered in the table below. : Not applicable
- 2.2.1.6.3.3.8. List of 'golden components' complete with series, part and marking number. : Not applicable
- 2.2.1.6.3.4. Test type V conducted according to Article 23(3c) of Regulation (EU) No 168/2013 : Not applicable
- 2.2.1.6.3.4.1. The Test Type I results of a vehicle with a mileage of 100 km or more, (see 2.2.1.2.16.), and the applicable deterioration factors set out in Annex VII(B) to Regulation (EU) No 168/2013 shall be entered in the table below along with the calculated test type V results : Not applicable

Table 5-7													
Test type V results in case of compliance with Article 23(3c) of Regulation (EU) No 168/2013													
Test Type V Test Results (TR TTVx)	Test No.	Accumulated mileage (km)	CO mg/km % of Lx	THC mg/km % of Lx	NMHC mg/km % of Lx	NOx mg/km % of Lx	THC+NOx mg/km % of Lx	PM mg/km % of Lx					
TR TTVx	1	100	0.0%	0.0%	0.0%	0.0%	--	--	--	--	--	--	--
Deterioration Factor DF x							--	--					
Final calculated TR TTVFin= DFx · TR TTVnx			0	0	0	0	--	--					
Limit value L x			1000	100	68	60	--	--					

NOTE: This table 5-7 is also used to present test results according to annex VI, paragraph 3.6 of Regulation (EU) No. 134/2014).

2.2.1.7. Test type VI has not been assigned; consequently there are no results to be submitted

2.2.1.8. Test type VII requirements: measurement of CO₂ emissions, fuel consumption, electric energy consumption and electric range determination

2.2.1.8.1.	Details of test vehicle(s), its powertrain and pollution-control devices explicitly documented and listed, emission test laboratory equipment and settings if different from data reported under items listed in Appendix 2.1	: Not applicable
2.2.1.8.2.	Documentation added according to UNECE Regulation No 101 (OJ L 138, 26.5.2012, p. 1)	: Yes / No
2.2.1.8.3.	The vehicle manufacturer has ensured that the CO₂ emissions, fuel consumption , electric energy consumption and electric range data are provided to the buyer of the vehicle at the time of purchase of a new vehicle	: Yes
2.2.1.8.4.	A completed specimen of the test type VII result format used to inform the buyer of the new vehicle is added to the information document	: Yes
2.2.1.8.5.	Type VII test results, where applicable and for each reference fuel tested	: Not applicable

2.2.1.8.6. CO₂ emissions and fuel consumption

Table 5-8 Test Type VII result table for propulsions equipped with a combustion engine only or equipped with not-externally-chargeable (NOVC) hybrid electric propulsion			
Test Type VII Test Results (TR _{TTVII})	Test No	CO ₂ g/km	Fuel consumption (l/100km) or (kg/100 km)
TR _{TTI} Measured x	1		
	2		
	3		
TR _{TTI} Measured Mean			
Ki		1	1
TR _{TTVIIx} = Ki · TR _{TTI} Measured x Mean		0	0
CO ₂ and Fuel consumption as declared by the manufacturer			

2.2.1.8.7. Electric energy consumption and electric range

Measurement of the electric range

2.2.1.8.7.1.	If the vehicle has several driving modes which may be selected by the driver, the operator shall select that which best matches the target curve	: Conform, Driving mode D was selected
--------------	--	--

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

2.2.1.8.7.2.	The vehicle tyres shall be inflated to the pressure specified by the vehicle manufacturer when the tyres are at ambient temperature	: Conform
2.2.1.8.7.3.	The viscosity of the oils for the mechanical moving parts shall conform to the vehicle manufacturer's specification	: Conform
2.2.1.8.7.4.	The lighting, signalling and auxiliary devices shall be off, except those required for the testing and usual day-time operation of the vehicle	: Conform
2.2.1.8.7.5.	All energy storage systems for other than traction purposes (electric, hydraulic, pneumatic, etc.) shall be charged to their maximum level as specified by the manufacturer.	: Conform
2.2.1.8.7.6.	If the batteries are operated above the ambient temperature, the operator shall follow the procedure recommended by the vehicle manufacturer in order to keep the battery temperature in the normal operating range	: Not applicable
2.2.1.8.7.7.	The vehicle shall have travelled at least 300 km in the seven days before the test with the batteries installed for the test	Conform : 301 km
2.2.1.8.7.8	Climatic conditions For testing performed outdoors, the ambient temperature shall be between 278,2 K and 305,2 K (5 °C and 32 °C). The indoor testing shall be performed at a temperature of between 275,2 K and 303,2 K (2 °C and 30 °C).	: Conform
2.2.1.8.7.9.	Initial charge of the battery Charging the battery consists of the following procedure: The 'initial charge' of the battery means the first charge of the battery, on reception of the vehicle. Where several combined tests or measurements are carried out consecutively, the first charge shall be an 'initial charge' and the subsequent charges may follow the 'normal overnight charge' procedure set out in 3.2.2.4. of Appendix 3 of reg. EU 134/2014.	: Conform
2.2.1.8.7.10.	Discharge of the battery For pure electric vehicles: The procedure starts with the discharge of the battery of the vehicle while driving (on the test track, on a chassis dynamometer, etc.) at a steady speed of 70 percent $\pm$ 5 percent of the maximum design vehicle speed, which is to be determined according to the test procedure in Appendix 1 to Annex X. Discharging shall stop under any of the following conditions: (a) when the vehicle is unable to run at 65 percent of the maximum thirty minutes speed; (b) when the standard on-board instrumentation indicates that the vehicle should be stopped; (c) after 100 km.	: Conform

By means of derogation if the manufacturer can prove to the technical service to the satisfaction of the approval authority that the vehicle is physically not capable of achieving the thirty minutes speed the maximum fifteen minute speed may be used instead.

2.2.1.8.7.11.

Normal overnight charge
For a pure electric vehicle, the battery shall be charged according to the normal overnight charge procedure, as defined in point 2.4.1.2. of Appendix 2, for a period not exceeding twelve hours.

: Conform

2.2.1.8.7.12.

Application of the cycle and measurement of the range.

For pure electric vehicles:

The test sequence set out in the Appendices shall be carried out on a chassis dynamometer adjusted as described in Annex II, until the test criteria are met.

The test criteria shall be deemed as having been met when the vehicle is unable to meet the target curve up to 50 km/h, or when the standard on-board instrumentation indicates that the vehicle should be stopped.

The vehicle shall then be slowed to 5 km/h without braking by releasing the accelerator pedal, and then stopped by braking.

At speeds of over 50 km/h, when the vehicle does not reach the acceleration or speed required for the test cycle, the accelerator pedal shall remain fully depressed, or the accelerator handle shall be turned fully, until the reference curve has been reached again.

Up to three interruptions, of no more than 15 minutes in total, are permitted between test sequences.

The distance covered in km (De) is the electric range of the electric vehicle. It shall be rounded to the nearest whole number.

: 51 km

2.2.1.8.7.13.

Final test result

: See table 5-9

2.2.1.8.8.

Electric energy consumption and electric range

Method of measuring the electric energy consumption of a vehicle powered by an electric powertrain only

2.2.1.8.8.1. to
2.2.1.8.8.7

Refer from 2.2.1.8.7.1. to 2.2.1.8.7.7.

: Conform

2.2.1.8.8.8.

In order to measure its electric consumption in the type I test cycle, the test vehicle shall be classified according to the achievable maximum design vehicle speed thresholds only, set-out in point 4.3. of Annex II.

: Selected Test cycle: Revised WMTc

2.2.1.8.8.9.

All the tests are conducted at a temperature of between 293,2 K and 303,2 K (20 °C and 30 °C).

: Conform

2.2.1.8.8.10.

Initial charge of the battery Charging the battery consists of the following procedures:

: Conform



01480

- 2.2.1.8.8.10.1. Discharge of the battery
 The battery is discharged while the vehicle is driven (on the test track, on a chassis dynamometer, etc.) at a steady speed of 70 percent $\pm$ 5 percent of the maximum design vehicle speed, as determined according to the test procedure in Appendix 1 to Annex X. Discharging shall stop:
 (a) when the vehicle is unable to run at 65 percent of the maximum thirty minutes speed, or
 (b) when the standard on-board instrumentation indicates that the vehicle should be stopped, or
 (c) after 100 km.
 By means of derogation if the manufacturer can prove to the technical service to the satisfaction of the approval authority that the vehicle is physically not capable of achieving the thirty minutes speed the maximum fifteen minute speed may be used instead. : Conform (On-board instrumentation)
- 2.2.1.8.8.10.2. Application of a normal overnight charge
 The battery shall be charged according to the following procedure:
 Normal overnight charge procedure
 The charge shall be carried out:
 (a) with the on-board charger if fitted;
 (b) with an external charger recommended by the manufacturer, using the charging pattern prescribed for normal charging;
 (c) in an ambient temperature of between 293,2 K and 303,2 K (20 °C and 30 °C).
 This procedure excludes all types of special charges that could be automatically or manually initiated, e.g. equalisation or servicing charges. : Conform (external charger)
- 2.2.1.8.8.10.2.1. The end-of-charge criteria shall correspond to a charging time of 12 hours except where the standard instrumentation indicates clearly that the battery is not yet fully charged, in which case : Conform
 the maximum time is = 3* claimed battery capacity (Wh) / mains power supply (Wh) : Not applicable
- 2.2.1.8.8.11. The end of charging time t₀ (plug off) shall be reported.
 The chassis dynamometer shall be set according to the method in point 4.5.6. of Annex II.
 Starting within four hours of t₀, the applicable type I test shall be run twice on a chassis dynamometer, following which the distance covered in km (Dtest) is recorded. If the manufacturer can demonstrate to the approval authority that twice the type I test distance can physically not be attained by the vehicle, the test cycle shall be conducted once and subsequently followed by a partial second test run. The second test run may stop if the minimum state of charge of the propulsion battery is reached as referred to in Appendix 3.1.
 End of charging time t₀ (plug off):
 : 08:40, 06/03/2025, Dtest: 15.7 km

- 2.2.1.8.8.12. Charge of the battery
 The test vehicle shall be connected to the mains within 30 minutes of the second run of the applicable type I test cycle.
 The vehicle shall be charged according to the normal overnight charge procedure in point 2.2.1.8.7.10.2. : 09:19, 06/03/2025
- The energy measurement equipment, placed between the mains socket and the vehicle charger, measures the energy charge E delivered from the mains and its duration. Charging shall stop 24 hours after the end of the previous charging time (t0).
Note:
 In the event of a mains power cut, the 24 hour period may be extended in line with the duration of the cut. The validity of the charge shall be discussed between the technical services of the approval laboratory and the vehicle manufacturer to the satisfaction of the approval authority. : Conform
- 2.2.1.8.8.13. Electric energy consumption calculation
 Energy E in Wh and charging time measurements are to be recorded in the test report.
 The electric energy consumption c shall be determined using the formula: $c = E/D_{test}$ (expressed in Wh/km and rounded to the nearest whole number).
 where D_{test} is the distance covered during the test (in km). : Charge stops at $t_0 + 24h$: 07:41, 07/03/2025, E= 1450 Wh
- 2.2.1.8.8.14. Final Test result : $C = E/D_{test} = 1450/15.7 = 92$ Wh/km
- : See table 5-9

Table 5-9 Test Type VII result table for pure electric propulsion or not-externally-chargeable (NOVC) propulsions equipped with an electric motor for propulsion				
	Measured electric energy consumption**	Declared electric energy consumption	Measured electric range	Declared electric range
	(Wh/km)*	(Wh/km)	(km)*	(km)
Pure electric powertrain	92	92	51	51
NOVC hybrid electric powertrain	--	--	--	--

*Rounded to Whole Number

**Measured Electric Energy Consumption within 4 % of declared.

APPENDIX 3 – A6

Testing Procedures and Technical Requirements as Regards Propulsion Unit Performance

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 134/2014, Annex X
Including amendment (EU) 2023/2724
UNECE R85.00 Supplement 13

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 11/03/2025, 10/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested engine : Make: QSMOTOR
Type: QS60V1500W

1.6. Facility and Equipment Checks

- 1.6.1. Calibration certificates checked and valid,
recorded in the following table : Conform
1.6.2. All instruments are equipped with identification
label : Yes
1.6.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
GPS road tester	090752 / 2024F34-10-5310354001	11/06/2025
Dynamometer	20211115002 / 2SB24033183621-0004	26/04/2025
Digital barometer	09M1660 / 1SA24033183621-0045	26/04/2025
Digital temperature-hygrometer	- / 1SA24033183621-0043	26/04/2025
Anemometer	45976154 / 1SA24033183621-0046	16/04/2025
Tyre pressure gauge	- / 1SA24033183621-0048A	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

2. Test Results

2.2.1.11. Propulsion unit performance test results

- 2.2.1.11.1. Propulsion unit performance data to be
provided to measure/determine the
maximum vehicle design speed : Conform

Inspection Report Nr.: CN-117-2-196-SYS25-26176-IR
 Manufacturer: Jiangsu YINGUAN Intelligence Technology Co., Ltd.
 Type: Steinadler Pro

2.2.1.11.1.1.	Details of hardware and software of test vehicle(s), fitted components and accessories referred to in Annex X to Commission Delegated Regulation (EU) No 134/2014, Any deviations by test vehicle(s) from data provided in information document, Annex I	:	Not any deviations
	If yes, please provide list with deviations relevant for measuring the maximum vehicle design speed and gear in which it was reached	:	Not applicable
2.2.1.11.1.2.	Test mass in running order	:	173 kg (F: 96 kg, R: 77 kg)
	mass plus rider/driver	:	280 kg (F: 138 kg, R: 142 kg)
2.2.1.11.1.3.	Test fuel specifications	:	Not applicable
2.2.1.11.1.4.	Powertrain lubricant specifications	:	Not applicable
2.2.1.11.1.5.	Atmospheric pressure (kPa)	:	102.8
2.2.1.11.1.6.	Relative humidity (%)	:	61.9
2.2.1.11.1.7.	Ambient temperature (K)	:	285
2.2.1.11.1.8.	Wind speed and direction on test track (km/h)	:	Average wind speed: 2.3 m/s, East direction; gusts of < 5 m/s
2.2.1.11.1.9.	Test track condition (temperature, level of moisture etc.)	:	Track temperature 285 K
2.2.1.11.1.10.	Maximum vehicle design speed measured and gear in which it is reached	:	70 km/h and gear in which it is reached: Not applicable
2.2.1.11.1.11.	Maximum vehicle design speed	:	Not applicable
2.2.1.11.1.12.	Exemption L3e-A3 and L4e-A3 vehicles; maximum vehicle design speed declared by manufacturer	:	70 km/h
2.2.1.11.2.	Propulsion unit performance data to be provided to measure/determine the torque and power of the propulsion on the engine dynamometer	:	Conform
2.2.1.11.2.1.	Details of propulsion(s) hardware and software tested, test equipment and settings relevant for propulsion unit performance measurements on engine dynamometer tests	:	Conform
2.2.1.11.2.1.1.	List of components and part numbers/markings relevant for propulsion unit performance measurement on engine dynamometer, referred to in Annex X to Commission Delegated Regulation (EU) No 134/2014	:	Conform
2.2.1.11.2.1.2.	Test fuel	:	Not applicable
2.2.1.11.2.1.3.	Powertrain lubricant specifications	:	Not applicable
2.2.1.11.2.1.4.	Atmospheric pressure (kPa)	:	103.3
2.2.1.11.2.1.5.	Relative humidity (%)	:	34.6
2.2.1.11.2.1.6.	Ambient temperature (K)	:	294
2.2.1.11.2.1.7.	Correction factor for reference atmospheric conditions α_1	:	Not applicable

2.2.1.11.2.1.8.	Correction factor for the efficiency of the transmission α_2	:	Not applicable
2.2.1.11.2.1.9	Engine cooling temperature (K)	:	Not applicable
2.2.1.11.2.1.10.	Oil temperature at measuring point (K)	:	Not applicable
2.2.1.11.2.1.11.	Exhaust temperature (K)	:	Not applicable
2.2.1.11.2.1.12.	The manufacturer shall indicate the propulsion unit performance test results below	:	Conform
2.2.1.11.2.1.13.	Maximum permitted combustion engine/electric motor/propulsion rotation speed (min^{-1})	:	1042 min^{-1}
2.2.1.11.2.1.14.	Maximum net power combustion engine	:	Not applicable
2.2.1.11.2.1.15.	Maximum net torque combustion engine	:	Not applicable
2.2.1.11.2.1.16.	Maximum continuous-rated power electric motor	:	Declared: 1.5 kW at 785 min^{-1} (Each motor) Measured: 1.5 kW at 780 min^{-1} (Each motor)
2.2.1.11.2.1.17.	Maximum continuous-rated torque electric motor	:	Declared: 18.3 Nm at 785 min^{-1} (Each motor) Measured: 18.4 Nm at 780 min^{-1} (Each motor)
2.2.1.11.2.1.18.	Maximum current e-motor at maximum continuous-rated power	:	22 A
2.2.1.11.2.1.19.	Maximum continuous total power for propulsion(s)	:	Declared: 6.0 kW at 785 min^{-1} (Total) Measured: 6.0 kW at 780 min^{-1} (Total)
2.2.1.11.2.1.20.	Maximum continuous total torque for propulsion(s)	:	Declared: 73.2 Nm at 785 min^{-1} (Total) Declared: 73.6 Nm at 780 min^{-1} (Total)
2.2.1.11.2.1.21.	Maximum peak power for propulsion(s)	:	Declared: 14.0 kW at 870 min^{-1} (Total) Measured: 14.0 kW at 872 min^{-1} (Total)
2.2.1.11.2.1.22.	Power/mass in running order ratio	:	Not applicable
2.2.1.11.2.1.23.	Specific fuel consumption, g/kWh at maximum net power and power	:	Not applicable
2.2.1.11.2.1.24.	Propulsion unit performance sweep graphs of total power and torque vs. engine speed (1 200 rpm to propulsion speed governor rpm, step 400 rpm). Secondary variables: spark angle, A/F ratio and mass air-flow (measured or calculated)	:	Not applicable
2.2.1.11.2.1.25.	Maximum speed of vehicle and gear in which it is reached km/h) (only for subcategories: L1e, L2e, L6e, L7e-B1, L7e-C)	:	Not applicable
2.2.1.11.2.1.26.	Maximum declared vehicle speed (only for subcategories without maximum vehicle speed limitation: L3e, L4e, L5e, L7e-A and L7e-B2)	:	70 km/h and gear in which it is reached: Not applicable

Inspection Report Nr.: CN-117-2-196-SYS25-26176-IR
 Manufacturer: Jiangsu YINGUAN Intelligence Technology Co., Ltd.
 Type: Steinadler Pro

TEST RESULTS

Item	Voltage	Current	Input power	Rev.	Torque	Out power	Temp.	Motor efficiency	Time
	V	A	W	r/min	N.m	W	°C	%	S
1	74.4	22.11	1645.0	783	18.3	1500.4	27.6	91.2	16:22:46
2	74.4	21.89	1628.6	781	18.3	1496.6	28.1	91.9	16:23:46
3	74.4	22.16	1648.7	783	18.4	1508.6	28.5	91.5	16:24:46
4	74.4	21.96	1633.8	780	18.4	1502.8	29.1	92.0	16:25:46
5	74.4	22.15	1648.0	781	18.4	1504.8	29.7	91.3	16:26:46
6	74.4	22.05	1640.5	785	18.4	1512.5	30.3	92.2	16:27:46
7	74.4	22.01	1637.5	777	18.4	1497.0	30.9	91.4	16:28:46
8	74.4	21.92	1630.8	778	18.4	1499.0	31.5	91.9	16:29:46
9	74.4	21.96	1633.8	780	18.4	1502.8	32.0	92.0	16:30:46
10	74.4	22.10	1644.2	781	18.4	1504.8	32.8	91.5	16:31:46
11	74.4	21.94	1632.3	777	18.4	1497.0	33.6	91.7	16:32:46
12	74.4	21.88	1627.9	780	18.4	1502.8	34.3	92.3	16:33:46
13	74.4	22.00	1636.8	785	18.3	1504.2	34.9	91.9	16:34:46
14	74.4	21.98	1635.3	781	18.4	1504.8	35.5	92.0	16:35:46
15	74.4	21.76	1618.9	785	18.2	1496.0	36.3	92.4	16:36:46
16	74.4	21.97	1634.6	783	18.4	1508.6	36.8	92.3	16:37:46
17	74.4	21.91	1630.1	780	18.4	1502.8	37.5	92.2	16:38:46
18	74.4	22.08	1642.8	780	18.4	1502.8	38.1	91.5	16:39:46
19	74.3	21.92	1628.7	777	18.4	1497.0	38.9	91.9	16:40:46
20	74.3	21.95	1630.9	777	18.5	1505.2	39.5	92.3	16:41:46
21	74.3	22.26	1653.9	781	18.4	1504.8	40.1	91.0	16:42:46
22	74.3	22.15	1645.7	778	18.4	1499.0	40.4	91.1	16:43:46
23	74.3	22.04	1637.6	777	18.5	1505.2	41.1	91.9	16:44:46
24	74.3	22.06	1639.1	781	18.4	1504.8	41.8	91.8	16:45:46
25	74.3	22.21	1650.2	777	18.5	1505.2	42.5	91.2	16:46:46
26	74.3	22.09	1641.3	781	18.4	1504.8	43.1	91.7	16:47:46
27	74.3	21.93	1629.4	778	18.4	1499.0	43.8	92.0	16:48:46
28	74.3	22.01	1635.3	775	18.5	1501.3	44.3	91.8	16:49:46
29	74.3	21.91	1627.9	778	18.4	1499.0	45.1	92.1	16:50:46
30	74.3	22.01	1635.3	781	18.3	1496.6	45.5	91.5	16:51:46
31	74.3	22.13	1644.3	780	18.4	1502.8	46.1	91.4	16:52:46

Maximum continuous-rated power electric motor (30 min)

Maximum continuous-rated torque electric motor

Item	Voltage	Current	Input power	Rev.	Torque	Out power	Temp.	Motor efficiency	Time
	V	A	W	r/min	N.m	W	°C	%	S
1	74.4	12.5	933.0	1042	1.3	141.8	24.8	15.2	10:45:36
2	74.4	13.3	987.3	1037	1.8	195.5	24.8	19.8	10:45:38
3	74.4	17.8	1324.3	1036	2.6	282.1	24.9	21.3	10:45:39
4	74.4	29.7	2208.2	1031	5.4	583.0	24.9	26.4	10:45:41
5	74.4	31.4	2338.4	1023	10.5	1124.8	25.0	48.1	10:45:43
6	74.4	35.6	2646.4	1011	15.4	1630.3	25.1	61.6	10:45:45
7	74.4	35.6	2644.9	1009	17.1	1806.7	25.1	68.3	10:45:46
8	74.3	37.3	2774.4	998	18.9	1975.1	25.2	71.2	10:45:47
9	74.3	43.4	3221.6	984	23.2	2390.5	25.3	74.2	10:45:49
10	74.3	45.9	3412.6	979	25.4	2603.8	25.3	76.3	10:45:50
11	74.3	49.0	3637.0	972	29.8	3033.0	25.3	83.4	10:45:51
12	74.3	48.3	3587.9	958	31.4	3149.9	25.4	87.8	10:45:52
13	74.3	49.0	3637.7	946	32.5	3219.4	25.4	88.5	10:45:53
14	74.3	51.4	3819.8	933	34.8	3399.8	25.5	89.0	10:45:54
15	74.3	50.0	3712.8	908	36.2	3441.8	25.5	92.7	10:45:55
16	74.3	50.5	3752.2	872	38.3	3497.1	25.6	93.2	10:45:56
17	74.3	49.9	3703.9	852	38.9	3470.5	25.6	93.7	10:45:57
18	74.2	49.3	3659.5	821	39.5	3395.8	25.7	92.8	10:45:58
19	74.2	48.6	3606.9	798	40.1	3350.8	25.7	92.9	10:45:59
20	74.2	50.3	3729.3	762	41.6	3319.3	25.8	89.0	10:46:00
21	74.2	48.9	3631.3	727	42.5	3235.3	25.8	89.1	10:46:01
22	74.2	47.8	3545.3	684	44.2	3165.7	25.8	89.3	10:46:02
23	74.2	47.1	3493.3	643	45.5	3063.5	25.9	87.7	10:46:03
24	74.2	46.6	3455.5	607	46.7	2968.3	25.9	85.9	10:46:04
25	74.2	48.1	3566.1	588	47.9	2949.2	25.9	82.7	10:46:05
26	74.2	45.5	3374.6	510	50.8	2712.9	26.0	80.4	10:46:07
27	74.2	44.0	3262.6	478	51.5	2577.7	26.0	79.0	10:46:08
28	74.1	42.0	3112.2	407	54.4	2318.4	26.0	74.5	10:46:10
29	74.1	38.1	2826.2	332	58.2	2023.3	26.1	71.6	10:46:12
30	74.1	33.3	2468.3	242	63.5	1609.1	26.1	65.2	10:46:14
31	74.1	27.6	2045.9	175	66.2	1213.1	26.2	59.3	10:46:15

Maximum peak power for propulsion(s)

Max. Speed Test

Para.	Requirement	PASS	FAIL	N/A
2.1.	Test vehicles used for propulsion unit performance tests are representative of the vehicle type, with regard to the propulsion unit performance produced in series and placed on the market.	☒	☐	☐
2.2.1.	Test vehicles are clean and only those accessories needed to enable the vehicle to undergo the test are in operation.	☒	☐	☐
2.2.2.	Fuel supply and ignition settings, viscosity of the lubricants for the mechanical parts in motion, and the tyre pressures are as required by the manufacturer.	☒	☐	☐
2.2.3.	Engine, drivetrain and tyres of the test vehicle have been properly run-in, in accordance with the manufacturer's requirements.	☒	☐	☐
2.2.4.	Before the test, all parts of the test vehicle are in a thermally stable state, at their normal operating temperature.	☒	☐	☐
2.2.5.- 2.2.6.	Test vehicle is submitted at its mass in running order with driver	☒	☐	☐

	Declared (kg)	Measured (kg)
Front axle:	138	138
Rear axle:	142	142
Total:	280	280

Uncabbed Vehicle

3.1.1.	Driver has a mass of:			
	75 kg $\pm$ 5 kg;	☒	☐	☐
	75 kg $\pm$ 2 kg for moped.	☐	☐	☒
	Driver has a height of:			
	1.75 m $\pm$ 0.05 m;	☒	☐	☐
	1.75 m $\pm$ 0.02 m for moped.	☐	☐	☒

Cabbed Vehicle

3.2.1.	Driver has a mass of:			
	75 kg $\pm$ 5 kg;	☐	☐	☒
	75 kg $\pm$ 2 kg for moped.	☐	☐	☒
4.	Test track in accordance with paragraph 4 of delegated act.	☒	☐	☐

4.2. Configurations for the measuring base:

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

(a) Type 1;	☒	☐	☐
(b) Type 2;	☐	☐	☒
(c) Type 3.	☐	☐	☒

5. **Atmospheric conditions**

	Measured	Limits	
Atmospheric pressure:	102.8	97 ± 10	kPa
Ambient temperature:	284	278.2 ÷ 318.2	K
Relative humidity:	61.9	30 to 90	%
Average wind speed:	2.3	< 3*	m/s

*Limit: av 3 m/s 5 m/s gusts, measured 1 m above ground.

Test Results

Test 1	Left (km/h)	Right (km/h)
Trap 1	69.5	69.8
Trap 2	69.7	69.9
Trap 3	69.8	70.0

Average test result:	69.8	km/h
----------------------	------	------

Test result (rounded):	70	km/h
------------------------	----	------

Left runs all within 3 %.	☒	☐	☐
---------------------------	-------------------------------------	--------------------------	--------------------------

Right runs within 3 %.	☒	☐	☐
------------------------	-------------------------------------	--------------------------	--------------------------

Test result within 5 % of maximum declare speed.	☒	☐	☐
--	-------------------------------------	--------------------------	--------------------------

Note: The maximum declare speed is 70 km/h.

APPENDIX 3 – B1 Audible Warning Devices

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 3/2014 Annex II
Including amendment (EU) 2016/1824
UNECE R28.00 Supplement 6

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 13/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Tape	- / 1SA24033183621-0027	26/04/2025
Sound level indicator	- / 1SA24033183621-0015	26/04/2025
Sound level calibrator	1019326 / 1SA24033183621-0017	26/04/2025
Digital barometer	09M1660 / 1SA24033183621-0045	26/04/2025
Anemometer	- / 1SA24033183621-0047	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

3. Details of Horns Fitted

- 3.1. Make and Type : Make: HELLA, Type: S70
3.2. Voltage Rating : 12 V
3.3. Number Fitted : One
3.4. Approval Number : E57*28R00/06*0051*00
3.5. Position : Front, refer to drawing No. Steinadler Pro-13-01

4. Condition of test

- 4.1. Wind : 0.6 m/s (N - E)
4.2. Test area, general condition : Asphalt, Dry, Flat

5. Test results

- 5.1. Height of microphone above ground (m) : 1.03
5.2. Sound level value (dB) : 99

APPENDIX 3 – B2

Braking, including anti- lock and combined brake systems

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 3/2014 Annex III
Including amendment (EU) 2016/1824
UNECE R78.06

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 11/03/2025, 12/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
GPS road tester	090752 / 2024F34-10-5310354001	11/06/2025
Digital temperature-hygrometer	- / 1SA24033183621-0043	26/04/2025
Handbrake force measuring device	490211201 / 2SB24033183621-0012	26/04/2025
Handbrake force measuring device	490211205 / 2SB24033183621-0013	26/04/2025
Foot brake force measure device	A366295 / 2SB24033183621-0011	26/04/2025
Digital barometer	09M1660 / 1SA24033183621-0045	26/04/2025
Anemometer	- / 1SA24033183621-0047	26/04/2025
Flowmeter	20240030296 / 1GA24041889026-0001	25/04/2025
Infrared thermometer	05608309 / 1SA240711114409-0001	29/07/2025

*Specify calibrated date + (interval) or calibration due date.

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

3. Summary of test results

3.1. Applicability :

	PASS	FAIL	N/A	COVERED PREVIOUS EXTENSION	See approval/Report Nr.
Dry Stops - Single Brake Control Actuated	☒	☐	☐	☐	-
Dry Stop - All Service Brake Controls Actuated	☒	☐	☐	☐	-
High Speed Stop	☐	☐	☒	☐	-
Wet Brake Test	☒	☐	☐	☐	-
Heat Fade Test	☒	☐	☐	☐	-
Hot Brake Stops	☒	☐	☐	☐	-
Parking brake system test	☒	☐	☐	☐	-
Determination of Peak Braking Coefficient (PBC)	☐	☐	☒	☐	-
Stops on a High Friction Surface	☐	☐	☒	☐	-
Stops on a Low Friction Surface	☐	☐	☒	☐	-
Wheel lock checks on high and low friction surfaces	☐	☐	☒	☐	-
Wheel lock checks high to low friction surface transition	☐	☐	☒	☐	-
Wheel lock checks low to high friction surface transition	☐	☐	☒	☐	-
Stops With an ABS Electrical Failure	☐	☐	☒	☐	-
Partial failure test - for split service brake systems	☐	☐	☒	☐	-
Power-assisted braking system failure test	☐	☐	☒	☐	-
CBS failure test	☒	☐	☐	☐	-

4. Vehicle Details

4.0.1. Mass of the vehicle

	MRO + Rider	Laden
Front Axle (kg) :	138	150
Rear Axle (kg) :	142	160
Total (kg) :	280	310

Tyres :	Front	Rear
	AT22×7-10 35L	AT22×7-10 35L

Braking system

		Front	Rear
4.0.2.	No of discs/drums and diameters (mm)	1 disc ø180 mm on per wheel, See Drawing No. Steinadler Pro-18-01	1 disc ø180 mm on per wheel, See Drawing No. Steinadler Pro-19-01
4.0.3.	Linings (Manufacturer and material)	Manufacturer: Rui'an Yuqi Automobile and Motorcycle Parts Co., Ltd. Type&Marking: R8 Material: Metal mixtures, CaSiO ₃ Asbestos free	Manufacturer: Rui'an Yuqi Automobile and Motorcycle Parts Co., Ltd. Type&Marking: HB4F036 Material: Metal mixtures, CaSiO ₃ Asbestos free
4.0.4.	Hand or foot operated	Service brake: Foot operated on all wheels, Front secondary brake: Hand operated on front wheels (Right hand), Rear secondary brake brake: Hand operated on rear wheels (Left hand), Parking brake: Hand operated on rear wheels	
4.0.5.	Lever ratio	Pedal ratio: 10.0, Left brake lever ratio: 6.16, Right brake lever ratio: 6.16, Parking brake handle ratio: 3.17	
4.0.6.	Brake calliper	Two ø 25 mm per wheel Front brake caliper piston area per wheel: 490.6 mm ² *2 = 981.2 mm ²	One ø 30 mm per wheel Rear brake caliper piston area per wheel: 706.5 mm ²
4.0.7.	Brake pump	Service brake: Capacity: 40 cm ³ , master cylinder piston: ø15.8 mm, piston areas of cylinder: 195.97 mm ² Front secondary brake: Capacity: 20 cm ³ , master cylinder piston: ø12.7 mm, piston areas of cylinder: 126.61 mm ² Rear secondary brake: Capacity: 20 cm ³ , master cylinder piston: ø12.7 mm, piston areas of cylinder: 126.61 mm ²	
4.0.8.	Front/rear, CBS or split system	CBS: Hydraulic disc brakes effective on all wheels, operated by foot pedal on right side of vehicle. Front secondary: Hydraulic disc brakes effective on front wheels, operated by right hand lever. Rear secondary: Hydraulic disc brakes effective on rear wheels, operated by left hand lever. Parking brake: Independent of the control of the service braking device and which operates on the wheels of rear axle: disc brakes actuated by a handle to hold in the locked position by mechanical means.	
4.0.9.	Brake distribution valve	Not applicable	
4.0.10.	Power assistance	Not applicable	
4.0.11.	ABS (controlled wheels, calibration)	Not applicable	

Test Results

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

5.1. Dry stops - single brake control actuated

- | | | | |
|--------|---|---|---------|
| 5.1.1. | Performed laden, engine disconnected | : | Conform |
| 5.1.2. | Vehicles with CBS and split service brakes: also perform test lightly loaded | : | Conform |
| 5.1.3. | Initial brake temperature: $\geq 55^{\circ}\text{C}$ and $\leq 100^{\circ}\text{C}$ | : | Yes |
| 5.1.4. | Each service brake control is operated separately | : | Yes |

Loaded conditions, engine disconnected

Brake System	Nominal Speed (km/h)	Actual Speed (km/h)	Actual Distance (m)	Corrected Distance (m)	MFDD (m/s ²)	Control Force (N)
Service brake [laden]	60	59.4	/	/	5.96	101
Service brake [lightly load]	60	59.8	/	/	5.89	88
Front secondary brake [laden]	60	60.3	/	/	3.87	81
Rear secondary brake [laden]	60	61.2	/	/	4.05	104
Limits (L7): CBS					≥ 5.0	≤ 500
Limits (L7): Secondary brake					≥ 2.5	≤ 200

5.2. Dry Stop - All Service Brake Controls Actuated

- | | | | |
|--------|---|---|---------|
| 5.2.1. | Performed lightly loaded, engine disconnected | : | Conform |
| 5.2.2. | Initial brake temperature: $\geq 55^{\circ}\text{C}$ and $\leq 100^{\circ}\text{C}$ | : | Conform |
| 5.2.3. | Simultaneous actuation of both service brake controls if so equipped or the single service brake system control for a service brake that operates on all wheels | : | Conform |
| 5.2.4. | Must achieve specified performance with no more than 6 stops | : | Conform |

Brake System	Nominal Speed (km/h)	Actual Speed (km/h)	Actual Distance (m)	Corrected Distance (m)	Control Force (N)		
					Right hand	Left hand	Foot
All brakes	63	63.4	21.30	/	95	109	118
Limits (L7):				≤ 23.81	≤ 250	≤ 250	≤ 500

5.3. High Speed Stop

Not applicable

5.4. Wet Brake Test

5.4.1.	Each service brake control is tested separately	:	Conform
5.4.2.	Performed laden, engine disconnected	:	Conform
5.4.3.	Vehicles with CBS and split service brakes: also perform test lightly loaded	:	Conform
5.4.4.	Run baseline test to achieve 2.5 - 3.0 m/s ² :	:	Conform

Loaded conditions, engine disconnected

Baseline Tests	Nominal Speed (km/h)	Actual Speed (km/h)	Average Decel 0.5 - 1.0 s (m/s ²)	Highest Decel (m/s ²)	Av Control Force (N)
Service brake [Laden]	60	59.6	2.67	4.24	43
	60	59.7	2.58	3.79	41
	60	59.8	2.51	3.92	37
Average:			2.59	3.98	40

Baseline Tests	Nominal Speed (km/h)	Actual Speed (km/h)	Average Decel 0.5 - 1.0 s (m/s ²)	Highest Decel (m/s ²)	Av Control Force (N)
Service brake [Lightly loaded]	60	60.8	2.67	4.26	49
	60	60.5	2.67	3.93	48
	60	60.5	2.59	4.17	48
Average:			2.64	4.12	48

Baseline Tests	Nominal Speed (km/h)	Actual Speed (km/h)	Average Decel 0.5 - 1.0 s (m/s ²)	Highest Decel (m/s ²)	Av Control Force (N)
Front secondary brake [Laden]	60	60.3	2.57	4.16	58
	60	59.2	2.70	4.31	64
	60	60.6	2.66	4.15	61
Average:			2.64	4.21	61

Baseline Tests	Nominal Speed (km/h)	Actual Speed (km/h)	Average Decel 0.5 - 1.0 s (m/s ²)	Highest Decel (m/s ²)	Av Control Force (N)
Rear secondary brake [Laden]	60	60.0	2.69	4.00	75
	60	59.8	2.52	4.02	69
	60	59.5	2.66	3.93	70
Average:			2.62	3.98	71

- 5.4.5. Ride the vehicle with water delivery for ≥ 500 m : Conform
- 5.4.6. Make a stop using the average control force from the baseline test : Conform

Wet Tests	Nominal Speed (km/h)	Actual Speed (km/h)	Average Decel 0.5 - 1.0 s (m/s ²)	Highest Decel (m/s ²)	Av Control Force (N)
Service brake [laden]	60	60.2	1.92	3.62	38
Service brake [lightly load]	60	59.6	2.12	4.06	47
Front secondary brake [laden]	60	60.1	1.92	3.96	59
Rear secondary brake [laden]	60	59.8	2.62	3.98	71
Limits (L7): Service brake [laden]			≥ 1.55	≤ 4.78	40
Limits (L7): Service brake [lightly load]			≥ 1.58	≤ 4.94	48
Limits (L7): Front secondary brake			≥ 1.58	≤ 5.05	61
Limits (L7): Rear secondary brake			≥ 1.57	≤ 4.78	71

5.5. Heat Fade Test

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

5.5.1. Heating Procedure

- 5.5.1.1. Test Speed : Front brake only: Lower of 100km/h or 0.7 V_{max}
Rear brake only: Lower of 80 km/h or 0.7 V_{max}
CBS or split service brake: Lower of 100 km/h or 0.7 V_{max}
- 5.5.1.2. Vehicle weight and Engine status : Performed laden, engine disconnected
- 5.5.1.3. Initial brake temperature : $\geq 55^{\circ}\text{C}$ and $\leq 100^{\circ}\text{C}$
- 5.5.1.4. First stop : 3 - 3.5 m/s² between 80% and 10% of the specified speed.
- Subsequent stops : Same constant control force as the first stop. 10 stops.

5.5.2. Hot Brake Stops

- 5.5.2.1. Within 1 minute of completing the heating procedure perform one stop under the same conditions as the baseline test but with a control force of no more than that used in the actual test : Conform

Loaded conditions, engine disconnected

Brake System	Nominal Speed (km/h)	Actual Speed (km/h)	Actual Distance (m)	Corrected Distance (m)	MFDD (m/s ²)	Control Force (N)
Service brake [laden]	60	60.7	/	/	4.83	100
Limits (L7): CBS					≥ 3.58	≤ 101

5.6. ABS test requirements

Not applicable

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

5.7. Parking brake system test - for vehicles equipped with parking brakes

5.7.1.	Performed laden	:	Conform
5.7.2.	Engine disconnected	:	Conform
5.7.3.	Initial brake temperature ≤ 100°C	:	Yes
5.7.4.	Test surface gradient = 18 per cent	:	Yes

Test procedure	Control force (N)	Holds stationary for 5 minutes
Vehicle facing up hill	124	Conform
Vehicle facing down hill	122	Conform
Limits:	≤ 400N (Hand) ≤ 500N (Foot)	

5.8. Partial failure test – for split service brake systems

Not applicable

5.9. Power-assisted braking system failure test

Not applicable

5.10 CBS failure test - for CBS brake systems

5.10.1	Brake system alteration	:	Alter the brake system to produce a failure causing a complete loss of braking in the portion of the system which is shared
5.10.2	Test performance	:	Carry out the test set out in section 3., instead of the provisions in section 3.2.(c), apply only the brake control not affected by the simulated failure.
5.10.3	Vehicle weight and engine transmission	:	Performed laden, engine disconnected
5.10.4	Initial brake temperature	:	≥ 55°C and ≤ 100°C

Brake System	Nominal Speed (km/h)	Actual Speed (km/h)	Actual Distance (m)	Corrected Distance (m)	MFDD (m/s ²)	Control Force (N)
Front brake failure	60	60.4	/	/	3.95	139
Rear brake failure	60	59.5	/	/	4.17	122
Limits (L7): Front					≥ 3.3	≤ 200
Limits (L7): Rear					≥ 3.3	≤ 200

APPENDIX 3 – B3

Electrical Safety

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 3/2014 Annex IV
Including amendment (EU) 2016/1824

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

3. Facility and Equipment Checks

- 3.1. Calibration certificates checked and valid : Conform
3.2. All instruments are equipped with identification label : Yes
3.3. Calibration certificates are complete of calibration-chain with detailed information regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Test probe (IPXXB)	2021110101 / 1SA24033183621-0051	26/04/2025
Test probe (IPXXD)	2021110102 / 1SA24033183621-0052	26/04/2025
DC stabilized power supplies	020220254314 / 2SB24033183621-0009A	26/04/2025
Insulation tester	YD9820A-222950 / 1SA250319179142N-0001	20/03/2026

*Specify calibrated date + (interval) or calibration due date.

PASS FAIL N/A

General Requirements

- | | | | | |
|--------|--|-------------------------------------|--------------------------|-------------------------------------|
| 2.1. | Protection against direct contact with live parts (e.g. solid insulator, barrier, enclosure) cannot be opened, disassembled or removed without the use of tools. | ☒ | ☐ | ☐ |
| 2.1.1. | For protection of live parts inside the enclosed driving and passenger compartment, as well as luggage compartment, the protection degree IPXXD is met. | ☐ | ☐ | ☒ |
| 2.1.2. | For protection of live parts in areas other than the enclosed driving and passenger compartment, or luggage compartment, the protection degree IPXXB is met. | ☐ | ☐ | ☒ |
| 2.1.3. | For protection of live parts of vehicles where no enclosed driving and passenger compartment is present, the protection degree IPXXD is met by the entire vehicle. | ☒ | ☐ | ☐ |

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

PASS FAIL N/A

2.1.4. Connectors (including vehicle inlet) are deemed to meet the requirements if they:

- Also comply with the protection degree IPXXB, when separated without the use of tools;
 - Are located underneath the vehicle floor and are provided with a locking mechanism (e.g. screw locking, bayonet locking);
 - Are provided with a locking mechanism and other components are first removed with the use of tools in order to separate the connector*
- or
- Voltage of live parts becomes $\leq$ DC 60 V or $\leq$ AC 30 V (rms) within 1 second after the connector is separated*

☒ ☐ ☐

*Strikethrough, as appropriate.

2.1.5. In case a service disconnect can be opened, disassembled or removed without the use of tools, the protection degree IPXXB is met under all of these conditions.

☒ ☐ ☐

2.1.6.1. In the case of a REESS having high voltage capability, the symbol shown in Figure 4-1 is placed on or near the REESS. The symbol background is yellow; the bordering and the arrow are black.

☒ ☐ ☐



(Figure 4-1)

2.1.6.2. Symbol is, in addition, placed on all enclosures and barriers, which when removed, expose live parts of high voltage circuits.

☒ ☐ ☐

Note: This provision is optional for connectors for high voltage buses and does not apply to any of the following cases:

- Where barriers or enclosures cannot be physically accessed, opened, or removed, unless other vehicle components are removed with the use of tools*
- ~~Where barriers or enclosures are located underneath the vehicle floor*~~

☒ ☐ ☐

*Strikethrough, if appropriate.

2.1.6.3. Cables for high voltage buses, which are not located fully within enclosures, are identified by having an outer covering with the colour orange.

☒ ☐ ☐

2.2.1. Concerning protection against electrical shock, which could arise from indirect contact, the exposed conductive parts, such as the conductive barrier and enclosure, are securely galvanically connected to the electrical chassis; for instance, by connections with electrical wire, ground cable, welds, or by connections using bolts so that no dangerous electric potential can exist.

☒ ☐ ☐

2.2.2. Resistance between all exposed conductive parts and the electrical chassis is lower than 0.1 Ω when there is current flow of at least 0.2 A. This requirement is deemed as satisfied if the galvanic connection has been established by welding.

☒ ☐ ☐

		PASS	FAIL	N/A
2.2.3.	In the case of vehicles intended to be connected to a grounded external electric power supply through a conductive connection, a device enabling the galvanic connection of the electrical chassis to the earth ground is provided.	☒	☐	☐
2.2.3.	Device enables connection to the earth ground before external voltage is supplied to the vehicle and retains this connection until after the exterior voltage is removed from the vehicle.	☒	☐	☐
2.2.3.1.	A galvanic connection of the electrical chassis to the earth ground does not need to be provided in the following cases:			
	- Vehicle can only use a dedicated charger that is protected when any single isolation fault arises;	☐	☐	☒
	- Vehicle's whole metallic body is protected when any single isolation fault arises*	☐	☐	☒
	or			
	- Vehicle cannot be charged without completely removing the traction battery pack from the vehicle*	☐	☐	☒
	Electric Power Trains Consisting of Separate DC or AC Buses			
2.3.1.	If AC buses and DC buses are galvanically isolated from each other, isolation resistance between all high voltage buses and the electrical chassis have a minimum value of 100 Ω/V of the working voltage for DC buses and a minimum value of 500 Ω/V of the working voltage for AC buses.	☒	☐	☐
	Concerning Electric Power Train Consisting of Combined DC and AC Buses			
2.3.2.	If AC high voltage buses and DC high voltage buses are galvanically connected, isolation resistance between all high voltage buses and the electrical chassis have a minimum value of 500 Ω/V of the working voltage.	☐	☐	☒
2.3.2.	However, if all AC high voltage buses are protected by one of the two following measures, isolation resistance between the high voltage bus and the electrical chassis have a minimum value of 100 Ω/V of the working voltage:	☐	☐	☒
	Double or more layers of solid insulators, barriers or enclosures that meet the requirements of paragraphs 2.1 to 2.1.6.3 independently, for example wiring harness*			
	Mechanically robust protections that have sufficient durability over vehicle service life, such as motor housings, electronic converter cases or connectors*			

*Strikethrough, as appropriate.

		PASS	FAIL	N/A
e13*168/2013*02582*00				
Fuel Cell Vehicles Société Nationale de Certification et d'Homologation				
2.3.3.	If the minimum isolation resistance requirement cannot be maintained over time, then protection is achieved by any of the following: – Double or more layers of solid insulators, barriers or enclosures that meet the requirements of paragraphs 2.1 to 2.1.6.3 independently* – On-board isolation resistance monitoring system together with a warning to the driver if the isolation resistance drops below the minimum required value. The isolation resistance between the high voltage bus of the coupling system for charging the REESS, which is not energised besides during charging the REESS, and the electrical chassis need not be monitored* *Strikethrough, as appropriate. Isolation Resistance Requirements for the Coupling System for Charging the REESS	☐	☐	☒
2.3.4.	Vehicle inlet or the recharge cable when permanently connected to the vehicle, intended to be conductively connected to the grounded external AC power supply and the electrical circuit that is galvanically connected to the vehicle inlet/recharge cable during charging of the REESS, have an isolation resistance between the high voltage bus and the electrical chassis of $\geq 1.0 \text{ M}\Omega$ when the charger coupler is disconnected. Note: During the measurement, the traction battery may be disconnected. Test value: 2400 MΩ Protection in Case of Excessive Current	☒	☐	☐
3.1.	REESS does not overheat in case of excessive current or, if the REESS is prone to overheating due to excessive current, it is equipped with one or more protective devices, such as fuses, circuit breakers and/or main contactors. Prevention of Accumulation of Gas	☒	☐	☐
3.2.	Places for containing open type traction battery that may produce hydrogen gas is provided with a ventilation fan or a ventilation duct, or any other suitable means to prevent the accumulation of hydrogen gas. Protection against Electrolyte Spills	☐	☐	☒
3.3.	Electrolyte does not spill from the vehicle when the vehicle is tilted in any direction, leaned left or right against the ground, or even when the REESS is put upside-down.	☒	☐	☐
3.3.	In case electrolyte is spilled from the REESS or its components due to other reasons, it does not reach the driver nor any person on or around the vehicle during normal conditions of use, parked condition (also when the vehicle is parked on a slope), or any other normal functional operation. Accidental or Unintentional Detachment	☐	☐	☒
3.4.	REESS and its components are installed in the vehicle in such a way as to preclude the possibility of inadvertent or unintentional detachment, or ejection of the REESS.	☒	☐	☐

		PASS	FAIL	N/A
3.4.	REESS and its components are not ejected when the vehicle is tilted in any direction, leaned left or right against the ground, or even when the REESS is put upside-down.	☒	☐	☐
	Propulsion System Power On and Power off Procedure			
4.1.1.	At the start-up, including system power on, in order to select the active driving possible mode, at least two deliberate and distinctive actions are performed by the driver.	☒	☐	☐
4.1.2.	At least a momentary indication is given to the rider when the vehicle is switched in active driving possible mode; however, this provision does not apply under conditions where an internal combustion engine provides directly or indirectly the vehicle's propulsion power.	☒	☐	☐
4.1.3.	When leaving the vehicle, the rider is informed by a signal (e.g. optical or audible signal) if the vehicle is still in the active driving possible mode.	☒	☐	☐
4.1.4.	If the on-board REESS can be externally charged by the driver, vehicle movement by its own propulsion system is impossible as long as the connector of the external electric power supply is physically connected to the vehicle inlet.	☒	☐	☐
4.1.4.	In the case of permanently connected charge cables, the requirement above is deemed to be met when use of the charge cable obviously prevents the use of the vehicle (e.g. cable is always routed over operator controls, rider's saddle, driver's seat, handle bar or steering wheel, or the seat covering the cable storage space needs to remain in open position).	☐	☐	☒
4.1.5.	If a vehicle is equipped with a drive direction control unit (i.e. reversing device), the state of this unit is identified to the rider.	☒	☐	☐
4.1.6.	It is permitted that only one action is required to deactivate the active driving possible mode or to complete the power off procedure.	☒	☐	☐
	Indication of Reduced Power			
4.2.1.	If the electric propulsion system is equipped with a means to automatically reduce the vehicle propulsion power (e.g. powertrain malfunction operating mode), significant reductions are indicated to the rider.	☐	☐	☒
	Indication of Low Energy Content of REESS			
4.2.2.	If the state of charge in the REESS has a significant impact on vehicle driving performance (i.e. acceleration and drivability, to be evaluated by the Technical Service together with the vehicle manufacturer), a low energy content is indicated to the rider by an obvious device (e.g. a visual or audible signal). The indication used for paragraph 4.2.1 is not used for this purpose.	☒	☐	☐
	Driving Backwards			
4.3.	It is not possible to activate the vehicle reverse control function whilst the vehicle is in forward motion.	☒	☐	☐

APPENDIX 3 – B4

Endurance Testing of Functional Safety Critical Systems, Parts and Equipment

0. Main Requirements

0.1. Requirements according to : Reg. (EU) 3/2014 Annex V
Including amendment (EU) 2016/1824

1. Detail

1.1. Remarks : See manufacturer information declaration

		PASS	FAIL	N/A
<i>Ann V</i>	Vehicles and their systems, parts and equipment critical for functional safety are capable of withstanding use under normal conditions and when serviced in accordance with the manufacturer's recommendations, taking into account regular and scheduled maintenance and specific equipment adjustments, carried out as per the clear and unambiguous instructions provided by the vehicle manufacturer in the instruction manual provided with the vehicle.	☒	☐	☐
<i>Ann V</i>	Normal use of a vehicle covers five years after first registration and a total distance travelled equal to 1.5 times the distance, as specified in Annex VII to Regulation (EU) No 168/2013, in direct relation to the vehicle category in question and the emission stage (i.e. Euro level), according to which the vehicle is to be type approved; however, the required distance does not exceed 60,000 km for any vehicle category. <i>Note: Normal use does not include use under harsh conditions (e.g. extreme cold or heat) and road conditions inflicting damage to the vehicle due to its state of repair.</i>	☒	☐	☐

APPENDIX 3 – B5

Requirements applying to front and rear protective structures

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 3/2014 Annex VI
Including amendment (EU) 2016/1824
UNECE R26.04

1. Witness details

- 1.1. Witness : Wang Liming
- 1.2. Location of Test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
- 1.3. Date of Test : 01/03/2025
- 1.4. Worst Case Rationale : Single specification
- 1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
- 2.2. All instruments are equipped with
identification label : Yes
- 2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
External projection test ball	- / 1SA24033183621-0054	26/04/2026
External projection test roller	- / 2SB24033183621-0056	26/04/2026
Vernier caliper	20105008 / 2SB24033183621-0036	26/04/2025
Radius Gages	- / 1SA24033183621-0029	26/04/2025
Radius Gages	- / 1SA24033183621-0030	26/04/2025
Tyre pressure gauge	- / 1SA24033183621-0048A	26/04/2025
Tape	- / 1SA24033183621-0027	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

3. Test results

	PASS	FAIL	N/A
3.1. The requirements set out in UNECE regulation No 26 are fulfilled.	☒	☐	☐
3.2. The requirements set out in Annex VI to Regulation (EU) No 3/2014 are fulfilled.	☒	☐	☐
3.2.1. Vehicles with more than one front wheel and of which the relevant front structure has not been fully assessed in accordance with UNECE Regulation No. 26 shall meet the following requirements	☒	☐	☐
3.2.1.1. At least two thirds of the maximum width of the forward section of the vehicle, measured at the location of the front axle or in front of it, shall consist of vehicle structure forward of the transverse line which is halfway between the front axle and the foremost point of the vehicle (i.e. the relevant structure, see Figure 6-1). The location, in terms of height, of this structure is relevant only above the floor line and below 2,0 m.	☒	☐	☐

e13*168/2013*02582*00


Société Nationale de Certification et d'Homologation

PASS FAIL N/A

- 3.2.1.2. None of the vehicle structure forward of the line described in point 1.2.3.1 shall have pointed or sharp parts or projections which are directed outwards and which are likely to catch or significantly increase the severity of injuries or chance of lacerations to vulnerable road users in the event of a collision while the vehicle is being driven forward. The structure shall in any case exhibit no edges which can be contacted by a 100 mm sphere and which have a radius of curvature of less than 2,5 mm. Edges may however be blunted where their projection is less than 5,0 mm and there are no specific requirements for edges with a projection of less than 1,5 mm.

Figure 6-1


Relevant structure of the forward section of the vehicle



Note: in this example the front tyres fall within the assessment zone and the respective widths are included in the overall compliant relevant structure.

- | | | | | |
|----------|--|-------------------------------------|--------------------------|--------------------------|
| 3.2.2. | Vehicles which are equipped with a device for reversing shall meet the following requirements: | ☒ | ☐ | ☐ |
| 3.2.2.1. | At least two thirds of the width of the vehicle, as measured at the rear axle, shall consist of vehicle structure(i.e. the relevant structure, see Figure 6-2). The location, in terms of height, of this structure is relevant only above the floor line and below 2,0 m. | ☒ | ☐ | ☐ |
| 3.2.2.2. | None of the structure rearward of the rear axle shall have pointed or sharp parts or projections which are directed outwards and which are likely to catch or significantly increase the severity of injuries or chance of lacerations to vulnerable road users in the event of a collision while the vehicle is being driven rearward. The structure shall in any case exhibit no edges which can be contacted by a 100 mm sphere and which have a radius of curvature of less than 2,5 mm. Edges may however be blunted where their projection is less than 5,0 mm and there are no specific requirements for edges with a projection of less than 1,5 mm. | ☒ | ☐ | ☐ |

PASS FAIL N/A



- 3.2.3. In case of vehicles of categories L2e-U, L5e-B, L6e-BU and L7e-CU, the edges which can be contacted by a 100 mm sphere shall at least be blunted when their projection is 1,5 mm or more.



	A mm	B mm	C mm	Wf or Wr mm	$A+B+C \geq \frac{2}{3} W_f$ or $A+B+C \geq \frac{2}{3} W_r$
Front	182	460	182	918	Conform
Rear	182	500	182	894	Conform

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

APPENDIX 3 – B7

Driver-operated controls including identification of controls, tell-tales and indicators

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 3/2014 Annex VIII
Including amendment (EU) 2016/1824
UNECE R121.01 Supplement 6
UNECE R39.01 Supplement 2

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025, 03/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested sample : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Dynamometer	- / 2SB24033183621-0001A	26/04/2025
Digital temperature-hygrometer	- / 1SA24033183621-0043	26/04/2025
Digital barometer	09M1660 / 1SA24033183621-0045	26/04/2025
Tyre pressure gauge	- / 1SA24033183621-0048A	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

3. Condition of test:

- 3.1. Ambient temperature (K) : Speedometer temperature within range 23 ± 5 °C: 294 K
Note: The technical service may accept an increased temperature range of 296 ± 15 K (23 ± 15 °C) instead of the range stated in point 5.2.3 of UNECE Regulation 39 if it can be demonstrated that the speedometer equipment is not sensitive to such temperature variations.
- 3.2. Tyre fitted on a vehicle
- Front : AT22×7-10 35L
Rear : AT22×7-10 35L
- 3.3. Tyre pressure (kPa) * : F: 65, R: 65
3.5. Test area, general condition : Dry, Flat
3.6. Actual mass of vehicle : 280 kg

* Note: The cold inflation pressure specified by vehicle manufacturer shall be increased by 0.2 bar (20 kPa).

4. Speedometer Specification

4.1.	Make	:	JIANDE WUXING BICYCLE CO., LTD.
4.2.	Type	:	DZ52
4.3.	Location	:	Centre of instrument
4.4.	Legible day and night	:	Yes
4.5.	Range of speed indicated (scale)	:	0 ~ 99 km/h
4.6.	Manufacturer's quoted maximum speed	:	70 km/h
4.7.	Analogue scale/Digital display	:	Digital display
4.8.	Steps for marked speed indication	:	Not applicable
4.9.	Overall transmission ratio	:	48 pulses /1 rear wheel cycle

5. Test Results

Requirement: $0 \leq V_1 - V_2 \leq (V_2/10) + 4 \text{ km/h}$

Test no.	Indicated speed V_1	True speed V_2	$V_1 - V_2$	$(V_2/10) + 4$ km/h
	(km/h)	(km/h)	(km/h)	(km/h)
1	40.0	38.1	1.9	7.81
2	56.0	53.1	2.9	9.31
3	N/A	120.0	N/A	N/A

																					
Control fitted	Y	Y	Y	Y	N/A	Y	N/A	N/A	N/A	N/A	N/A	N/A	Y	Y	Y	N/A	N/A	N/A	N/A	N/A	N/A
Correct symbol	Y	Y	Y	Y	N/A	Y	N/A	N/A	N/A	N/A	N/A	N/A	Y	Y	Y	N/A	N/A	N/A	N/A	N/A	N/A
Visibility and clarity requirements met	Y	Y	Y	Y	N/A	Y	N/A	N/A	N/A	N/A	N/A	N/A	Y	Y	Y	N/A	N/A	N/A	N/A	N/A	N/A
Symbol on (o) or close (c) to control	C	C	C	O	N/A	C	N/A	N/A	N/A	N/A	N/A	N/A	C	C	C	N/A	N/A	N/A	N/A	N/A	N/A

Tell-tale required: Y/N/O (Optional)	Y	Y	Y	Y	N	O	N	N	N	N	N	N	O	O	Y*	Y*	N	N	N	N	Y
Tell-tale fitted	Y	Y	Y	Y	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Y	N/A	N/A	N/A	N/A	Y
Colour requirements of tell-tale	Blue	Green	Green	Green	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Green	N/A	N/A	N/A	N/A	Amber
Colour of tell-tale complies	Y	Y	Y	Y	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Y	N/A	N/A	N/A	N/A	Y
Tell-tale has correct symbol	Y	Y	Y	Y	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	Y	N/A	N/A	N/A	N/A	Y
Symbol on or close to tell-tale	O	O	O	O	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	O	N/A	N/A	N/A	N/A	O

*Can be via panel lamp, provided panel lamp cannot be turned off; brightness adjustment acceptable.

APPENDIX 3 - B8

Installation of lighting and light- signalling devices, including automatic switching of lighting

0. Main Requirements

0.1. Requirements according to : Reg. (EU) 3/2014 Annex IX
Including amendment (EU) 2016/1824

1. Witness details

1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Tape	- / 1SA24033183621-0027	26/04/2025
Bevel protractor	- / 1SA24033183621-0039	26/04/2025

*Specify ~~calibrated date + (interval)~~ or calibration due date.

Requirement	Vehicle and lamps are as specified in documentation	All lamps and reflectors securely mounted	Not likely to become obscured or misaligned	Headlamp can be easily adjusted	All pairs of lamps are symmetrically mounted	All pairs of lamps appear to be the same colour and brightness	No red light visible to the front and no white light visible to the rear
All lamps comply	Y	Y	Y	Y	Y	Y	Y

Specifications of Individual Lamps					
Requirement	Any specific mounting recommendations have been complied with	All lamps and reflectors (except head, front fog and reversing lamps) have reference axis $\pm 3^\circ$ parallel to the ground and to the longitudinal plane	All side reflectors have their reference axis $\pm 3^\circ$ perpendicular to the longitudinal median plane	All the requirements of sub-paragraphs (6.1) to (6.12) are complied with as appropriate to the motorcycle category	Dipped (passing) headlamp – possible to re-set alignment using normal screws
All lamps comply	Y	Y	Y	Y	Y

3. Test results

3.1	Lighting and light-signalling devices	:	Conform
3.2	Devices fitted	:	Conform
3.3	Grouping and electrical connections	:	Conform

Component Approval Mark Details

Main beam head lamp	WCR-DS PL MA RL
Dip beam head lamp	E4 12.5
Front position lamp	148R00
Day time running lamp(s)	149R00 30960
Front direction indicators	11 12
Rear direction indicators	E4 148R00 0723
Front fog lamps	Not applicable
Rear position lamp	MR MS LM1 E4 148R00 30676
Rear stop lamp	IB 150R00 30676
Rear registration plate lamp	
Rear reflector	
Rear fog lamp	Not applicable
Side reflectors	IA E4 0224744

APPENDIX 3 - B9 Rearward visibility

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 3/2014 Annex X
Including amendment (EU) 2016/1824
UNECE R81.00 Supplement 2

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Tape	- / 1SA24033183621-0027	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

3. Test results

- 3.1. Mirror fitted on a vehicle (approval number) : Make: XIONGXIN
Type: XX-650
Approval number: E13*81R00/02*9911*00
After checking, Rear visibility meet the all specifications
of Reg. (EU) 3/2014 Annex X Including amendment (EU)
2016/1824.
Refer to drawing No. Steinadler Pro-32-01

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

APPENDIX 3 – B12

Seating positions (saddles and seats)

0. Main Requirements

0.1. Requirements according to : Reg. (EU) 3/2014 Annex XIII
Including amendment (EU) 2016/1824

1. Witness details

1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
3-D H machine	- / 2SB240711114409-0061	24/07/2025
Tape	- / 1SA24033183621-0027	26/04/2025
Ruler	- / 1SA24033183621-0038	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

		PASS	FAIL	N/A
General Requirements				
1.1.	Vehicles are fitted with at least one seat or saddle:	☒	☐	☐
	- Two seats*			
	- One saddle*			
	<i>*Strikethrough, as appropriate.</i>			
1.1.1.	All seating positions are forward-facing.	☒	☐	☐
1.2.	Vehicles without bodywork may have saddles.	☒	☐	☐
1.3.	Vehicles of categories L2e, L5e, L6e and L7e, which are fitted with bodywork, have seats.	☐	☐	☒
1.5.	All seats have seat backs.	☐	☐	☒
1.6.1.	Spaces resembling seats, and on which a 5 th percentile adult female manikin can be seated, are regarded as seats and therefore meet all the relevant requirements of this annex.	☐	☐	☒

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

- | | | | | |
|--------|---|-------------------------------------|--------------------------|-------------------------------------|
| 1.7. | Height of the R-point of the seating position of the driver or rider is: | ☒ | ☐ | ☐ |
| | - ≥ 540 mm in the case of vehicles of categories L1e, L3e and L4e (*) * | | | |
| | - ≥ 400 mm in the case of vehicles of categories L2e, L5e, L6e and L7e (*) | | | |
| | <i>*Strikethrough, as appropriate.</i> | | | |
| 1.8. | All seats and saddles, which are fitted with safety belt anchorage points and/or safety belts, are capable of withstanding a deceleration of 10 g for 20 ms in forward direction without breakage. If fitted, locking, adjustment and displacement systems do not malfunction or release. Displacement systems fitted to seats are capable of being manually activated once, after being subjected to the deceleration. | ☐ | ☐ | ☒ |
| | For seats: | | | |
| | By submitting representative parts of the vehicle to a deceleration of 10 g in forward direction for at least 20 ms; | ☐ | ☐ | ☒ |
| | <u>or</u> | | | |
| | By performing the test in points 3.4.4 to 3.4.4.2 of Part 2 of Annex XII. | ☐ | ☐ | ☒ |
| | For saddles: | | | |
| | By exerting in the forward direction, in its centre of gravity, a force equal to 10 times the weight of the complete saddle in question. | ☐ | ☐ | ☒ |
| | Child Restraint Systems | | | |
| 2.1. | Child restraint systems complying with UNECE Regulation 44 (1) may be recommended by the vehicle manufacturers for use in vehicles of categories L2e, L5e, L6e and L7e, fitted with safety belts and/or ISOFIX. | ☐ | ☐ | ☒ |
| 2.1.1. | In this case, all relevant requirements of UNECE Regulation 16 regarding the installation of child restraint systems are met, including those regarding information provided in the vehicle's instruction manual. | ☐ | ☐ | ☒ |
| 2.2. | Child restraint systems complying with UNECE Regulation 44 may be recommended by the vehicle manufacturers for use in side-cars of vehicles of category L4e, fitted with safety belts and/or ISOFIX. | ☐ | ☐ | ☒ |
| 2.2.1. | In this case, the safety belt anchorages comply with the requirements of points 1.3 to 1.6.2 of Part 1 of Annex XII, and points 1 to 3.6.1 of Part 2 of Annex XII; however, seats in side-cars may be fitted with two-point lap belts. | ☐ | ☐ | ☒ |
| 2.2.2. | All relevant requirements of UNECE Regulation 16 regarding the installation of child restraint systems are met, including those regarding the information to be provided in the vehicle's instruction manual. | ☐ | ☐ | ☒ |

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

APPENDIX 3 – B13

Steer-ability, cornering properties and turn- ability

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 3/2014 Annex XIV
Including amendment (EU) 2016/1824

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 11/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
GPS road tester	090752 / 2024F34-10-5310354001	11/06/2025
Digital temperature-hygrometer	- / 1SA24033183621-0043	26/04/2025
Digital barometer	FYP-1 / 1SA24033183621-0045	26/04/2025
Anemometer	- / 1SA24033183621-0047	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

3. Condition of test

- 3.1. Tyre pressure (kPa) : F: 45, R: 45
3.2. Test area, general condition : Dry, Flat.
3.3. Vehicle mass : 310 kg (Laden)

4. Test results

- 4.1. Turning from straight ahead : It shall be possible to steer a vehicle from a straight
ahead direction into a spiral with a final turning circle
radius of 12 m at a speed of at least 6 km/h
4.2. Test of speed on turning circle : It is possible to keep 23 km/h on a turning circle of with
the radius 10 m
4.3. Straight test : Without unusual steering corrections by the rider or driver
and without unusual vibration in the steering system
At 0,8Vmax on the straight, no vibration or correction are
requested from the driver.
4.4. Constant turning : Conform, turning circle becomes larger
4.5. Requirements as per directive described in
this test record : Conform

APPENDIX 3 – B14 Installation of tyres

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 3/2014 Annex XV
Including amendment (EU) 2016/1824
UNECE R75.00 supplement 20
- e13*168/2013*02582*00**
Société Nationale de Certification et d'Homologation

1. Witness details

- 1.1. Witness : Wang Liming
- 1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
- 1.3. Date of test : 01/03/2025
- 1.4. Worst Case Rationale : Single specification
- 1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
- 2.2. All instruments are equipped with
identification label : Yes
- 2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Tyre pressure gauge	- / 1SA24033183621-0048A	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

3. Vehicle specifications

- 3.1. Mass of the vehicle in running order (declared) : 173 kg
- 3.2. Technically permissible maximum mass
(declared) : 310 kg
- 3.3. Front technically permissible maximum mass
(declared) : 150 kg
- 3.4. Rear technically permissible maximum mass
(declared) : 160 kg
- 3.5. Maximum designed speed : 70 km/h

4. Test Results

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

	Size	LCI	Load (kg)	Speed (rating)	Speed (km/h)	Type approval No.
Front	AT22×7-10 35L	35	121	L	120	E4-75R-0012200 Ext. 00
	--	--	--	--	--	--
	--	--	--	--	--	--
	--	--	--	--	--	--
Rear	AT22×7-10 35L	35	121	L	120	E4-75R-0012200 Ext. 00
	--	--	--	--	--	--
	--	--	--	--	--	--
	--	--	--	--	--	--
Spare	--	--	--	--	--	--

*All tyres fitted to vehicles, including any spare tyre, are type approved according to UNECE Regulation 75, as referred to in paragraph 1.1 to Regulation 3/2014/EU.

**Where a vehicle is designed for conditions of use that are incompatible with the characteristics of tyres type approved according to UNECE Regulation 75 and is therefore necessary to fit tyres with different characteristics, the requirements of paragraph 1.1 do not apply, provided that the following conditions are met:

- The tyres are type approved according to Council Directive 92/23/EEC (1), Regulation (EC) No 661/2009 of the European Parliament and of the Council (2), or UNECE Regulation No 106;
- Approval authority and technical service are satisfied that the tyres fitted are suitable for the operating conditions of the vehicle. The nature of the exemption and reasons for acceptance are clearly stated in the test report.

		PASS	FAIL	N/A
General Requirements				
1.1.	All tyres fitted to vehicles, including any spare tyre, are type-approved according to UNECE Regulation 75.	☒	☐	☐
1.1.2.	Vehicles of categories L1e, L2e and L6e with a technically permissible maximum mass ≤ 150 kg may be fitted with non-type approved tyres, with a section width ≤ 67 mm.	☐	☐	☒
2.1.	All tyres normally fitted to the same axle, except those on side-cars of L4e category vehicles, are of the same type.	☒	☐	☐
2.2.	The vehicle manufacturer may restrict the category of use of original and replacement tyres that may be installed on the vehicle. In this case, the categories of use of tyres that may be fitted to the vehicle shall be clearly stated in the vehicle's instruction manual	☐	☐	☒
2.3.	The space in which each wheel revolves shall be such as to allow unrestricted movement when using the maximum permissible size of tyres and rim widths, taking into account the minimum and maximum wheel off-sets if applicable, within the minimum and maximum suspension and steering constraints as declared by the vehicle manufacturer.	☒	☐	☐
2.3.1.	All tyres that may be fitted to the vehicle in accordance with point 2.2. shall be taken into account for the determination of the permissible overall dimensions (i.e. the maximum envelope) of the relevant tyre, as applicable in the Union legislation at the time of type-approval testing of the vehicle. For this purpose, either the specifications as provided for in Annex 5 of UNECE Regulation No 75 or the permitted percentages as provided for sizes not included in that Annex shall be taken into account (e.g. overall width of multiservice tyres (MST) + 25 %, normal and snow service tyres + 10 % in case of rim diameter code 13 and above and + 8 % in case of rim diameter codes up to 12 inclusive).	☐	☐	☒
2.3.2.	the vehicle manufacturer shall take into account both the permitted categories of use as well as the speed category that is compatible with the maximum design vehicle speed, for the determination of the permitted tolerance laid down in point 4.1. of Annex 9 to UNECE regulation No 75 (i.e. $H_{dyn} = H \times 1,10$ up to $H_{dyn} = H \times 1,18$). More stringent categories may be taken into account at the discretion of the vehicle manufacturer.	☐	☐	☒

		PASS	FAIL	N/A
2.4.	The technical service may agree to an alternative test procedure (e.g. virtual testing) to verify that the requirements of point 2.3. to 2.3.2. are met, provided that the clearance between the tyre's maximum envelope and vehicle structure exceeds 10 mm at all points.;	☐	☐	☒
3.1.	Maximum load rating of each tyre with which the vehicle is fitted is at least equal to the following:			
	Maximum permissible mass on the axle where the axle is equipped with one tyre only;	☐	☐	☒
	Half of the maximum permissible mass on the axle where the axle is equipped with 2 tyres in single formation;	☒	☐	☐
	0.54 times the maximum permissible mass on the axle where the axle is equipped with 2 tyres in dual (twin) formation;	☐	☐	☒
	0.27 times the maximum permissible mass on the axle where the axle is equipped with 2 sets of tyres in dual (twin) formation;	☐	☐	☒
	With reference to the maximum permissible mass on each axle, as declared by the vehicle manufacturer.	☒	☐	☐

APPENDIX 3 – B17

Maximum continuous total power and/or maximum vehicle speed limitation by design

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 3/2014 Annex XVIII
Including amendment (EU) 2016/1824

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid : Not applicable
2.2. All instruments are equipped with
identification label : Not applicable
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Not applicable

Equipment	Serial / Certificate No.	Calibration due*
--	--	--

*Specify calibrated date + (interval) or calibration due date.

		PASS	FAIL	N/A
1.1.2.01. 1.2.1.	For vehicles with positive ignition engines propelling the vehicle either directly or through a mechanical or hydraulic transmission, maximum vehicle speed and/or maximum power is limited by adjusting two or more of the following: Properties, timing or presence of the spark igniting the fuel/air mixture in the cylinder(s)* Amount of air intake of the engine* Amount of fuel intake of the engine* Electronically and/or mechanically controlled output rotation speed of the drive-train, such as clutch, gearbox or final drive*	☐	☐	☒
1.1.2.1.1.	Adjustment of the spark properties, including timing and/or presence, in order to limit the maximum design vehicle speed and/or maximum power shall be allowed for (sub)categories L3e-A2 (only if maximum net power ≥ 20 kW), L3e-A3, L4e-A, L5e, L6eB and L7eC. It may also be allowed for other (sub)categories provided that the adjustment concept does not negatively affect emission of gaseous pollutants, CO ₂ emissions and fuel consumption while at maximum design vehicle speed and/or maximum power conditions which shall be verified by the technical service.';	☐	☐	☒

		PASS	FAIL	N/A
1.1.2.2.	For vehicles with compression ignition engines propelling the vehicle either directly or through a mechanical or hydraulic transmission, maximum vehicle speed and/or maximum power is limited by adjusting two or more of the following: — Amount of air intake of the engine* — Amount of fuel intake of the engine* — Electronically and/or mechanically controlled output rotation speed of the drive-train, such as clutch, gearbox or final drive*	☐	☐	☒
1.1.2.3.	For vehicles that are propelled by means of one or more electric motors, including pure and hybrid electric vehicles, maximum vehicle speed and/or maximum power are limited by means of two or more of the following: - Reduction of the maximum power output of one or more electric motors, based on the vehicle or rotation speed, as sensed internally to the electric motor* - Reduction of the maximum power output of one or more electric motors, based on the actual vehicle speed, as sensed fully externally to the electric motor* - Physical vehicle speed limitation by means of internal or external components, such as a maximum achievable revolution speed of an electric motor*	☒	☐	☐
1.1.2.4.	For vehicles that are propelled by means other than those listed above, the maximum vehicle speed and/or maximum power is limited by two or more separate means, which are, as far as possible, based on the above mentioned adjustment, reduction or physical speed limitation principles.	☐	☐	☒
1.1.2.5.	At least two of the limitation methods used, as referred to in points 1.1.2.1 to 1.1.2.4., shall operate independently of each other, be different in nature and have different design philosophies, although they may apply similar elements (e.g. both methods based on the notion of rotation speed as a criterion, but one measured inside a motor and the other in the drive-train's transmission). Failure of one method to work as intended (e.g. due to tampering) shall not impair the limitation function of other methods. In this case, the maximum power and/or vehicle speed which can be attained may be lower than under normal conditions. Without prejudice to the conformity of production tolerance set 15.10.2016 L 279/10 Official Journal of the European Union EN out in point 4.1.4. of Annex IV to Regulation (EU) No 44/2014, the maximum power and/or vehicle speed may not be higher than demonstrated at type-approval, if one out of the two redundant limitation methods is eliminated.	☒	☐	☐
1.1.2.6.	The vehicle manufacturer shall be allowed to make use of limitation methods other than those listed in points 1.1.2.1 to 1.1.2.4. if the manufacturer can prove to the technical service and to the satisfaction of the type approval authority that those alternative limitation methods meet the principles of redundancy set out in point 1.1.2.5. and provided that at least one of the parameters listed in points 1.1.2.1., 1.1.2.2. or 1.1.2.3.	☐	☐	☒
1.1.2.7.	The manufacturer shall be allowed to combine two or more of the individual limitation methods referred to in points 1.1.2.1 to 1.1.2.4. as part of a limitation strategy.	☐	☐	☒
1.1.2.8.	Individual limitation methods or combinations of the limitation methods referred to in points 1.1.2.1 to 1.1.2.4. may be applied more than once provided that their multiple uses operate independently of each other	☒	☐	☐
1.1.2.9.	A limitation strategy that in case of failure includes the activation of a special operating mode with substantially reduced maximum vehicle speed and/or maximum power not suitable for normal operation or that activates an ignition interlock preventing the engine from running for as long as the failure remains, shall be regarded as one limitation method	☐	☐	☒

Via della Bufalotta, 374,
00139 Roma

This inspection report shall not be reproduced except in full, without written
approval of the technical service.

		PASS	FAIL	N/A
1.1.3.	Maximum vehicle speed or power is not limited by means of a mechanical throttle stop or any other mechanical stop that limits the opening of a throttle to restrict the engine's air intake.	☐	☐	☒
1.1.4.	The provision and use of any other means enabling the vehicle operator to directly or indirectly adjust, set, select or alter the maximum propulsion unit performance determined on the basis of the information submitted in accordance with Annex I, Part B, point 2.8., items 1.8.2. to 1.8.9. of Regulation (EU) No 901/2014 resulting in exceedance is prohibited	☒	☐	☐
2.1.	The vehicle manufacturer shall demonstrate compliance with the specific requirements of points 1.1 to 1.1.2.9 by proving that two or more of the methods implemented, by integrating specific devices and/or functions in the vehicle propulsion system, ensure the required maximum continuous rated or net power and/or maximum vehicle speed limitation and that each method does so in a fully independent manner	☒	☐	☐

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

APPENDIX 3 – B18

Vehicle structure integrity

0. Main Requirements

0.1. Requirements according to : Reg. (EU) 3/2014 Annex XIX
including amendment (EU) 2016/1824

1. Witness details

1.1. Witness : Not applicable
1.2. Date of test : Not applicable

2. Test Results

	PASS	FAIL	N/A
2.1. The manufacturer's statement on vehicle structure integrity as referred to in Article 22(5) of Regulation (EU) No. 168/2013 and set out in Annex II to Regulation (EU) No 901/2014 is provided.	☒	☐	☐
2.2. Enhanced functional safety requirements on vehicle structure integrity of Annex VIII to Regulation (EU) No 168/2013 are fulfilled.	☒	☐	☐

APPENDIX 3 – C1

Powertrain tampering prevention (anti-tampering) measures

0. Main Requirements

0.1. Requirements according to : Reg. (EU) 44/2014 Annex II
Including amendment (EU) 2018/295

1. Witness details

1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

2.1. Calibration certificates checked and valid, recorded in the following table : Not applicable
2.2. All instruments are equipped with identification label : Not applicable
2.3. Calibration certificates are complete of calibration-chain with detailed information regarding primary used. : Not applicable

Equipment	Serial / Certificate No.	Calibration due*
--	--	--

*Specify calibrated date + (interval) or calibration due date.

		PASS	FAIL	N/A						
2.3.1.	Interchangeability of the following parts, in an individual or combined way, does not result in an increase of the propulsion unit performance exceeding the values measured and reported at type approval, meaning that in any case the maximum design vehicle speed and/or the maximum continuous rated and/or net engine power of the relevant category remains within the conformity of production boundaries set out in paragraph 4.1.4 of Annex IV.	☐	☐	☒						
2.4.	In no case may the approved maximum design vehicle speed, and/or the maximum continuous rated and/or net engine power of the relevant (sub)-category set out in Annex I to Regulation (EU) No 168/2013, be exceeded.	☒	☐	☐						
2.5.	In the case of chains or cogged belts, the number of teeth is displayed on the pinions.	☐	☐	☒						
	<table><tr><td></td><td>Number of teeth</td></tr><tr><td>Chains:</td><td>--</td></tr><tr><td>Cogged belts:</td><td>--</td></tr></table>		Number of teeth	Chains:	--	Cogged belts:	--			
	Number of teeth									
Chains:	--									
Cogged belts:	--									
2.7.	If the ignition timing is adjustable, the propulsion unit performance is measured with the ignition advance set within $\pm 5^\circ$ of the value at which the maximum engine power is achieved.	☐	☐	☒						

		PASS	FAIL	N/A
Specific Requirements for (Sub)-category L1e, L2e and L6e Vehicles				
3.1.	Acceptable tolerance for maximum vehicle speed and/or power limitation of category L1e, L2e and L6e vehicles is $\pm 5\%$ of the maximum design vehicle speed and/or net, and/or continuous rated power classification criteria referred to in Annex I to Regulation (EU) No 168/2013.	☐	☐	☒
Requirements for Category L1e, L2e and L6e Vehicles Equipped with a Combustion Engine				
3.2.1.1.	Each intake pipe is fixed with shear-bolts or bolts removable only using special tools. A restricted section, indicated on the outside, is located inside the pipes; at that point, the wall is less than 4 mm in thickness, or 5 mm if composed of a flexible material, such as rubber.	☐	☐	☒
3.2.1.2.	Any interference with the pipes aimed at modifying the restricted section leads to either the destruction of the pipes, or complete and permanent malfunctioning of the engine until they are restored to their approved condition.	☐	☐	☒
3.2.1.3.	A marking with indication of the vehicle (sub-) category as defined in Articles 2 and 4 of, and Annex I to, Regulation (EU) No 168/2013 shall be legible on the pipes	☐	☐	☒
3.2.2.1.	If an engine is equipped with (a) reed valve(s), it (they) are fixed with shear-bolts, which prevent re-use of its support, or bolts removable only using special tools.	☐	☐	☒
3.2.2.2.	After mounting, the maximum thickness of a cylinder-head gasket, if any, does not exceed 1.3 mm.	☐	☐	☒
3.2.2.3.	For two-stroke engines, the piston, when in position at top dead centre, does not cover the inlet port. <i>Note: This requirement does not apply to those parts of the transfer/scavenging port that coincide with the inlet port in the case of vehicles, the engine of which is equipped with an induction system incorporating reed valve(s).</i>	☐	☐	☒
3.2.2.4.	For two-stroke engines, rotation of the piston through 180° does not increase engine performance.	☐	☐	☒
3.2.2.5.	For two-stroke engines, the maximum thickness of any gasket between the base of the cylinder and the crankcase, if any, may not exceed 0,5 mm, after mounting.	☐	☐	☒
3.2.3.1.	No artificial restriction is permitted in the exhaust system. <i>Note: Valve guides of a four-stroke engine are not to be considered artificial restrictions.</i>	☐	☐	☒
3.2.3.2.	Removing the resonator tube, if installed, does not result in an increase in propulsion unit performance.	☐	☐	☒
3.2.3.3.	Part(s) of the exhaust system inside the silencer(s) that determine(s) the effective length of the exhaust pipe are affixed to the silencer(s) or expansion box(es) in such a way that it (they) cannot be removed.	☐	☐	☒
Continuous Variable Transmission (CVT)				
3.3.1.	CVT Transmission covers, if available, shall be fixed by means of at a minimum 2 shear bolts or be disassembled only by using special tools	☐	☐	☒

		PASS	FAIL	N/A
3.3.2.	The CVT mechanism intended to limit the drive ratio by limitation of the effective distance between two discs shall be fully integrated in one or both discs in such a way that it is impossible to modify the effective distance beyond a limit that would result in an increase of the maximum vehicle speed of more than 10 % of this maximum permissible vehicle speed without destroying the disc system. If the manufacturer employs interchangeable spacer rings in the CVT to adjust the maximum vehicle speed, the complete removal of these rings shall not increase the maximum vehicle speed with more than 10 %.	☐	☐	☒
Specific Requirements for (Sub)-categories L3e-A1 and L4e-A1				
4.1.	Subcategory L3e-A1 and L4e-A1 vehicles shall comply with the requirements of either points 4.2. to 4.2.3., or points 4.3., 4.3.1. and 4.3.2., or points 4.4., 4.4.1. and 4.4.2., and with points 4.5., 4.6. and 4.7. In addition, they shall comply the requirements of points 3.2.2.1., 3.2.2.3., 3.2.2.4., 3.2.2.5., 3.2.3.1. and 3.2.3.3.	☐	☐	☒
4.2.	An irremovable sleeve must be located in the inlet conduit. If such a sleeve is located in the intake pipe, the latter shall be fixed to the engine block by means of shear-bolts or bolts removable only using special tools	☐	☐	☒
4.2.1.	Sleeve has a minimum hardness of 60 HRC. In the restricted section, it does not exceed 4 mm in thickness.	☐	☐	☒
4.2.2.	Any interference with the sleeve aimed at removing or modifying it leads to either the destruction of the sleeve and its support, or complete and permanent malfunctioning of the engine until it is restored to its approved condition.	☐	☐	☒
4.2.3.	Marking with indication of the vehicle category or categories is:	☐	☐	☒
	— Legible on the surface of the sleeve*			
	— Not far from it*			
	<i>*Strikethrough, as appropriate.</i>			
4.2.5.	Each intake pipe is fixed with shear-bolts or bolts removable only using special tools. A restricted section, indicated on the outside, is located inside the pipes; at that point, the wall is:	☐	☐	☒
	— < 4 mm in thickness*			
	— 5 mm, if composed of a flexible material, such as rubber*			
	<i>*Strikethrough, as appropriate.</i>			
4.2.6.	Any interference with the pipes aimed at modifying the restricted section leads to either the destruction of the pipes or complete and permanent malfunctioning of the engine until they are restored to their approved condition.	☐	☐	☒
4.2.7.	Marking with indication of the vehicle (sub)-category, as defined in Articles 2 and 4 of Annex I to Regulation (EU) No 168/2013, is legible on the pipes.	☐	☐	☒
4.2.8.	Part of the inlet conduit located in the cylinder head has a restricted section. In the whole inlet passage, there is not a more restricted section (except the valve-seat section).	☐	☐	☒
4.2.9.	Any interference with the conduit aimed at modifying the restricted section leads to either the destruction of the pipe, or complete and permanent malfunctioning of the engine until it is restored to its approved condition.	☐	☐	☒
4.2.10.	Marking with indication of the vehicle category, as referred to in Article 39 of Regulation (EU) No 168/2013, is legible on the cylinder head.	☐	☐	☒
4.2.11.	Diameter of the restricted sections referred to in paragraph 4.2 may vary according to the (sub)-category vehicle concerned.	☐	☐	☒

		PASS	FAIL	N/A
4.3.	Each intake pipe shall be fixed with shear-bolts or bolts removable only using special tools. A restricted section, indicated on the outside, shall be located inside the pipes; at that point the wall shall be less than 4 mm in thickness, or 5 mm if composed of a flexible material such as rubber	☐	☐	☒
4.3.1.	Any interference with the pipes aimed at modifying the restricted section shall lead to either the destruction of the pipes or complete and permanent malfunctioning of the engine until they are restored to their approved condition.	☐	☐	☒
4.3.2.	A marking with indication of the vehicle (sub-) category as defined in Articles 2 and 4 of, and Annex I to, Regulation (EU) No 168/2013 shall be legible on the pipes	☐	☐	☒
4.4.	The part of the inlet conduit located in the cylinder head shall have a restricted section. In the whole inlet passage, there shall not be a more restricted section (except the valve-seat section).	☐	☐	☒
4.4.1.	Any interference with the conduit aimed at modifying the restricted section shall lead to either the destruction of the pipe or complete and permanent malfunctioning of the engine until it is restored to its approved condition	☐	☐	☒
4.4.2.	A marking with indication of the vehicle category as defined in Articles 2 and 4 of, and Annex I to, Regulation (EU) No 168/2013 shall be legible on the cylinder head.	☐	☐	☒
4.5.	The diameter of the restricted sections referred to in point 4.2. may vary according to the (sub-) category vehicle concerned.	☐	☐	☒
4.6.	The manufacturer shall supply the diameter(s) of the restricted section(s) and demonstrate to the approval authority and technical service that this restricted section is the most critical for the passage of gases, and that there is no other section which, if modified, could increase propulsion unit performance.	☐	☐	☒
4.7.	After mounting, the maximum thickness of a cylinder-head gasket shall not exceed 1,6 mm	☐	☐	☒
Additional Specific Requirements for Other (Sub)-categories of Vehicle within the Scope of Point 1.3				
5.1.	Any variant or version under the same type of vehicle of subcategory L3e-A2 or of subcategory L4e-A2 complying with the conversion requirements set out in point 4 of Annex III, shall not be derived from a L3e-A3 or L4e-A3 type, variant or version with a maximum net engine power and/or maximum continuous rated power more than twice the values set out in the classification of subcategories L3e-A2 or L4e-A2 in Annex I to Regulation (EU) No 168/2013 (e.g. 70 kW to 35 kW or lower, 50 kW to 35 kW or lower).';	☐	☐	☒
5.2.	The manufacturer shall declare that modifications and interchangeability of the characteristics and components listed below shall not lead to: - for vehicles of subcategory L3e-A2 and L4e-A2, exceeding the double of the net engine power or maximum continuous rated power - for vehicles of category L7e, exceeding the approved propulsion unit performance; *Strikethrough, as appropriate.	☒	☐	☐
5.2.1.	Spark delivery of the ignition system, if applicable;	☐	☐	☒
5.2.3.	Fuel feed and delivery system;	☐	☐	☒
5.2.4.	Air intake system including air filter(s) (modification or removal);	☐	☐	☒
5.2.5.	The drive train;	☐	☐	☒

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

PASS FAIL N/A

5.2.6	The control unit(s) that control(s) the propulsion unit performance of the powertrain;	☐	☐	☒
5.2.7	Removal of any component (mechanical, electrical, structural, etc.) which limits full engine load leading to any change in the propulsion unit performance approved in accordance with Annex II (A) to Regulation (EU) No 168/2013.	☒	☐	☐
Additional requirements for (sub) categories L1e, L2e, L3e-A1, L4e-A1 and L6e				
6.2.	The marking referred to in point 6.1. shall in principle be visible without dismantling the part in question or other parts of the vehicle. Where the bodywork or other parts of the vehicle obscure a marking, the vehicle manufacturer shall provide the competent authorities with indications for opening or dismantling the parts in question and the location of the marking	☐	☐	☒
6.3.	The characters, figures or symbols used shall be at least 2,5 mm in height and be easily legible	☐	☐	☒
6.4.	The parts, equipment and components must be marked are the following, for all (sub) categories	☐	☐	☒
6.4.1.	any electrical/electronic device for the purpose of combustion engine or electric propulsion motor management (ECU ignition module, injectors, intake air temperature etc.),	☐	☐	☒
6.4.2.	carburettor or equivalent device,	☐	☐	☒
6.4.3.	catalytic converter(s) (only if not integrated in the silencer),	☐	☐	☒
6.4.4.	crankcase,	☐	☐	☒
6.4.5.	cylinder	☐	☐	☒
6.4.6.	cylinder head,	☐	☐	☒
6.4.7.	exhaust pipe(s) (if separate from the silencer),	☐	☐	☒
6.4.8.	inlet pipe (if cast separately from the carburettor or cylinder or crankcase),	☐	☐	☒
6.4.9.	intake silencer (air filter),	☐	☐	☒
6.4.10.	restricted section (sleeve or other),	☐	☐	☒
6.4.11.	noise abatement device (silencer(s)),	☐	☐	☒
6.4.12.	transmission driven part (rear chain wheel (sprocket) or pulley),	☐	☐	☒
6.4.13.	transmission driving part (front chain wheel (sprocket) or pulley).	☐	☐	☒
6.5.	For categories L1e, L2e, and L6e	☐	☐	☒
6.5.1.	transmission CVT,	☐	☐	☒
6.5.2.	transmission controller	☐	☐	☒

APPENDIX 3 – C2 Arrangements for type-approval procedures

0. Main Requirements

0.1. Requirements according to : Reg. (EU) 44/2014 Annex III
Including amendment (EU) 2018/295

1. Witness details

1.1. Witness : Not applicable

1.2. Date of test : Not applicable

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

2. Results

	PASS	FAIL	N/A
2.1. Type-approval process			
Single-step type-approval is chosen by manufacturer	☒	☐	☐
Step-by-step type-approval is chosen by manufacturer	☐	☐	☒
Mixed step type-approval is chosen by manufacturer	☐	☐	☒
2.2. Combination of technical specifications			
The number of vehicles to be submitted is sufficient to permit the proper check of the various combinations to be type-approved according to the vehicle criteria.	☒	☐	☐
2.3. Specific provisions	☐	☐	☒
2.4. Provisions regarding conversion of subcategories (L3e/L4e)-A2 and (L3e/L4e)-A3 motorcycles	☐	☐	☒
2.5. Procedures to be followed during multi-stage EU type-approval	☐	☐	☒
2.6. Specific conditions required of virtual testing methods and regulatory acts for which virtual and/or self-testing methods may be used by a manufacturer or a technical service	☐	☐	☒

APPENDIX 3 – C3

Conformity of production

0. Main Requirements

0.1. Requirements according to : Reg. (EU) 44/2014 Annex IV
Including amendment (EU) 2018/295

1. Witness details

1.1. Witness : Not applicable
1.2. Date of test : Not applicable

2. Test Results

		PASS	FAIL	N/A
2.1.	Initial assessment			
	The manufacturer's certification complies with the international ISO 9001:2015.	☒	☐	☐
	The requirements of point 1 of Annex IV to Regulation (EU) No 44/2014 are fulfilled.	☒	☐	☐
2.2.	Product conformity arrangements			
	Existence of procedures for effective control of the conformity of product.	☒	☐	☐
	The requirements of point 2 of Annex IV to Regulation (EU) No 44/2014 are fulfilled.	☒	☐	☐

APPENDIX 3 – C5

Devices to prevent unauthorised use

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 44/2014 Annex VI
Including amendment (EU) 2018/295
UNECE R62.01

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Torque wrench	YD10160118/1SA24033183621-0024	26/04/2025
Torque wrench	WAP010140/1SA24033183621-0025	26/04/2025
Bevel protractor	- / 1SA24033183621-0039	26/04/2025
Digital angle ruler	-1SA24033183621-0035	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

Vehicles of categories L1e with a mass in running order > 35 kg and L2e to L7e, which are fitted with handlebars:
UNECE R62.01

Test Results

PASS FAIL N/A

- 2.3. Type number of device (1, 2, 3 or 4): ☒ ☐ ☐
- Type 1: Solely and positively operated on the steering alone*
 - ~~Type 2: Positively operated on the steering in conjunction with the device, which de-activates the engine*~~
 - ~~Type 3: Pre-loaded, operating on the steering in conjunction with the device, which deactivates the engine*~~
 - ~~Type 4: Positively operated on the transmission*~~

*Strikethrough, as appropriate.

Test Results		PASS	FAIL	N/A
5.1.	Protective device is so designed that:			
5.1.1.	It is necessary to put it out of action in order to enable the vehicle to be steered, or to be driven or moved forward in a straight line	☒	☐	☐
5.1.2.	In the case of protective devices of Type 4, the device is so designed that it is necessary to put it out of action in order to release the transmission. If this device is activated by the control of the parking device, it acts in conjunction with the device that deactivates the engine of the vehicle	☐	☐	☒
5.1.3.	It is only possible to extract the key with the bolt in the fully engaged or fully disengaged position. Any intermediate position of the key that risks subsequent engagement of the bolt – even if the key of the protective device is inserted – is excluded.	☒	☐	☐
5.3.	Protective device referred to in paragraph 5.1 above – and the vehicle components on which it operates – is so designed that it cannot rapidly and without attracting attention be opened, rendered ineffective, or destroyed by, for example, the use of low-cost, easily concealed tools, equipment or fabrications readily available to the public at large.	☒	☐	☐
5.4.	Protective device is mounted on the vehicle as an item of original equipment (i.e. equipment installed by the vehicle manufacturer prior to first retail sale). Lock is securely assembled in the protective device. <i>Note: If the lock can be extracted using the key after the cover or any other retention device has been removed, this is not in contradiction with the requirement.</i>	☒	☐	☐
5.5.	Key locking system provides at least 1,000 different key combinations, or a number equal to the total number of vehicles manufactured annually, if less than 1,000. In vehicles of one type, the frequency of occurrence of each combination is roughly one per 1,000.	☒	☐	☐
5.6.	Key and lock are not visibly coded.	☒	☐	☐
5.7.	Lock is so designed, constructed and fitted that the turning of the lock cylinder (when in the locked position) with a torque of less than 0.245 mdaN, is not possible with anything other than the mating key.	☒	☐	☐
5.7.1.	For lock cylinders with pin tumblers, no more than two identical tumblers operating in the same direction are positioned adjacent to each other, and in a lock there are not > 60 % identical tumblers.	☒	☐	☐
5.7.2.	For lock cylinders with disc tumblers, no more than two identical tumblers operating in the same direction are positioned adjacent to each other, and in a lock there are not > 50 % identical tumblers.	☐	☐	☒
5.8.	Protective devices are such as to exclude any risk, while the vehicle is in motion with the engine running, of accidental blockage likely to compromise safety in particular.	☒	☐	☐
5.9.	Protective device, if it is of Type 1, Type 2 or Type 3 is, in its activated position, strong enough to withstand, without damage to the steering mechanism likely to compromise safety, the application of a torque of 20 mdaN about the axis of the steering shaft in both directions under static conditions.	☒	☐	☐
5.10.	Protective device, if it is of Type 1, Type 2 or Type 3, is so designed that the steering can only be locked at an angle of $\geq 20^\circ$ to the left and/or the right of the straight-ahead position.	☒	☐	☐

Test Results

PASS FAIL N/A

Particular Specifications

6.1.1.	Lockable only by movement of key (handlebars being in appropriate position for bolt to engage in slot). <i>Note: Types 1 and 2 only.</i>	☒	☐	☐
6.1.2.	Pre-loading of bolt only possible by separate action combined with or in addition to turning of key/Removal of key not possible after bolt has been pre-loaded other than in accordance with 5.1.3. <i>Note: Type 3 only.</i>	☐	☐	☒
6.2.	Bolt prevented from engaging when device is in position that permits starting of engine. <i>Note: Types 2 and 3 only.</i>	☐	☐	☒
6.3.	Impossible to prevent device functioning when set. <i>Note: Type 3 only.</i> Device subjected to wear test for 2,500 cycles. <i>Note: Type 3 only.</i>	☐	☐	☒
6.4.	Device in good working order and complies with 5.7, 5.8, 5.9 and 6.3 after wear test. <i>Note: Type 3 only.</i>	☐	☐	☒

Vehicles of categories L1e to L7e, which are not fitted with handlebars: NOT APPLICABLE

APPENDIX 3 - C6

Electromagnetic compatibility (EMC)

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 44/2014 Annex VII
Including amendment (EU) 2018/295
UNECE R10.06

1. Witness details

- 1.1. Witness : Wang Liming
- 1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
- 1.3. Date of test : 14/03/2025 - 15/03/2025
- 1.4. Worst Case Rationale : Single specification
- 1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
- 2.2. All instruments are equipped with
identification label : Yes
- 2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
3m Semi-anechoic Chamber	NY0045CA8410224 / 2SB240711114409-0051A	23/07/2027
EMI receiver	102812 / 2SB240711114409-0004	24/07/2025
Hybrid antenna	01405 / 1SA241209155064N-0014B	21/12/2025
Artificial main network	20028 / 2SB240711114409-0006A	24/07/2025
Signal generator	DSG8M225000149 / 2SB240711114409-0020	24/07/2025
Power sensor	SG41490199 / 2SB240711114409-0009A	24/07/2025
Power sensor	MY41498243 / 2SB240711114409-0010A	24/07/2025
Power amplifier	MPA2106161 / 2SB240711114409-0019A	24/07/2025
Power amplifier	MPA2106162 / 2SB240711114409-0018	24/07/2025
Power amplifier	MPA2106163 / 2SB240711114409-0017C	24/07/2025
Field probe	811ZX01095 / 1GA240711114409-0012	24/07/2025
Harmonic & flicker test system	2110A01096+2108A01846 / 2SB240711114409-0023A	24/07/2025
Surge/EFT generator	SX082103J9 / 2SB240711114409-0024A	24/07/2025
Biconical antenna**	VHBB9124+BBA916 / 1SA240711114409-0002	27/07/2025
Log periodic antenna**	#177 / 1SA240711114409-0003A	27/07/2025

*Specify ~~calibrated date + (interval)~~ or calibration due date.

**Calibration is not required for the antenna used for immunity of vehicles to electromagnetic radiation.

3 Test results

3.1. Specifications in configurations other than REESS charging mode coupled to power grid

- | | | | |
|--------|--|---|---------------------------------|
| 3.1.1. | Broadband electromagnetic radiation from vehicles | : | Referring to test results below |
| 3.1.2. | Narrowband electromagnetic radiation from vehicles | : | Referring to test results below |
| 3.1.3. | Immunity of vehicles to electromagnetic radiation | : | Referring to test results below |

3.2. Additional specifications in configuration REESS charging mode coupled to power grid



- | | | | |
|--------|---|---|---------------------------------|
| 3.2.1. | Broadband electromagnetic radiation from vehicle | : | Referring to test results below |
| 3.2.2. | Emission of harmonics on AC power lines from vehicle | : | Referring to test results below |
| 3.2.3. | Emission of voltage changes, fluctuations, flickers on AC power lines from vehicle | : | Referring to test results below |
| 3.2.4. | Emission of radiofrequency conducted disturbances on AC or DC power lines from vehicle | : | Referring to test results below |
| 3.2.5. | Emission of radiofrequency conducted disturbances on network and telecommunication access from vehicle | : | Not applicable |
| 3.2.6. | Immunity of vehicle to electromagnetic radiation | : | Referring to test results below |
| 3.2.7. | Immunity of vehicle to electrical fast transient/burst disturbances conducted along AC and DC power lines | : | Referring to test results below |
| 3.2.8. | Immunity of vehicle to surge conducted along AC and DC power lines | : | Referring to test results below |



Test Results

1. Broadband electromagnetic radiation from vehicles other than REESS charging mode

Para.	Requirements	PASS	FAIL	N/A
Ann 4, 2.1.1 CISPR 12, 5.3.2	Engine is at normal operating temperature and running at correct speed - For single cylinder engines, engine speed is 2500 ±10% rpm* - For multiple cylinder engines, engine speed is 1500 ±10% rpm* *Strike-through, as appropriate.	☐	☐	☒
Ann4, 2.1.1. Add by 10.06	For vehicle with an electric propulsion motor or hybrid propulsion system, if this is not appropriate (e.g. in case of busses, trucks, two- and three wheel vehicles), transmission shafts, belts or chains may be disconnected to achieve the same operation condition for the propulsion.	☒	☐	☐
CISPR 12, 5.3.2	For vehicles with electric propulsion motor, vehicle is driven at 40 km/h on an unloaded dynamometer or insulated axle stands	☒	☐	☐
CISPR 12, 5.3.2	Speed setting mechanism not influencing electromagnetic radiation	☒	☐	☐
Ann 4, 2.1.2	Other sources of broadband noise at maximum current drain List: Lighting and light-signalling device	☒	☐	☐
Ann 4, 3.2. Rev by 10.06	Absorber lined shielded enclosures (ALSE) and outdoor test site (OTS) may be used. An ALSE has the advantage of all all-weather testing, a controlled environment and improved repeatability because of the stable chamber electrical characteristics.	☒	☐	☐

Para.	Requirements	PASS	FAIL	N/A																		
Ann 4, 4.2	Detector used: - Peak Detector * (For electric vehicles, only peak detector is used) - Quasi-peak detector * <i>*Strike-through, as appropriate.</i>	☒	☐	☐																		
Ann 4. 4.3	The measurements shall be performed with following receiver - Spectrum analyser * - Scanning receiver * <i>*Strike-through, as appropriate.</i>	☒	☐	☐																		
Ann 4, 4 Table 1 Rev by 10.06	Spectrum analyser measurement parameters <table><tr><th colspan="2">Peak Detector</th><th colspan="2">Quasi-peak Detector</th></tr><tr><td>RBW at -3 dB *1</td><td>Minimum Scan time</td><td>RBW at -6 dB</td><td>Minimum Scan time</td></tr><tr><td>100 /120 kHz *2</td><td>100 ms/MHz</td><td>120 kHz</td><td>20 s/MHz</td></tr></table> <i>Note: *1 the video bandwidth shall be at least three times the resolution bandwidth</i> <i>*2 Strike-through, as appropriate.</i>	Peak Detector		Quasi-peak Detector		RBW at -3 dB *1	Minimum Scan time	RBW at -6 dB	Minimum Scan time	100 /120 kHz *2	100 ms/MHz	120 kHz	20 s/MHz	☐	☐	☒						
Peak Detector		Quasi-peak Detector																				
RBW at -3 dB *1	Minimum Scan time	RBW at -6 dB	Minimum Scan time																			
100 /120 kHz *2	100 ms/MHz	120 kHz	20 s/MHz																			
Ann 4, 4 Table 2 Rev by 10.06	Scanning receiver measurement parameters <table><tr><th colspan="3">Peak Detector</th><th colspan="3">Quasi-peak Detector</th></tr><tr><td>BW at -6 dB</td><td>Step size</td><td>Minimum Scan time</td><td>BW at -6 dB</td><td>Step size</td><td>Minimum Scan time</td></tr><tr><td>120 kHz</td><td>50 kHz</td><td>5 ms</td><td>120 kHz</td><td>50 kHz</td><td>1 s</td></tr></table> <i>Note: the maximum frequency step size may be increased up to a value not greater than the bandwidth value.</i>	Peak Detector			Quasi-peak Detector			BW at -6 dB	Step size	Minimum Scan time	BW at -6 dB	Step size	Minimum Scan time	120 kHz	50 kHz	5 ms	120 kHz	50 kHz	1 s	☒	☐	☐
Peak Detector			Quasi-peak Detector																			
BW at -6 dB	Step size	Minimum Scan time	BW at -6 dB	Step size	Minimum Scan time																	
120 kHz	50 kHz	5 ms	120 kHz	50 kHz	1 s																	
6.2.2.3	Measured results below limits across frequency band <i>Note: Ann 4, 4.2 If peak detectors are used a correction factor of 20 dB as defined in CISPR 12 shall be applied</i>	☒	☐	☐																		





e13*168/2013*02582*00



Société Nationale de Certification et d'Homologation

2. Narrowband electromagnetic radiation from vehicles other than REESS charging mode

Para.	Requirements	PASS	FAIL	N/A						
Ann 5, 2.1	Ignition switched on and the engine shall not be operating.	☒	☐	☐						
Ann 5, 2.2, 2.3	The vehicle's electronic systems shall all be in normal operating mode with the vehicle stationary. All equipment which can be switched on permanently by the driver or passenger with internal oscillators 9 kHz or repetitive signals should be in normal operation.	☒	☐	☐						
Ann 5, 3.2	Average detector used	☒	☐	☐						
Ann 5. 3.2	The measurements shall be performed with following receiver - Spectrum analyser * - Scanning receiver * <i>*Strike-through, as appropriate.</i>	☒	☐	☐						
Ann 4, 4 Table 1 Rev by 10.06	Spectrum analyser measurement parameters <table><tr><td>RBW at -3 dB</td><td colspan="2">Minimum Scan Time</td></tr><tr><td>100 /120 kHz *2</td><td colspan="2">100 ms/MHz</td></tr></table> <i>*2 Strike-through, as appropriate.</i>	RBW at -3 dB	Minimum Scan Time		100 /120 kHz *2	100 ms/MHz		☐	☐	☒
RBW at -3 dB	Minimum Scan Time									
100 /120 kHz *2	100 ms/MHz									
Ann 4, 4 Table 2 Rev by 10.06	Scanning receiver measurement parameters <table><tr><td>BW at -6 dB</td><td>Step Size</td><td>Minimum Scan Time</td></tr><tr><td>120 kHz</td><td>50 kHz</td><td>5 ms</td></tr></table> <i>Note: the maximum frequency step size may be increased up to a value not greater than the bandwidth value</i>	BW at -6 dB	Step Size	Minimum Scan Time	120 kHz	50 kHz	5 ms	☒	☐	☐
BW at -6 dB	Step Size	Minimum Scan Time								
120 kHz	50 kHz	5 ms								
6.3.2.1 Rev by 10.06	If measurements are made using the method described in Annex 5 using a vehicle-to-antenna spacing of 10.0 +/- 0.2 m, the limits shall be 28 dB microvolts/m in the 30 to 230 MHz frequency band and 35 dB microvolts/m in the 230 to 1,000 MHz frequency band.	☐	☐	☒						
6.3.2.2 Rev by 10.06	If measurements are made using the method described in Annex 5 using a vehicle-to-antenna spacing of 3.0 +/- 0.5 m, the limits shall be 38 dB microvolts/m in the 30 to 230 MHz frequency band and 35 dB microvolts/m in the 230 to 1,000 MHz frequency band.	☒	☐	☐						
6.3.2.3	Measured results below limits across frequency band	☒	☐	☐						
6.3.2.4	Initial test carried out (the signal strength measured at the vehicle broadcast radio antenna is less than 20 dB micro-volts over the frequency range 76 to 108 MHz) then the vehicle shall be deemed to comply with the limits for narrowband emissions	☐	☐	☒						



e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



3. Immunity of vehicles to electromagnetic radiation other than REESS charging mode

Para.	Requirements	PASS	FAIL	N/A
5.1.2	Test method	☒	☐	☐
	- Transmission Line System (TLS)* - Antenna * - Bulk Current Injection (BCI), If a vehicle is longer than 12 m and/or wider than 2.60 m and/or higher than 4.00 m (Optional)* <i>*Strike-through, as appropriate.</i>			
	TLS method			
Ann 6, 5.1.2	One field probe at the facility reference point shall be used	☐	☐	☒
ISO11451-2, 8.2.3	No part of TLS closer than 0.5 m to any part of the vehicle	☐	☐	☒
ISO11451-2, 8.2.3	TLS radiating elements separated by at least 1 m vertically from the reference point	☐	☐	☒
ISO11451-2, 8.2.3	TLS ≥ 75 % of length of vehicle	☐	☐	☒
	Antenna method			
ISO11451-2 9.4.2.1	Four probe method used to establish reference line	☒	☐	☐
ISO11451-2 9.4.1	Field strength contour within + 0dB, -6dB for at least 80 % of the test frequency points, measured 0.50m each side of the reference point	☒	☐	☐
ISO11451-2 9.4.2.2 b	Heights of four probes are:	☒	☐	☐
	- 0.5 m, 0.8 m, 1.0 m and 1.2 m for vehicles with roof height ≤ 3 m * - 1.2 m, 1.5 m, 1.8 m and 2.1 m for vehicles with roof height > 3 m * <i>*Strike-through, as appropriate.</i>			
ISO11451-2 9.4.1	Two probes are 0.5 m on each side of the reference point	☒	☐	☐
Ann 6, 4.1	Antenna vertically polarized	☒	☐	☐
ISO11451-2, 8.2.1	Antenna elements no closer than 0.5 m to any absorber	☒	☐	☐
	and no closer than 1.5 m to any wall	☒	☐	☐
ISO11451-2, 8.2.2	Antenna elements no closer than 0.5 m to outer body surface of the vehicle	☒	☐	☐
ISO11451-2, 8.2.2	Phase centre of the antenna is at least 2 m horizontally from the reference point	☒	☐	☐
ISO11451-2, 8.2.2	and no closer than 0.25 m to the floor	☒	☐	☐
ISO11451-2, 8.2.2	No absorbent material between antenna and vehicle	☒	☐	☐
	Vehicle Reference Point Setup			
ISO11451-2 9.4.2.2	On vehicle centre line	☒	☐	☐

Para.	Requirements	PASS	FAIL	N/A
	For Category M, N, O:			
ISO11451-2 9.4.2.2	Either 0.2 ± 0.2 m behind front axle (Figure 4) or 1.0 ± 0.2 m inside the vehicle measured from base of windscreen (Figure 5), whichever results in a reference point closer to the antenna	☐	☐	☒
	For Category L			
Ann 6, 3.3.1	At least 2 m horizontally from the antenna phase centre or at least 1 m vertically from the radiating elements of a TLS	☒	☐	☐
Ann 6, 3.3.2	On the vehicle's centre line	☒	☐	☐
Ann 6, 3.3.3	At a height of 1.0 ± 0.05 m above the plane on which the vehicle rests or 2.0 ± 0.05 m if the minimum height of the roof exceeds 3.0 m	☒	☐	☐
Ann 6, 3.3.4 App 1 Fig 1	Three-wheeled vehicles ; Either at 1.0 ± 0.2 m behind the vertical centreline of the vehicle's front wheel (point C in Figure 1)	☐	☐	☒
Ann 6, 3.3.4 App 1 Fig 2	Two-wheeled vehicles. 0.2 ± 0.2 m behind the vertical centreline of the vehicle's front wheel (point D in Figure 2)	☐	☐	☒
Ann 6, 3.3.5 App1 Fig 3	If it is decided to radiate the rear of the vehicle, the reference point shall be established as in paragraphs 3.3.1. to 3.3.4.above The vehicle shall then be installed facing away from the antenna and positioned as if it had been horizontally rotated 180 around its centre point (Figure 3)	☒	☐	☐
	Vehicle Setup e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation			
Ann 6, 5.1.3	Vehicle phase - The vehicle shall be positioned with the centre line of the vehicle on the facility reference point or line - The electronic control units and the associated wiring harness are predominantly in the rear of the vehicle, the test should normally be carried out with the vehicle facing away from the antenna * - In the case of long vehicles (except categories L, M1 and N1), which have electronic control units and associated wiring harness predominantly towards the middle of the vehicle, a reference point may be established based on either the right side surface or the left side surface of the vehicle. This reference point shall be at the midpoint of the vehicle's length or at one point along the side *Strike-through, as appropriate.	☒	☐	☐
ISO11451-1 4.2	Ambient temperature is 23 ± 5 °C	☒	☐	☐
Ann 6, 2.1.1	Unladen except test equipment	☒	☐	☐
Ann 6, 2.1.1.1	Vehicle running - Dynamometer with appropriately load * - Insulated axle stands * *Strike-through, as appropriate.	☒	☐	☐
Ann 6, 2.1.1.1	Vehicle speed: 50 km/h and gear: N/A 50 km/h or 25 km/h for L1, L2	☒	☐	☐

Para.	Requirements	PASS	FAIL	N/A																				
Ann 6, 2.1.1.2	Set vehicle test conditions (see below vehicle test conditions)	☒	☐	☐																				
Ann 6, 2.1.1.3	All equipment which can be switched on permanently by the driver or passenger is in normal operation	☒	☐	☐																				
Ann 6, 2.1.1.4	All other systems which affect driver's control on as in normal operation of vehicle	☒	☐	☐																				
Ann 6, 2.1.2	Reports for other systems which affect driver's control but cannot be activated during the test are attached	☐	☐	☒																				
Ann 6, 2.1.3	Only non-perturbing monitoring equipment	☒	☐	☐																				
Test Requirements																								
Ann 6, 4.1.1	Pre-test sweep supplied to show compliance throughout frequency range 20 to 2000 MHz	☒	☐	☐																				
Ann 6, 4.1.1	Test frequencies chosen from pre-test data. If the test laboratory accredited by ISO 17025 and recognized by CETOC TS	☐	☐	☒																				
Ann 6, 4.1.1	Suggested frequency points used	☒	☐	☐																				
ISO11451-1 4.6	Frequency step sizes are less than:	☒	☐	☐																				
<table><tr><th>Frequency Band MHz</th><th>Linear Steps MHz</th><th>Log Steps %</th><th>Actual Steps Used</th></tr><tr><td>20 – 200</td><td>5</td><td>5</td><td>5</td></tr><tr><td>200 – 400</td><td>10</td><td>5</td><td>5</td></tr><tr><td>400 – 1000</td><td>20</td><td>2</td><td>2</td></tr><tr><td>1000 – 2000</td><td>40</td><td>2</td><td>2</td></tr></table>		Frequency Band MHz	Linear Steps MHz	Log Steps %	Actual Steps Used	20 – 200	5	5	5	200 – 400	10	5	5	400 – 1000	20	2	2	1000 – 2000	40	2	2			
Frequency Band MHz	Linear Steps MHz	Log Steps %	Actual Steps Used																					
20 – 200	5	5	5																					
200 – 400	10	5	5																					
400 – 1000	20	2	2																					
1000 – 2000	40	2	2																					
ISO11451-1 4.5	Test signal dwell time sufficient (minimum 1 seconds)	☒	☐	☐																				
Ann 6, 4.1	Between 20 MHz and 800 MHz, test signal is sine wave amplitude modulated (AM) by a 1 kHz sine wave at a modulation depth of 80 %	☒	☐	☐																				
Ann 6, 4.1	Between 800 MHz and 2000 MHz, test signal is pulse modulated (PM), time on 577 µs, period 4600 µs	☒	☐	☐																				

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

PASS FAIL N/A

'50 km/h Cycle' Vehicle Test Conditions

Pass Criteria

Vehicle speed 50 km/h (respectively 25 km/h for L1, L2 vehicles) $\pm 20\%$ (vehicle driving the rollers). If the vehicle is equipped with a cruise control system, it is operational

Speed variation not more than $\pm 10\%$ of the nominal speed

☒ ☐ ☐

In case of automatic gearbox: change-of-gear ratio inducing a speed variation not more than $\pm 10\%$ of the nominal speed

Dipped beams on (manual mode)

Lights remains on

☒ ☐ ☐

Front wiper on (manual mode) maximum speed

No stopping of front wiper

☐ ☐ ☒

Direction indicator on driver's side on

Frequency change (not less than 0.75 Hz or not more than 2.25 Hz)

☒ ☐ ☐

Duty cycle change (greater than 25 % or lower than 75 %)

Adjustable suspension in normal position

No unexpected significant variation

☐ ☐ ☒

Driver's seat and steering wheel in mid-position

No unexpected variation greater than 10 % of total range

☐ ☐ ☒

Alarm unset

No unexpected activation of alarm

☐ ☐ ☒

Horn off

No unexpected activation of horn

☒ ☐ ☐

Airbag and safety restraint systems operational with inhibited passenger airbag

No unexpected activation

☐ ☐ ☒

Automatic doors closed

No unexpected activation

☐ ☐ ☒

Adjustable endurance brake lever in normal position

No unexpected activation

☐ ☐ ☒

'Brake Cycle' Vehicle Test Conditions

Pass Criteria

Operation of the brake pedal, but not necessarily activation of the ABS system

Stop lights remain active during cycle

☒ ☐ ☐


Brake warning light (tell-tale) remains off with no loss of function or performance

No unexpected activation

4. Broadband electromagnetic radiation from vehicle in configuration REESS charging mode coupled to power grid


Para.	Requirements	PASS	FAIL	N/A	
Ann 4, 2.2	The state of charge (SOC) of the traction battery shall be kept between 20 per cent and 80 per cent of the maximum SOC	☒	☐	☐	
Ann 4, 2.2	If the current consumption can be adjusted, then the current shall be set to at least 80 per cent of its nominal value	☒	☐	☐	
CETOC TS	SOC of REESS	☒	☐	☐	
	Pre <table border="1"><tr><td>38</td></tr></table> %	38			
38					
	Post <table border="1"><tr><td>41</td></tr></table> %	41			
41					
Ann 4, 2.2	The test set-up for the connection of the vehicle in configuration "REESS in charging mode coupled to the power grid" is as per shown in figure 3a to 3h of Annex 4	☒	☐	☐	
Ann 4, 2.3	Duplicated power mains and communication lines socket(s) shall be placed in the test location with the following conditions: (a) It shall be placed on the ground plane. (b) The length of the harness between the power mains/communication lines socket and the AN(s)/IS(s) shall be kept as short as possible. (c) The harness between the power mains/communication lines socket and the AN(s)/IS(s) shall be placed as close as possible to the ground plane.	☒	☐	☐	
Ann 4, 2.3	If the charging station is placed inside the test location then the harness between charging station and the power mains / communication lines socket shall be placed with the following conditions (a) The harness on charging station side shall hang vertically down to the ground plane. (b)The extraneous length shall be placed as close as possible to the ground plane and "Z-folded" if necessary.	☐	☐	☒	
Ann 4, 2.4	The AN shall be mounted directly on the ground plane. The cases of the AN shall be bonded to the ground plane. The measuring port of each AN shall be terminated with a 50Ω load. The AN shall be placed as defined in Figures 3a to 3h of Annex 4	☒	☐	☐	
Ann 4, 2.5	Communication lines shall be applied to the vehicle through impedance stabilization (IS). The IS to be connected in the network and communication cables is defined in CISPR 22, paragraph 9.6.2. The IS shall be mounted directly on the ground plane. The case of the IS shall be bonded to the ground plane. The measuring port of each IS shall be terminated with a 50Ω load. The IS shall be placed as defined in Figures 3e to 3h of Annex 4	☒	☐	☐	
Ann 4, 2.6	The power charging / communication cable shall be placed in a straight line between the AN(s) / IS(s) and the vehicle charging plug. The projected cable length shall be 0.8 m (+0.2/-0 m).	☒	☐	☐	
Ann 4, 2.6	If the length of the cable is longer than 1.0 m, the extraneous length shall be "Z-folded" in less than 0.5 m width.	☒	☐	☐	
Ann 4, 2.6	The charging / communication cable at vehicle side shall hang vertically at a distance of 100 mm (+200/-0 mm) from the vehicle body.	☒	☐	☐	
Ann 4, 2.6	The whole cable shall be placed on a non-conductive, low relative permittivity (dielectric-constant) material $\epsilon_r \leq 1.4$, at 100 mm (± 25 mm) above the ground plane.	☒	☐	☐	

Para.	Requirements	PASS	FAIL	N/A																		
Ann 4, 4.2	Detector used: - Peak Detector * (For electric vehicles, only peak detector is used) - Quasi-peak detector * <i>*Strike-through, as appropriate.</i>	☒	☐	☐																		
Ann 4, 4.3	The measurements shall be performed with following receiver - Spectrum analyser * - Scanning receiver * <i>*Strike-through, as appropriate.</i>	☒	☐	☐																		
Ann 4, 4 Table 1	Spectrum analyser measurement parameters <table><tr><th colspan="2">Peak Detector</th><th colspan="2">Quasi-peak Detector</th></tr><tr><td>RBW at -3 dB *1</td><td>Scan time</td><td>RBW at -6 dB</td><td>Scan time</td></tr><tr><td>100 /120 kHz *2</td><td>100 ms/MHz</td><td>120 kHz</td><td>20 s/MHz</td></tr></table> <i>Note: *1 the video bandwidth shall be at least three times the resolution bandwidth</i> <i>*2 Strike-through, as appropriate.</i>	Peak Detector		Quasi-peak Detector		RBW at -3 dB *1	Scan time	RBW at -6 dB	Scan time	100 /120 kHz *2	100 ms/MHz	120 kHz	20 s/MHz	☐	☐	☒						
Peak Detector		Quasi-peak Detector																				
RBW at -3 dB *1	Scan time	RBW at -6 dB	Scan time																			
100 /120 kHz *2	100 ms/MHz	120 kHz	20 s/MHz																			
Ann 4, 4 Table 2	Scanning receiver measurement parameters <table><tr><th colspan="3">Peak Detector</th><th colspan="3">Quasi-peak Detector</th></tr><tr><td>BW at -6 dB</td><td>Step size</td><td>Dwell time</td><td>BW at -6 dB</td><td>Step size</td><td>Dwell time</td></tr><tr><td>120 kHz</td><td>50 kHz</td><td>5 ms</td><td>120 kHz</td><td>50 kHz</td><td>1 s</td></tr></table> <i>Note: the maximum frequency step size may be increased up to a value not greater than the bandwidth value.</i>	Peak Detector			Quasi-peak Detector			BW at -6 dB	Step size	Dwell time	BW at -6 dB	Step size	Dwell time	120 kHz	50 kHz	5 ms	120 kHz	50 kHz	1 s	☒	☐	☐
Peak Detector			Quasi-peak Detector																			
BW at -6 dB	Step size	Dwell time	BW at -6 dB	Step size	Dwell time																	
120 kHz	50 kHz	5 ms	120 kHz	50 kHz	1 s																	
Test Results																						
7.2.2	Measured results below limits across frequency band Note: Ann 4, 4.2 If peak detectors are used a correction factor of 20 dB as defined in CISPR 12 shall be applied	☒	☐	☐																		




Société Nationale de Certification et d'Homologation

BBHL



BBHR



e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

5. Emission of harmonics on AC power lines from vehicle

Para.	Requirements	PASS	FAIL	N/A	
Ann 11, 2.1	The state of charge (SOC) of the traction battery shall be kept between 20 per cent and 80 per cent of the maximum SOC	☒	☐	☐	
Ann 11, 2.1	If the current consumption can be adjusted, then the current shall be set to at least 80 per cent of its nominal value	☒	☐	☐	
CETOC TS	SOC of REESS	☒	☐	☐	
	Pre <table border="1"><tr><td>42</td></tr></table> %	42			
42					
	Post <table border="1"><tr><td>48</td></tr></table> %	48			
48					
Ann 11, 2.1	Immobilized, engine OFF and in charging mode	☒	☐	☐	
Ann 11, 2.1	All other equipment which can be switched on permanently by the driver or passenger switched OFF	☒	☐	☐	
Ann 11, 1.2	Test Arrangement - IEC 61000-3-2 for input current in charging mode ≤16 A per phase for class A equipment,* - IEC 61000-3-12 for input current in charging mode > 16 A and ≤75 A per phase* <i>*Strike-through, as appropriate.</i>				
Ann 11, 3.1	The observation time to be used for the measurements shall be as for quasi-stationary equipment as defined in IEC 61000-3-2 Table 4.	☒	☐	☐	
Ann 11, 3.2, 3.3	The test set-up - Single phase vehicle in configuration "REESS charging mode coupled to the power grid" is shown in figure 1 of Annex 11 * - Three phase vehicle in configuration "REESS charging mode coupled to the power grid" is shown in figure 2 of Annex 11 * <i>*Strike-through, as appropriate.</i>	☒	☐	☐	
Ann 11, 4.1	The measurements of even and odd current harmonics shall be performed up to the 40th harmonic.	☒	☐	☐	
	Test Results				
7.3.2 Ann 11, 4.2-4.5	Measured results below limits - Single phase or three-phase "REESS charging mode coupled to the power grid" with input current ≤ 16 A per phase are given in Table 3 of paragraph 7.3.2.1 * - Single phase "REESS charging mode coupled to the power grid" with input current > 16 A and ≤ 75 A per phase are given in Table 4 of paragraph 7.3.2.2 * - Three phase "REESS charging mode coupled to the power grid" with input current > 16 A and ≤ 75 A per phase are given in Table 5 of paragraph 7.3.2.2. * - Three phase "REESS charging mode coupled to the power grid" with input current > 16 A and ≤ 75 A per phase, when at least one of the three conditions a), b) or c) described in clause 5.2. of IEC 61000-3-12 is fulfilled, then the limits given in Table 6 of paragraph 7.3.2.2. * <i>*Strike-through, as appropriate.</i>	☒	☐	☐	

Test results

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Current Harmonics (values at the end of test)

Harm#	Harms(avg)	100%Limit	%of Limit	Harms(max)	150%Limit	%of Limit	Status
2	0.005	1.080	N/A	0.010	1.620	N/A	Pass
3	0.242	2.300	10.5	0.250	3.450	7.2	Pass
4	0.004	0.430	N/A	0.006	0.645	N/A	Pass
5	0.112	1.140	9.9	0.116	1.710	6.8	Pass
6	0.003	0.300	N/A	0.005	0.450	N/A	Pass
7	0.096	0.770	12.5	0.101	1.155	8.7	Pass
8	0.002	0.230	N/A	0.004	0.345	N/A	Pass
9	0.027	0.400	N/A	0.030	0.600	N/A	Pass
10	0.002	0.184	N/A	0.004	0.276	N/A	Pass
11	0.052	0.330	15.7	0.054	0.495	10.8	Pass
12	0.002	0.153	N/A	0.004	0.230	N/A	Pass
13	0.069	0.210	32.9	0.071	0.315	22.5	Pass
14	0.002	0.131	N/A	0.003	0.197	N/A	Pass
15	0.049	0.150	32.7	0.052	0.225	23.0	Pass
16	0.002	0.115	N/A	0.003	0.173	N/A	Pass
17	0.031	0.132	N/A	0.032	0.198	N/A	Pass
18	0.002	0.102	N/A	0.004	0.153	N/A	Pass
19	0.027	0.118	N/A	0.029	0.178	N/A	Pass
20	0.002	0.092	N/A	0.004	0.138	N/A	Pass
21	0.024	0.107	N/A	0.026	0.161	N/A	Pass
22	0.002	0.084	N/A	0.003	0.125	N/A	Pass
23	0.025	0.098	N/A	0.026	0.147	N/A	Pass
24	0.002	0.077	N/A	0.004	0.115	N/A	Pass
25	0.021	0.090	N/A	0.023	0.135	N/A	Pass
26	0.003	0.071	N/A	0.005	0.107	N/A	Pass
27	0.018	0.083	N/A	0.020	0.125	N/A	Pass
28	0.010	0.066	N/A	0.011	0.099	N/A	Pass
29	0.018	0.078	N/A	0.020	0.116	N/A	Pass
30	0.007	0.061	N/A	0.008	0.092	N/A	Pass
31	0.016	0.073	N/A	0.019	0.109	N/A	Pass
32	0.009	0.058	N/A	0.011	0.086	N/A	Pass
33	0.013	0.068	N/A	0.015	0.102	N/A	Pass
34	0.003	0.054	N/A	0.004	0.081	N/A	Pass
35	0.011	0.064	N/A	0.012	0.096	N/A	Pass
36	0.002	0.051	N/A	0.003	0.077	N/A	Pass
37	0.009	0.061	N/A	0.011	0.091	N/A	Pass
38	0.002	0.048	N/A	0.005	0.073	N/A	Pass
39	0.009	0.058	N/A	0.013	0.087	N/A	Pass
40	0.002	0.046	N/A	0.005	0.069	N/A	Pass

6. Emission of voltage changes, fluctuations, flickers on AC power lines from vehicle

Para.	Requirements	PASS	FAIL	N/A		
Ann 12, 2.1	The SOC of the traction battery kept between 20% and 80% of the maximum SOC.	☒	☐	☐		
Ann 12, 2.1	If the current consumption can be adjusted, then the current is set to at least 80% of its nominal value.	☒	☐	☐		
CETOC TS	SOC of REESS	☒	☐	☐		
	Pre <table><tr><td>45</td><td>%</td></tr></table>	45	%			
45	%					
	Post <table><tr><td>51</td><td>%</td></tr></table>	51	%			
51	%					
Ann 12, 2.1	Vehicle is immobilized, engine(s) (ICE and/or electrical machine) OFF and in charging mode.	☒	☐	☐		
Ann 12, 2.1	All other equipment which can be switched on permanently by the driver or passenger switched OFF.	☒	☐	☐		
Ann 12, 3.3	Vehicle in configuration "RESS charging mode coupled to the power grid" is set-up for test as shown in figure 1a to 1b of Annex 12.	☒	☐	☐		
Ann 12, 3.1 - 3.2	Test Arrangements - Tests for vehicle in configuration "RESS charging mode coupled to the power grid" with rated current ≤16 A per phase and not subjected to conditional connection are performed according to IEC 61000-3-3, Para 4 * - Tests for vehicle in configuration "RESS charging mode coupled to the power grid" with rated current > 16 A and ≤75 A per phase and subjected to conditional connection are performed according IEC 61000-3-11 Para 6 * <i>*Strike-through, as appropriate.</i>	☒	☐	☐		
Annex 12, 4.1	The parameters to be determined in the time-domain are "short duration flicker value", "long duration flicker value" and "voltage relative variation."	☒	☐	☐		
	Test Results					
7.4.2	Measured results are below limits:					
	Rated current ≤ 16 A per phase and not subjected to conditional connection as defined in IEC 61000-3-3, Para 5	☒	☐	☐		
	Rated current > 16 A and ≤ 75 A per phase and subjected to conditional connection as defined in IEC 61000-3-11, Para 5	☐	☐	☒		

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation


Type: Steinadler Pro
Test category: All parameters (European limits)
Test duration (min): 120
Test Result: Pass

Test date: 15/03/2025
Comment: N/A


Vrms at the end of test (Volt):	227.10	Test limit (mS):	500.0	Pass
T-max (mS):	0	Test limit (%):	3.30	Pass
Highest dc (%):	0.00	Test limit (%):	6.00	Pass
Highest dmax (%):	0.00	Test limit:	1.000	Pass
Highest Pst (10 min. period):	0.198	Test limit:	0.650	Pass
Highest Plt (2 hr. period):	0.086			

7. Emission of radiofrequency conducted disturbances on AC or DC power lines from vehicle

Para.	Requirements	PASS	FAIL	N/A																											
Ann 13, 2.1	The state of charge (SOC) of the traction battery shall be kept between 20 per cent and 80 per cent of the maximum SOC	☒	☐	☐																											
Ann 13, 2.1	If the current consumption can be adjusted, then the current shall be set to at least 80 per cent of its nominal value	☒	☐	☐																											
CETOC TS	SOC of REESS	☒	☐	☐																											
	Pre <table><tr><td>51</td><td>%</td></tr><tr><td>59</td><td>%</td></tr></table>	51	%	59	%																										
51	%																														
59	%																														
	Post																														
Ann 13, 2.1	Immobilized, engine OFF and in charging mode	☒	☐	☐																											
Ann 13, 2.1	All other equipment which can be switched on permanently by the driver or passenger switched OFF	☒	☐	☐																											
Ann 13, 3.1	Test performed according to CISPR 16-2-1 (edition 2.0 – 2008) clause 7.4.1, as floor-standing equipment.	☒	☐	☐																											
Ann 13, 3.2	The AN(s) shall be mounted directly on the ground plane. The cases of the AN(s) shall be bonded to the ground plane. The measuring port of each AN shall be terminated with a 50Ω load. The AN shall be placed as defined in Figures 1a to 1d of Annex 13	☒	☐	☐																											
Ann 13, 3.3	The test set-up for the connection of the vehicle in configuration "RESS charging mode coupled to the power grid" is shown in figure 1 of Annex 13	☒	☐	☐																											
Ann 13, 3.4	The measurements shall be performed with following receiver - Spectrum analyser * - Scanning receiver * <i>*Strike-through, as appropriate.</i>	☒	☐	☐																											
Ann 13, 3.4 Table 1	Spectrum analyser measurement parameters	☐	☐	☒																											
<table><tr><td colspan="2">Peak Detector</td><td colspan="2">Quasi-peak Detector</td><td colspan="2">Average Detector</td></tr><tr><td>RBW at -3 dB</td><td>Scan time</td><td>RBW at -6 dB</td><td>Scan time</td><td>RBW at -3 dB</td><td>Scan time</td></tr><tr><td>9 / 10 kHz</td><td>10 s / MHz</td><td>9 kHz</td><td>200 s / MHz</td><td>9 / 10 kHz</td><td>10s / MHz</td></tr></table> <i>Note: *1 the video bandwidth shall be at least three times the resolution bandwidth</i>					Peak Detector		Quasi-peak Detector		Average Detector		RBW at -3 dB	Scan time	RBW at -6 dB	Scan time	RBW at -3 dB	Scan time	9 / 10 kHz	10 s / MHz	9 kHz	200 s / MHz	9 / 10 kHz	10s / MHz									
Peak Detector		Quasi-peak Detector		Average Detector																											
RBW at -3 dB	Scan time	RBW at -6 dB	Scan time	RBW at -3 dB	Scan time																										
9 / 10 kHz	10 s / MHz	9 kHz	200 s / MHz	9 / 10 kHz	10s / MHz																										
Ann 13, 3.4 Table 2	Scanning receiver measurement parameters	☒	☐	☐																											
<table><tr><td colspan="3">Peak Detector</td><td colspan="3">Quasi-peak Detector</td><td colspan="3">Average Detector</td></tr><tr><td>BW at -6 dB</td><td>Step size</td><td>Dwell time</td><td>BW at -6 dB</td><td>Step size</td><td>Dwell time</td><td>BW at -6 dB</td><td>Step size</td><td>Dwell time</td></tr><tr><td>9 kHz</td><td>5 kHz</td><td>50 ms</td><td>9 kHz</td><td>5 kHz</td><td>1 s</td><td>9 kHz</td><td>5 kHz</td><td>50 ms</td></tr></table> <i>Note: the maximum frequency step size may be increased up to a value not greater than the bandwidth value.</i>					Peak Detector			Quasi-peak Detector			Average Detector			BW at -6 dB	Step size	Dwell time	BW at -6 dB	Step size	Dwell time	BW at -6 dB	Step size	Dwell time	9 kHz	5 kHz	50 ms	9 kHz	5 kHz	1 s	9 kHz	5 kHz	50 ms
Peak Detector			Quasi-peak Detector			Average Detector																									
BW at -6 dB	Step size	Dwell time	BW at -6 dB	Step size	Dwell time	BW at -6 dB	Step size	Dwell time																							
9 kHz	5 kHz	50 ms	9 kHz	5 kHz	1 s	9 kHz	5 kHz	50 ms																							
Ann 13, 4.2	Measurements shall be performed with average and quasi-peak/peak detectors* <i>* Strike-through, as appropriate</i>	☒	☐	☐																											



No.	Frequency	Limit dBuV	Level dBuV	Delta dB	Reading dBuV	Factor dB	Detector	Phase
1	155.000kHz	65.73	49.68	-16.05	39.38	10.30	QP	L1
2	585.000kHz	56.00	37.56	-18.44	27.36	10.20	QP	L1
3	715.000kHz	56.00	30.82	-25.18	20.62	10.20	QP	L1
4	10.330MHz	60.00	36.48	-23.52	25.88	10.60	QP	L1
5	18.435MHz	60.00	27.44	-32.56	16.54	10.90	QP	L1
6	23.095MHz	60.00	26.41	-33.59	15.31	11.10	QP	L1
7	585.000kHz	46.00	31.51	-14.49	21.31	10.20	AV	L1
8	715.000kHz	46.00	26.57	-19.43	16.37	10.20	AV	L1
9	7.365MHz	50.00	18.28	-31.72	7.88	10.40	AV	L1
10	10.280MHz	50.00	16.29	-33.71	5.69	10.60	AV	L1
11	18.240MHz	50.00	20.38	-29.62	9.48	10.90	AV	L1
12	23.260MHz	50.00	14.99	-35.01	3.89	11.10	AV	L1



No.	Frequency	Limit dBuV	Level dBuV	Delta dB	Reading dBuV	Factor dB	Detector	Phase
1	155.000kHz	65.73	49.62	-16.11	39.42	10.20	QP	N
2	585.000kHz	56.00	35.49	-20.51	25.29	10.20	QP	N
3	6.930MHz	60.00	30.14	-29.86	19.64	10.50	QP	N
4	8.650MHz	60.00	33.42	-26.58	22.82	10.60	QP	N
5	9.450MHz	60.00	40.74	-19.26	30.04	10.70	QP	N
6	10.885MHz	60.00	37.15	-22.85	26.45	10.70	QP	N
7	160.000kHz	55.46	34.40	-21.06	24.20	10.20	AV	N
8	325.000kHz	49.58	28.07	-21.51	17.97	10.10	AV	N
9	415.000kHz	47.55	27.82	-19.73	17.62	10.20	AV	N
10	585.000kHz	46.00	28.23	-17.77	18.03	10.20	AV	N
11	6.855MHz	50.00	22.07	-27.93	11.57	10.50	AV	N
12	17.790MHz	50.00	19.92	-30.08	9.02	10.90	AV	N

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

8. Emission of radiofrequency conducted disturbances on network and telecommunication access from vehicle

Not applicable (There is no direct connection to a wired network which includes telecommunication service additional to the charging communication service)

9. Immunity of vehicle to electromagnetic radiation in the charging status

Para.	Requirements	PASS	FAIL	N/A	
Radiated Immunity Test					
	Test configuration is same as 6.4 above	☒	☐	☐	
Vehicle Setup					
ISO11451-1 4.2	Ambient temperature is 23 ± 5 °C	☒	☐	☐	
Ann 6, 2.2.1	Unladen except test equipment	☒	☐	☐	
Ann 6, 2.2.1.1	Immobilized, engine OFF and in charging mode	☒	☐	☐	
Ann 6, 2.2.1.3	All other equipment which can be switched on permanently by the driver or passenger switched OFF	☒	☐	☐	
Ann 6, 2.2.1.2	The state of charge (SOC) of the traction battery shall be kept between 20 per cent and 80 per cent of the maximum SOC	☒	☐	☐	
Ann 6, 2.2.1.2	If the current consumption can be adjusted, then the current shall be set to at least 20 per cent of its nominal value	☒	☐	☐	
CETOC TS	SOC of REESS	☒	☐	☐	
	Pre <table><tr><td>58</td></tr></table> %	58			
58					
	Post <table><tr><td>67</td></tr></table> %	67			
67					
Ann 6, 2.2.2	Only non-perturbing monitoring equipment	☒	☐	☐	
Ann 6, 2.2.3	The test set-up for the connection of the vehicle in configuration "REESS in charging mode coupled to the power grid" is as per shown in figure 4a to 4h of the Annex 6	☒	☐	☐	
Ann 6, 2.3	Duplicated power mains and communication lines socket(s) shall be placed in the test location with the following conditions: (a) It shall be placed on the ground plane. (b) The length of the harness between the power mains/communication lines socket and the AN(s)/IS(s) shall be kept as short as possible. (c) The harness between the power mains/communication lines socket and the AN(s)/IS(s) shall be placed as close as possible to the ground plane.	☒	☐	☐	
Ann 6, 2.3	If the charging station is placed inside the test location then the harness between charging station and the power mains / communication lines socket shall be placed with the following conditions (a) The harness on charging station side shall hang vertically down to the ground plane. (b)The extraneous length shall be placed as close as possible to the ground plane and "Z-folded" if necessary.	☐	☐	☒	

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Para.	Requirements	PASS	FAIL	N/A
Ann 6, 2.4	The AN(s) shall be mounted directly on the ground plane. The cases of the AN(s) shall be bonded to the ground plane. The measuring port of each AN shall be terminated with a 50Ω load. The AN shall be placed as defined in Figures 4a to 4h of Annex 6.	☒	☐	☐
Ann 6, 2.5	Communication lines shall be applied to the vehicle through IS(s). The IS to be connected in the network and communication cables is defined in CISPR 22, paragraph 9.6.2. The IS(s) shall be mounted directly on the ground plane. The case of the IS(s) shall be bonded to the ground plane. The measuring port of each IS shall be terminated with a 50Ω load. The IS shall be placed as defined in Figures 4a to 4h of Annex 6.	☒	☐	☐
Ann 6, 2.6	The power charging / communication cable shall be placed in a straight line between the AN(s) / IS(s) and the vehicle charging plug. The projected cable length shall be 0.8 m (+0.2/-0 m).	☒	☐	☐
Ann 6, 2.6	If the length of the cable is longer than 1.0 m, the extraneous length shall be "Z-folded" in less than 0.5 m width.	☒	☐	☐
Ann 6, 2.6	The charging / communication cable at vehicle side shall hang vertically at a distance of 100 mm (+200/-0 mm) from the vehicle body.	☒	☐	☐
Ann 6, 2.6	The whole cable shall be placed on a non-conductive, low relative permittivity (dielectric-constant) material $\epsilon_r \leq 1.4$, at 100 mm (± 25 mm) above the ground plane.	☒	☐	☐

e13*168/2013*02582*00

Test results

Société Nationale de Certification et d'Homologation

Ann 6, 2.2	Vehicle does not set in motion	☒	☐	☐
------------	--------------------------------	-------------------------------------	--------------------------	--------------------------

10. Immunity of vehicle to electrical fast transient/burst disturbances conducted along AC and DC power lines

Para.	Requirements	PASS	FAIL	N/A	
Ann 15, 2.1.2	The state of charge (SOC) of the traction battery shall be kept between 20 per cent and 80 per cent of the maximum SOC	☒	☐	☐	
Ann 15, 2.1.2	If the current consumption can be adjusted, then the current shall be set to at least 20 per cent of its nominal value	☒	☐	☐	
CETOC TS	SOC of REESS	☒	☐	☐	
	Pre <table border="1"><tr><td>65</td></tr></table> %	65			
65					
	Post <table border="1"><tr><td>75</td></tr></table> %	75			
75					
Ann 15, 2.1	Unladen except test equipment	☒	☐	☐	
Ann 15, 2.1	Immobilized, engine OFF and in charging mode	☒	☐	☐	
Ann 15, 2.1.3	All other equipment which can be switched on permanently by the driver or passenger switched OFF	☒	☐	☐	
Ann 15, 2.2	Only non-perturbing equipment shall be used while monitoring the vehicle.	☒	☐	☐	
	The vehicle exterior and the passenger compartment monitored to determine whether the requirements of this annex are met	☒	☐	☐	

Para.	Requirements	PASS	FAIL	N/A
Ann 15, 3.1	The test equipment is composed of a reference ground plane, a transient/burst generator, coupling/decoupling network (CDN) and capacitive coupling clamp.			
Ann 15, 3.2	The transient/burst generator shall meet the condition defined in paragraph 6.1. of IEC 61000-4-4	☒	☐	☐
Ann 15, 3.3	The coupling/decoupling network shall meet the condition defined in paragraph 6.2. of IEC 61000-4-4. When the coupling/decoupling network cannot be used on AC or DC power lines, the capacitive coupling clamp defined in paragraph 6.3. of IEC 61000-4-4 can be used	☒	☐	☐
Ann 15, 4.1	The vehicle test setup is based on the laboratory type setup as described in paragraph 7.2. of IEC 61000-4-4.	☒	☐	☐
Ann 15, 4.2	The vehicle shall be placed directly on the ground plane.	☒	☐	☐
7.8.2.1	The immunity test levels, for AC or DC power lines, shall be: ± 2 kV test voltage in open circuit, with a rise time (T_r) of 5 ns, and a hold time (T_h) of 50 ns and a repetition rate of 5 kHz for at least 1 minute.	☒	☐	☐
Ann 15, 5.1.1	The test method according to IEC 61000-4-4 shall be used to establish the test level requirements	☒	☐	☐
Ann 15, 5.1.2	The vehicle shall be positioned on the ground plane. The electrical fast transient/burst (EFT/B) shall be applied on the vehicle on the AC/DC power lines in common modes by using CDN as described in Figure 1 of Appendix 1 to this annex	☒	☐	☐
Test results				
Ann 6, 2.2	Vehicle does not set in motion	☒	☐	☐

11. Immunity of vehicle to surge conducted along AC and DC power lines

Para.	Requirements	PASS	FAIL	N/A
Ann 16, 2.1.2	The state of charge (SOC) of the traction battery shall be kept between 20 per cent and 80 per cent of the maximum SOC	☒	☐	☐
Ann 16, 2.1.2	If the current consumption can be adjusted, then the current shall be set to at least 20 per cent of its nominal value	☒	☐	☐
CETOC TS	SOC of REESS	☒	☐	☐
	Pre			
	Post			
Ann 16, 2.1	Unladen except test equipment	☒	☐	☐
Ann 16, 2.1.1	Immobilized, engine OFF and in charging mode	☒	☐	☐
Ann 16, 2.1.3	All other equipment which can be switched on permanently by the driver or passenger switched OFF	☒	☐	☐

Para.	Requirements	PASS	FAIL	N/A
Ann 16, 2.2	Only non-perturbing equipment shall be used while monitoring the vehicle.	☒	☐	☐
	The vehicle exterior and the passenger compartment monitored to determine whether the requirements of this annex are met	☒	☐	☐
	Test equipment			
Ann 16, 3.1	The test equipment is composed of a reference ground plane, a surge generator and a coupling/decoupling network (CDN).	☒	☐	☐
Ann 16, 3.2	Test shall be performed according to IEC 61000-4-5	☒	☐	☐
Ann 16, 3.3	The coupling/decoupling network shall meet the condition defined in paragraph 6.3. of IEC 61000-4-5.	☒	☐	☐
Ann 16, 4.1	The vehicle test setup is based on the setup described in paragraph 7.2. of IEC 61000-4-5.	☒	☐	☐
Ann 16, 4.2	The vehicle shall be placed directly on the ground plane.	☒	☐	☐
7.9.2	Vehicle immunity type approval limits	☒	☐	☐
	- AC power lines: ± 2 kV test voltage in open circuit between line and earth and ± 1 kV between lines (pulse $1.2 \mu\text{s}$ / $50 \mu\text{s}$), with a rise time (T_r) of $1.2 \mu\text{s}$, and a hold time (T_h) of $50 \mu\text{s}$. Each surge shall be applied five times with a maximum delay of 1 minute between each pulse. This has to be applied for the following phases: 0, 90, 180 and 270°* - DC power lines: ± 0.5 kV test voltage in open circuit between line and earth and ± 0.5 kV between lines (pulse $1.2 \mu\text{s}$ / $50 \mu\text{s}$) with a rise time (T_r) of $1.2 \mu\text{s}$, and a hold time (T_h) of $50 \mu\text{s}$. Each surge shall be applied five times with a maximum delay of 1 minute.*			
	*Strike-through, as appropriate.			
	Test results			
Ann 6, 2.2	Vehicle does not set in motion	☒	☐	☐

APPENDIX 3 - C7

External projections

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 44/2014 Annex VIII
Including amendment (EU) 2018/295
UNECE R26.04

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Radius Gage	- / 1SA24033183621-0029	26/04/2025
Radius Gage	- / 1SA24033183621-0030	26/04/2025
External projection test roller	- / 2SB24033183621-0056	26/04/2026
External projection test ball	- / 1SA24033183621-0054	26/04/2026
External projection test ball	- / 1SA24033183621-0055	26/04/2026

*Specify ~~calibrated date + (interval)~~ or calibration due date.

3. Test results

- 3.1. Vehicle assessment : Vehicle is in a straight line, vertical position as level floor
with 50 percentile rider and steering free to move.
3.2. Group 1 parts: Grazing ($0^\circ \leq \alpha < 45^\circ$) : Conform as per requirements
3.3. Group 1 parts: Collision: ($45^\circ \leq \alpha < 90^\circ$) : Conform as per requirements
3.4. Windscreen : Not applicable
3.5. Covers that resemble windscreens or fairings
installed to protect instrument cluster or head
lamp : Not applicable
3.6. Uncovered levers : Conform as per requirements
3.7. Mudguard : Conform as per requirements
3.8. All others outward pointed and protruding
parts of the vehicles : Conform as per requirements
3.9. Other requirements as per directive
described in this test record : Conform as per requirements

Para.	Requirements	PASS	FAIL	N/A
e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation				
1.	Requirements applying to two-wheel mopeds and two-wheel motorcycles with or without side-car	☐	☐	☒
2	Requirements applying to three-wheel vehicles and quadricycles			
2.1.1.	Vehicles of categories L2e, L5e, L6e and L7e shall meet the following general requirements.			
2.1.1.1.	Vehicles shall incorporate no pointed, sharp or protruding parts, pointing outwards, of such a shape, dimension, angle of direction and hardness that they increase the risk or seriousness of body lesions and lacerations suffered by any person struck or grazed by the vehicle in the event of an accident.	☒	☐	☐
2.1.2.1.	Vehicles shall meet all the relevant requirements of UNECE regulation No 26 as prescribed for vehicle category M1.	☒	☐	☐

UNECE No. 26 - General Requirements

Para.	Requirements	PASS	FAIL	N/A
5.2	The external surface of vehicles shall not exhibit, directed outwards, any pointed or sharp parts or any projections of such shape, dimensions, direction or hardness as to be likely to increase the risk or seriousness of bodily injury to a person hit by the external surface or brushing against it in the event of a collision	☒	☐	☐
5.3	The external surface of vehicles shall not exhibit, directed outwards, any part likely to catch on pedestrians, cyclists or motor cyclists	☒	☐	☐
5.4	No protruding part of the external surface shall have a radius of curvature less than 2.5 mm. This requirement shall not apply to parts of the external surface which protrude less than 5 mm, but the outward facing angles of such parts shall be blunted, save where such parts protrude less than 1.5 mm.	☒	☐	☐
5.5	Protruding parts of the external surface, made of a material of hardness not exceeding 60 shore A, may have a radius of curvature less than 2.5 mm.	☐	☐	☒

Ornaments

6.1.1	Added ornaments which project more than 10mm from their support shall retract, become detached or bend over under a force of 10daN exerted at their most salient point in any direction in a plane approximately parallel to the surface on which they are mounted.	☐	☐	☒
	After the ornaments are retracted, detached or bent over, the remaining projections shall not project more than 10 mm. These projections shall in any case satisfy the provisions of paragraph 5.2. If the ornament is mounted on a base, this base is regarded as belonging to the ornament and not to the supporting surface	☐	☐	☒
6.1.2.	Protective strips or shielding on the external surface shall not be subject to the requirements of paragraph 6.1.1 above; however, they shall be firmly secured to the vehicle	☒	☐	☐

Headlights

6.2.1	Projecting visors and rims shall be permitted on headlights, provided that their projection, as measured in relation to the external transparent surface of the headlight does not exceed 30mm and their radius of curvature is at least 2.5 mm throughout	☒	☐	☐
-------	--	-------------------------------------	--------------------------	--------------------------

Para.	Requirements	PASS	FAIL	N/A
e13*168/2013*02582*00				
Grilles and gaps Société Nationale de Certification et d'Homologation				
6.3.1.	For gaps of between 40 mm and 25 mm the radii of curvature shall be 1 mm or more. However, if the distance between two consecutive elements is equal to or less than 25 mm, the radii of curvature of external faces of the elements shall not be less than 0.5 mm	☐	☐	☒
6.3.2.	The junction of the front with the side faces of each element forming a grille or gap shall be blunted.	☐	☐	☒
Windscreen wipers				
6.4.1.	End surface area of not less than 150 mm ²	☐	☐	☒
	In the case of rounded covers, these shall have a minimum projected area of 150 mm ² when measured not more than 6.5 mm from the point projecting furthest	☐	☐	☒
Bumpers				
6.5.1.	The ends of the bumpers shall be turned in towards the external surface	☒	☐	☐
6.5.2.	If the line of the bumper which corresponds to the outline contour of the car vertical projection is on a rigid surface, that surface shall have a minimum radius of curvature of 5 mm at all its points lying from the contour line to 20 mm inward, and a minimum radius of curvature of 2.5 mm in all other cases.	☒	☐	☐
Handles, hinges and push-buttons of doors, luggage compartments and bonnets; fuel tank filler caps and covers				
6.6.1.	The projection shall not exceed 40 mm in the case of door or luggage compartment handles and 30 mm in all other cases	☐	☐	☒
6.6.2.1.	In the case of handles which rotate parallel to the plane of the door, the open end of handles must be directed towards the rear. The end of such handles shall be turned back towards the plane of the door and fitted into a protective surround or be recessed.	☐	☐	☒
6.6.2.2.	Handles which pivot outwards in any direction which is not parallel to the plane of the door shall, when in the closed position, be enclosed in a protective surround or be recessed. The open end shall face either rearwards or downwards.	☐	☐	☒
	Nevertheless, handles which do not comply with this last condition may be accepted if:	☐	☐	☒
	(a) they have an independent return mechanism,			
	(b) should the return mechanism fail, they cannot project more than 15 mm,			
	(c) they comply, in such opened position, with the provisions of paragraph 5.4., and			
	(d) their end surface area, when measured not more than 6.5 mm from the point projecting furthest, is not less than 150 mm ² .			
Wheels, wheel nuts, hub caps and wheel discs				
6.7.2	The wheels, wheel nuts, hub caps and wheel discs shall not exhibit any pointed or sharp projections that extend beyond the external plane of the wheel rim. Wing nuts shall not be allowed.	☒	☐	☐

Para.	Requirements	PASS	FAIL	N/A
6.7.3.	When the vehicle is travelling in a straight line, no part of the wheels other than the tyres, situated above the horizontal plane passing through their axis of rotation shall project beyond the vertical projection, in a horizontal plane, of the external surface or structure. However, if functional requirements so warrant, wheel discs which cover wheel and hub nuts may project beyond the vertical projection of the external surface or structure on condition that the radius of curvature of the surface of the projecting part is not less than 30mm and that the projection beyond the vertical projection of the external surface or structure in no case exceeds 30mm	☒	☐	☐

Sheet metal edges

6.8.1.	Sheet-metal edges, such as gutter edges and the rails of sliding doors, shall not be permitted unless they are folded back or are fitted with a shield meeting the requirements of this Regulation which are applicable to it.	☐	☐	☒
--------	--	--------------------------	--------------------------	-------------------------------------

Body panels

6.9.1.	Folds in body panels may have a radius of curvature of less than 2.5 mm, provided that it is not less than one tenth of the height "H" of the projection	☐	☐	☒
--------	--	--------------------------	--------------------------	-------------------------------------

Lateral air or rain deflectors

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

6.10.1	Lateral deflectors shall have a radius of curvature of at least 1mm on edges capable of being directed outwards	☐	☐	☒
--------	---	--------------------------	--------------------------	-------------------------------------

Jacking brackets and exhaust pipes

6.11.1	The jacking brackets and exhaust pipe(s) shall not project more than 10 mm beyond the vertical projection of the floor line lying vertically above them As an exception to this requirement an exhaust pipe may project more than 10 mm beyond the vertical projection of the floor line, so long as it terminates in rounded edges, the minimum radius of curvature being 2.5 mm	☐	☐	☒
--------	--	--------------------------	--------------------------	-------------------------------------

Air intake and outlet flaps

6.12.1	Air intake and outlet flaps shall meet the requirements of paragraph 5.2., 5.3. and 5.4. above in all positions of use	☐	☐	☒
--------	--	--------------------------	--------------------------	-------------------------------------

Roof

6.13.1	Opening roofs shall be considered only in the closed position	☐	☐	☒
6.13.2	Convertible vehicles shall be examined with the hood in both the raised and lowered positions	☐	☐	☒

Windows

6.14.	Windows which move outwards from the external surface of the vehicle shall comply with the following provisions in all positions of use: no exposed edge shall face forwards no part of the window shall project beyond the extreme outer edge of the vehicle	☐	☐	☒
-------	---	--------------------------	--------------------------	-------------------------------------

Para.	Requirements	PASS	FAIL	N/A
Registration plate bracket				
6.15.1.	Supporting brackets provided by the vehicle manufacturer for registration plates shall comply with the requirements of paragraph 5.4. of this Regulation if they are contactable by a 100 mm diameter sphere when a registration plate is fitted in accordance with the vehicle manufacturer's recommendation.	☒	☐	☐
Luggage racks and ski racks				
6.16.1.	Luggage racks and ski racks shall be so attached to the vehicle that positive locking exists in at least one direction and that horizontal, longitudinal and transverse forces can be transmitted which are at least equal to the vertical load-bearing capacity of the rack as specified by its manufacturer.	☐	☐	☒
6.16.2.	Surfaces which, after installation of the rack, can be contacted by a sphere of 165 mm diameter shall not have parts with a radius of curvature less than 2.5 mm, unless the provisions of paragraph 6.3. can be applied.	☐	☐	☒
6.12.3.	Fastening elements such as bolts that are tightened or loosened without tools shall not project more than 40 mm beyond the surfaces referred to in 6.16.2.	☐	☐	☒
Aerials				
6.17.1.	Radio receiving and transmitting aerials shall be fitted to the vehicle in such a way that if their unattached end is less than 2 m from the road surface in any position of use specified by the manufacturer of the aerial, it shall be inside the zone bounded by the vertical planes which are 10 cm inside the extreme outer edge of the vehicle	☐	☐	☒
6.17.2.	Furthermore, aerials shall be so fitted to the vehicle, and if necessary their unattached ends so restricted, that no part of the aerials protrude beyond the extreme outer edge of the vehicle	☐	☐	☒
6.17.3.	Shafts of aerials may have radii of curvature of less than 2.5 mm. However, the unattached ends shall be fitted with fixed cappings, the radii of curvature of which are not less than 2.5 mm.	☐	☐	☒
6.17.4.	The bases of aerials shall not project more than 40 mm	☐	☐	☒
6.17.4.1.	In cases where by the absence of a flexible shaft or part it is not possible to identify what the base is of an aerial this requirement is deemed to be met if, after a horizontal force of not more than 50 daN in forward and rearward direction is applied by a flatended ram of not more than 50 mm diameter at the most salient part of the aerial: (a) the aerial bends towards the support and does not project more than 40 mm, or (b) the aerial breaks off and the remaining part of the aerial does not show any sharp or dangerous part that can be contacted by the 100 mm sphere and does not project more than 40 mm.	☐	☐	☒
6.17.4.2.	Paragraphs 6.17.4. and 6.17.4.1. shall not apply to aerials located behind the vertical transversal plane passing through the "R" point of the driver, provided that the maximum projection of the aerial including its housing does not exceed 70 mm. If the aerial is located behind that vertical plane but projects more than 70 mm, paragraph 6.17.4.1. shall apply using a projection limit of 70 mm instead of 40 mm	☐	☐	☒

APPENDIX 3 - C10 Masses and dimensions

0. Main Requirements

0.1. Requirements according to : Reg. (EU) 44/2014 Annex XI
Including amendment (EU) 2018/295

1. Witness details

1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

2.1 Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Tape measure	- / 1SA24033183621-0027	26/04/2025
Electronic platform scale	- / 2SB24033183621-0018	26/04/2025
Electronic platform scale	- / 2SB24033183621-0019	26/04/2025
Electronic platform scale	- / 2SB24033183621-0020	26/04/2025
Electronic platform scale	- / 2SB24033183621-0021	26/04/2025
Steel angle ruler	- / 1SA24033183621-0040	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

MASSES	Measured (kg)	Declared (kg)	Limit	Comply (Yes / No)
In running order	173	173	5%	Yes
Actual Mass	280	280	5%	Yes
Technically permissible mass	310	310	--	Yes
Maximum payload	30	30	--	Yes

Dimension	Measured (mm)	Declared (mm)	Limit (mm)	% between the declared and tested (< 3 %)	Comply (Yes / No)
Length	1818	1818	4000	< 3 %	Yes
Width	918	918	2000	< 3 %	Yes
Height	1325	1325	2500	< 3 %	Yes
Wheelbase	1257	1257	--	< 3 %	Yes
Ground clearance	--	--	≥ 310 (L3e-AxE) ≥ 280 (L3e-AxT)	< 3 %	N/A
Length loading bed	--	--	N/A	N/A	N/A
Width loading bed	--	--	N/A	N/A	N/A

APPENDIX 3 – C11

Functional on-board diagnostics (OBD)

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 44/2014 Annex XII
Including amendment (EU) 2018/295

1. Witness details

- 1.1. Witness : Wang Liming
- 1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu Road, Chongfu,
Tongxiang, Jiaxing, Zhejiang, China
- 1.3. Date of test : 01/03/2025
- 1.4. Worst Case Rationale : Single specification
- 1.5. Tested Vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
- 2.2. All instruments are equipped with
identification label : Yes
- 2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
OBD Scanner	MST-500Pro / ---	---

*Specify calibrated date + (interval) or calibration due date.

3.1. List of main applicable functions and associated requirements according with numbering of annex XII of Regulation EU 44/2014 including last amendment Regulation EU 2018/295.

- 3.1.1. 2.3.1. The electric circuit and electronic failure
diagnostics with regard to OBD stage I and/or II
shall at a minimum contain the sensor and
actuator diagnostics as well as the internal
diagnostics of the electronic control units listed
in Appendix 2 of annex XII of Regulation EU
44/2014 including last amendment Regulation
EU 2018/295 : Conform

Device circuit tested	Level required	Circuit continuity tested			Circuit rationality tested			Device not present recorded	MI activation criteria witnessed
		Circuit low	Circuit high	Open circuit	Out of range	Performance / plausibility	Signal stuck		
Throttle	1	P0122	P0123	P0120	-	-	-	-	-
Drive motor control module	1	-	-	U0110	-	-	-	-	-
Drive motor temperature	1	P0A2C	P0A2D	-	-	-	-	-	-
System voltage	1	P0562	P0563	-	-	-	-	-	-

3.1.2. 3.2.1. Temporary disablement of the OBD system : Conform

3.1.3. 3.5.3. The MI shall operate in a distinct warning mode, e.g. a flashing light, during any period in which engine misfire occurs at a level likely to cause catalyst damage, as specified by the manufacturer. : Conform

3.1.4. 3.6.1. The distance travelled by the vehicle while the MI is activated shall be available at any moment through the serial port on the standardised diagnostic connector : Conform

3.1.5. 3.1., appendix 1. Upon determination of the first malfunction of any component or system, 'freeze-frame' engine conditions present at the time shall be stored in computer memory. Stored engine conditions shall include, but are not limited to, calculated load value, engine speed, fuel trim value(s) (if available), fuel pressure (if available), vehicle speed (if available), coolant temperature, intake manifold pressure (if available), closed- or open-loop operation (if available) and the fault code which caused the data to be stored. : Conform

3.1.6. 3.5., appendix 1. The software identification and calibration verification numbers shall be made available through the serial port on the standardized diagnostic connector. Both numbers shall be provided in a standardized format. : Conform

- | | | | |
|----------|--|---|----------------|
| 3.1.7. | The connection interface between the vehicle and the diagnostic tester is according to point 3.12 of appendix 1. | : | Conform |
| 3.1.7.1. | Until an OBD stage II system for L-category vehicle has been implemented on the vehicle, an alternative connection interface may be installed at the request of the vehicle manufacturer according to point 3.13 of appendix 1. | : | Not applicable |
| 3.1.8. | 4.6., appendix 1. The OBD system shall report in accordance with the ISO 15031-5:2011 specifications the ignition cycle counter and general denominator as well as separate numerators and denominators for the monitors listed at point 4.6 of appendix 1, if their presence on the vehicle is required. Applicable to OBD stage II only. | : | Not applicable |

APPENDIX 3 – C12

Passenger handholds and footrests

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 44/2014 Annex XIII
Including amendment (EU) 2018/295

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 13/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Load sensor	2112-Y820256 / 2SB24033183621-0023	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

3. Passenger handholds and footrests specification

- 3.1. Type and number of driver footrest : Floor board, Refer to Drawing No. Steinadler Pro-36-01
3.2. Type and number of passenger handhold : Not applicable
3.3. Type and number of passenger footrest : Not applicable

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

	PASS	FAIL	N/A
1.2. For vehicles designed to carry one or more passengers but not equipped with safety belts for those passengers, the seating positions in question are fitted with a passenger handhold system consisting of either a strap, or one or two hand-grip bars.	☐	☐	☒
1.2.1. Strap is easily used by the passenger.	☐	☐	☒
Strap withstood a vertical traction force of 2,000 N (load).	☐	☐	☒
Pressure (maximum 2 Mpa) (Force/area)	☐	☐	☒

		PASS	FAIL	N/A
1.2.2.	Hand-grip is close to the saddle and symmetrical to the median longitudinal plane of the vehicle.	☐	☐	☒
	Hand-grip withstood a vertical traction force of 2000 N (load).	☐	☐	☒
	Pressure (maximum 2 Mpa).	☐	☐	☒
1.2.3.	If two hand-grips are used, they are fitted one on each side in a symmetrical manner.	☐	☐	☒
	Hand-grip withstood a vertical traction force of 1,000 N.	☐	☐	☒
	Pressure: Maximum 1 Mpa each			
1.2.4.	Design features of the vehicle, which could be confused with the designated passenger handhold system, are not permitted, unless they also meet the requirements of points 1.2.1 to 1.2.3.	☐	☐	☒
1.3.	All seating positions of the vehicle are fitted either with designated footrests, or a floor or floor boards on which both of the rider's, driver's, or passenger's feet can rest.	☒	☐	☐
1.3.1.	Vehicle's floor, each designated floor board and each designated footrest are capable of withstanding, without any resulting permanent deformation that is harmful to its function, a vertical compression force of 1,700 N, applied statically to any point on the floor or floor board, or 15 mm from the end of the footrest, at a maximum pressure of 2.0 MPa.	☒	☐	☐
1.3.2.	Space provided by each designated footrest, including the space on the floor or floor board, is sufficient for a foot ≥ 300 mm long and ≥ 110 mm wide to be placed safely without hampering the vehicle operator's feet. Footrests are located so that no direct contact between the foot/leg and rotating parts (e.g. tyres) of the vehicle is possible when in use.	☒	☐	☐
1.3.3.	Design features of the vehicle, which could be confused with the designated footrests, floor boards or vehicle floor are not permitted, unless they also meet the requirements of points 1.3.1 to 1.3.2.	☒	☐	☐
1.3.4.	Pedals enabling the vehicle to be propelled by the rider's muscular leg power are deemed to meet the requirements of points 1.3 to 1.3.3	☐	☐	☒

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

APPENDIX 3 – C13

Registration plate space

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 44/2014 Annex XIV
Including amendment (EU) 2018/295

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Digital display angle meter	60136CF / 1SA24033183621-0033	26/04/2025
Tape	- / 1SA24033183621-0027	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

		PASS	FAIL	N/A
1.2.	Vehicles are equipped with a space for mounting and fixing rear registration plates.	☒	☐	☐
1.3.	Vehicles of categories L6e and L7e are, in addition, equipped with a space for mounting and fixing front registration plates.	☒	☐	☐
1.4.1.	Space for mounting comprises of a rectangular area with the following minimum dimensions:	☒	☐	☐
	For vehicles of categories L1e, L2e and L6e:	☐	☐	☒
	Width: 100 mm; Height: 175 mm*			
	Width: 145 mm; Height: 125 mm*			
	*Strikethrough, as appropriate.			
	For vehicles of categories L3e, L4e, L5e and L7e:	☒	☐	☐
	- Width: 280 mm; Height: 200 mm			

PASS FAIL N/A

Mounting and Fixing of a Rear Registration Plate on Vehicles of Categories L1e, L2e, L3e, L4e and L5e

1.5.1.1.1.	Space for mounting a registration plate at the rear of the vehicle is such that the plate can be positioned entirely within the two parallel longitudinal vertical planes passing through the outer extremities of the vehicle, not taking into account any rearview mirrors. The space itself does not form the widest point of the vehicle.	☐	☐	☒
1.5.1.2.	Plate is perpendicular to the longitudinal median plane of the vehicle.	☐	☐	☒
1.5.1.3.1.	Plate may be inclined to the vertical at $\geq -15^\circ$ and $\leq 30^\circ$.	☐	☐	☒
1.5.1.4.1.	Lower edge of the plate is ≥ 0.20 m above the ground or not less than the radius of any rear wheel above the ground if that is less than 0.20 m.	☐	☐	☒
1.5.1.4.2.	Height of the upper edge of the plate from the ground does not exceed 1.50 m.	☐	☐	☒
1.5.1.5.1.	Plate is visible in the whole space within the following four planes: — Two vertical planes touching the two lateral edges of the plate and forming an angle measured outwards to the left and to the right of the plate of 30° to the longitudinal plane, parallel to the longitudinal median plane of the vehicle, passing through the centre of the plate; — Plane touching the upper edge of the plate and forming an angle measured upwards of 15° to the horizontal; — Horizontal plane through the lower edge of the plate.	☐	☐	☒
1.5.1.5.2.	No structural element, even when fully transparent, is located in the space described above.	☐	☐	☒
1.6.	Mounting and fixing of front and rear registration plates on vehicles of categories L6e and L7e			
1.6.1	The space for mounting a front or rear registration plate shall comprise a flat or virtually flat rectangular surface. A "virtually flat surface" means a surface of solid material, which may also consist of patterned mesh or grille, with a radius of curvature of at least 5000mm	☒	☐	☐
1.6.2.	The surface to be covered by a front or rear registration plate may have holes or gaps; however, these shall be no more than 40mm wide without having to take into account their length	☒	☐	☐
1.6.3.	The surface to be covered by a front or rear registration plate may have a protrusion, provided that these do not project more than 5,0 mm from the nominal surface. Patches of very soft materials, such as foam or felt to stop the registration plate vibrating, shall not be taken into account.	☒	☐	☐
1.6.4.1.1	The space for mounting a registration plate at the front of the vehicle shall be such that the plate can be positioned entirely within the two parallel longitudinal vertical planes passing through the outer extremities of the vehicle, not taking into account any rear-view mirrors. The space itself shall not form the widest point of the vehicle.	☒	☐	☐
1.6.4.1.2	The space for mounting a registration plate at the rear of the vehicle shall be such that the plate can be positioned entirely within the two parallel longitudinal vertical planes passing through the outer extremities of the vehicle, not taking into account any rear-view mirrors. The space itself shall not form the widest point of the vehicle.	☒	☐	☐
1.6.4.1.3	Front and rear registration plates shall be perpendicular to the longitudinal median plane of the vehicle	☒	☐	☐
1.6.4.2.1	The plate may be inclined to the vertical at not less than -15° and not more than 30° .	☒	☐	☐

		PASS	FAIL	N/A
1.6.4.3.1	The lower edge of the plate shall not be less than 0,20 m above the ground or less than the radius of any front wheel above the ground if that is less than 0,20 m	☒	☐	☐
1.6.4.3.2	The height of the upper edge of the plate from the ground surface shall not exceed 1,50 m.	☒	☐	☐
1.6.4.4.1	Front and rear plates shall be visible in the whole space within the following four planes: - the two vertical planes touching the two lateral edges of the plate and forming an angle measured outwards to the left and to the right of the plate of 30° to the longitudinal median plane of the vehicle, - the plane touching the upper edge of the plate and forming an angle measured upwards of 15° to the horizontal, - the horizontal plane through the lower edge of the plate.	☒	☐	☐
1.6.4.4.2.	No structural element, even when fully transparent, shall be located within the space described above.	☒	☐	☐
1.6.4.5	The gap between the edges of a mounted and fixed registration plate and the actual surface of the plate space shall not exceed 5,0 mm along the complete outline of the plate.	☒	☐	☐
1.6.4.5.1	This gap may be exceeded if measured at a hole or gap in the surface of patterned mesh or between parallel bars in a surface of a grille.	☒	☐	☐
Other Requirements				
1.7.1.	Presence of a registration plate may not form the basis or part of the basis for attaching, mounting, or clipping any other vehicle part, component or device onto it (e.g. lighting device supports may not be fixed onto a registration plate).	☒	☐	☐
1.7.2.	No vehicle part, component or device becomes loosened or detached as a result of removal of a registration plate.	☒	☐	☐
1.7.3.	When a registration plate is fixed, its visibility is not reduced under normal conditions of use due, in particular, to vibrations and dynamic forces, such as driving wind forces.	☒	☐	☐
1.7.4.	It is not permitted to provide a registration plate mounting location that can easily pivot up and/or down beyond the angles laid down in paragraphs 1.5.1.3.1 and 1.6.4.2.1, in relation to the vehicle structure in normal driving conditions (i.e. with doors or access panels closed).	☒	☐	☐
1.7.5.	If the vehicle has the tendency to lean, a mounted registration plate of the applicable maximum dimensions, which is not located in the longitudinal median plane of the vehicle, is not the limiting factor of the maximum lean angle.	☒	☐	☐

APPENDIX 3 – C14

Access to repair and maintenance information

0. Main Requirements

- | | | | |
|------|---------------------------|---|---|
| 0.1. | Requirements according to | : | Reg. (EU) 44/2014 Annex XV
Including amendment (EU) 2018/295 |
|------|---------------------------|---|---|

1. Witness details

- | | | | |
|------|--------------|---|----------------|
| 1.1. | Witness | : | Not applicable |
| 1.2. | Date of test | : | Not applicable |

2. Test results

- | | | | |
|-------|---|---|--|
| 2.1. | The manufacturers certificate on access to vehicle OBD stage I and vehicle repair and maintenance information | : | The manufacturers certificate providing proof of compliance to the type-approval authority on access to vehicle on-board diagnostic (OBD) systems and to vehicle repair and maintenance information as referred to in Article 57(8) of Regulation (EU) No 168/2013 and set out in Annex III to Regulation (EU) No 901/2014 is provided |
| 2.2. | Access to vehicle OBD and vehicle repair and maintenance information (website) | : | https://rjtech-offroad.com/ |
| 2.2.1 | Date from which it is available | : | 6 months from the date of type approval |
| 2.2.2 | Terms and conditions of access | : | according to point 3 of Annex XV to this Regulation |
| 2.2.3 | Format of vehicle repair and maintenance information accessible through website | : | according to Appendix 1 of Annex XV to this Regulation |
| 2.3. | Service parts, diagnostic tools and test equipment | : | The manufacturer makes the necessary information in the context of Article 57 (6) of Regulation (EU) No 168/2013 available to interested parties on the basis of individual arrangements to which the principle of Article 59 of Regulation (EU) No 168/2013 apply and to provide contact details on its website |
| 2.4. | Multi-stage type approval | : | Not applicable |
| 2.5. | Small volume manufacturers | : | Not applicable |

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

APPENDIX 3 – D1

Statutory plate

0. Main Requirements

- 0.1. Requirements according to : Reg. (EU) 901/2014 Annex V
Including amendment (EU) 2020/239

1. Witness details

- 1.1. Witness : Wang Liming
1.2. Location of test : Zhejiang Huachen Inspection and Testing Co., Ltd.
Building 23, No.1336, Hangfu road, Chongfu, Tongxiang,
Jiaxing, Zhejiang, China
1.3. Date of test : 01/03/2025
1.4. Worst Case Rationale : Single specification
1.5. Tested vehicle : 00/00

2. Facility and Equipment Checks

- 2.1. Calibration certificates checked and valid,
recorded in the following table : Conform
2.2. All instruments are equipped with
identification label : Yes
2.3. Calibration certificates are complete of
calibration-chain with detailed information
regarding primary used. : Yes

Equipment	Serial / Certificate No.	Calibration due*
Ruler	- / 1SA24033183621-0038	26/04/2025
Vernier caliper	20105008 / 2SB24033183621-0036	26/04/2025
Tape	- / 1SA24033183621-0027	26/04/2025

*Specify calibrated date + (interval) or calibration due date.

3. Test results

- 3.1. Positioning of statutory plate : As described on information document of manufacturer.
See drawing No. Steinadler Pro-01-01
3.2. Height of characters [mm] : Statutory plate: 4
VIN: 8
See drawing No. Steinadler Pro-01-01,
Steinadler Pro-02-01
3.3. Material of statutory plate : Metal
3.4. Requirements as per directive described in
this test record : Conform

Remarks

None

Note: CETOC TS apply measurement uncertainty to calibrated items but not test results.

INFORMATION FOLDER

A List of contents

A list of contents	1 page
Information folder sheet	2 pages
Information document	30 pages
Relevant drawings as required in the information document	41 pages
Manufacturer's statement on endurance testing.....	1 page
Manufacturer's statement on structure integrity	1 page
Manufacturer's certificate on access to vehicle OBD (stage I) and vehicle repair and maintenance information	4 pages
Manufacturer's declaration on powertrain tampering prevention measures	2 pages
Statement concerning authority of signature on CoC paper	1 page
Model for the certificate of conformity	2 pages

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information on the type-approval procedure chosen in accordance with Article 25(1) of Regulation (EU) No 168/2013

Information folder sheet

The undersigned : Ms. Shanshan Wang, General Manager

Company name and address of the manufacturer : Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Zone B, 528, Huilong South Rd, Rucheng Street, Rugao City,
Jiangsu Province, China

Hereby applies for type-approval procedure : ~~(a) Step-by-step type-approval~~
(b) Single-step type-approval
~~(c) Mixed type-approval~~

Multi-stage type-approval chosen in accordance
with Article 25(5) of Regulation (EU) No
168/2013 : No

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

Information on the vehicle(s) to be filled in, if application is for EU whole-vehicle type-approval

0.1. Make :  (RJTech)

0.2. Type : Steinadler Pro

0.2.1. Variant : 00

0.2.2. Version : 00

0.2.3. Commercial name(s) (if available) : Steinadler Pro (L7e)

0.3. Category, subcategory and sub-
subcategory of vehicle : L7e-A1

Information to be filled in, if application is for type-approval of a system/ component/ separate technical unit

0.7. Make(s) (trade name(s) of manufacturer) : Not applicable

0.8. Type : Not applicable

0.8.1. Commercial name(s) (if available) : Not applicable

1.6. Virtual and/or self-testing

1.6.1. Overview list with virtual and/or self-tested systems, components or separate technical units pursuant to point 6 of Annex III to Commission Delegated Regulation (EU) No 44/2014 below:

Delegated act	Annex	Subject	Virtual and/or self-tested
Commission Delegated Regulation (EU) No 134/2014	X	Testing procedures on maximum design vehicle speed	Self-testing: no
Commission Delegated Regulation (EU) No 3/2014	II	Audible warning devices	Self-testing: no

Jiangsu YINGUAN Intelligence Technology Co., Ltd.


Commission Delegated Regulation (EU) No 3/2014	VIII	Driver-operated controls including identification of controls, tell-tales and indicators	Self-testing: no
Commission Delegated Regulation (EU) No 3/2014	IX	Installation of lighting and light-signalling devices	Virtual testing: no
Commission Delegated Regulation (EU) No 3/2014	X	Rearward visibility	Virtual testing: no
Commission Delegated Regulation (EU) No 3/2014	XV	Installation of tyres	Virtual testing: no
Commission Delegated Regulation (EU) No 44/2014	XIV	Registration plate space	Self & Virtual testing: no
Commission Delegated Regulation (EU) No 44/2014	XVI	Stands	Self-testing: no
Commission Implementing Regulation (EU) No 901/2014	V	Statutory plate and EU type-approval mark	Self-testing: no

1.6.2. Detailed report on validation of virtual and/or self-testing added : No

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

Jiangsu Province, China
(place)

22/02/2025
(date)





(Signature)

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

SUBJECT: QUADRICYCLE TYPE “Steinadler Pro”

Variant(s) and Version(s) matrix:

Type	Variant	Version	Max. Speed	30 minutes power	Electric motor type	Controller	Battery	Brake system
Steinadler Pro	00	00	70 km/h	6 kW (1.5 kW × 4)	QS60V1 500W	Main: RJ-VCU-EVA20 Four sub: DEMCS0604QS05L	Lithium battery: 74.4V, 55Ah	CBS (Parking braking + CBS + Front secondary braking + Rear secondary braking)

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Document extension:

Extension Index	Revision	Application Date	Reasons for revision/extension
00	00	22/02/2025	New approval

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

INFORMATION DOCUMENT FOR THE PURPOSE OF EC TYPE-APPROVAL OF VEHICLES

According to Regulation (EU) number 168/2013*2024/2847
and Commission implementing Regulation (EU) number 901/2014*2020/239

Item No	(Sub) categories	Detailed information	
0.		GENERAL INFORMATION	e13*168/2013*02582*00
A.		General information concerning vehicles	Société Nationale de Certification et d'Homologation
0.1.	L1e-L7e	Make (trade name of manufacturer)	:  (RJTech)
0.2.	L1e-L7e	Type ⁽¹⁷⁾	: Steinadler Pro
0.2.1.	L1e-L7e	Variant(s) ⁽¹⁷⁾	: 00
0.2.2.	L1e-L7e	Version(s) ⁽¹⁷⁾	: 00
0.2.3.	L1e-L7e	Commercial name(s) (if available)	: Steinadler Pro (L7e)
0.3.	L1e-L7e	Category, subcategory and sub-subcategory of vehicle ⁽²⁾	: L7e-A1
0.4.	L1e-L7e	Company name and address of manufacturer	: Jiangsu YINGUAN Intelligence Technology Co., Ltd. Zone B, 528, Huilong South Rd, Rucheng Street, Rugao City, Jiangsu Province, China
0.4.1.	L1e-L7e	Name(s) and address(es) of assembly plants	: Jiangsu YINGUAN Intelligence Technology Co., Ltd. Building 1, No. 1289, Duhui Rd, Minhang District, Shanghai, China
0.4.2.	L1e-L7e	Name and address of manufacturer's authorized representative, if any	: Benlinq Henegouwenlaan 28, 1966RK Heemskerk, Netherlands
0.5.	L1e-L7e	Manufacturer's statutory plate(s)	
0.5.1.	L1e-L7e	Location of the manufacturer's statutory plate ⁽¹⁵⁾ ⁽¹⁸⁾	: R, x 1000, y 245, z 470
0.5.2.	L1e-L7e	Method of attachment	: By riveted
0.5.3.	L1e-L7e	Photographs and/or drawings of the statutory plate (completed example with dimensions)	: Refer to drawing No. Steinadler Pro-01-01
0.6.	L1e-L7e	Location of the vehicle identification number ⁽¹⁵⁾	: R, x 460, y 240, z 240
0.6.1.	L1e-L7e	Photographs and/or drawings of the locations of the vehicle identification number (completed example with dimensions)	: Refer to drawing No. Steinadler Pro-02-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
0.6.1.1.	L1e-L7e	The serial number of the type begins with : ☆H2XAAAVC??1?????☆ Refer to drawing No. Steinadler Pro-02-01
B.		General information concerning systems, components or separate technical units : Not applicable
C.		General information regarding conformity of production and access to repair and maintenance information e13*168/2013*02582*00
0.12.		Conformity of production Société Nationale de Certification et d'Homologation
0.12.1.	L1e-L7e	Description of overall quality-assurance : Conforms to ISO9001: 2015 quality management system and EEC requirements.
0.13.		Access to repair and maintenance information
0.13.1.	L1e-L7e	Address of principal website for access to vehicle repair and maintenance information : https://rjtech-offroad.com/ Information available within six months from the date of type approval. See regulation (EU) No 168/2013, Article 57, paragraph 8
0.13.2.	L1e-L7e	In the case of multi-stage type-approval, address of principal website for access to vehicle repair and maintenance information from manufacturer(s) at previous stage(s) : Not applicable
1.		GENERAL CONSTRUCTION CHARACTERISTICS
1.1.	L1e-L7e	Photographs and/or drawings of a representative vehicle : Refer to drawing No. Steinadler Pro-03-01
1.2.	L1e-L7e	Scale drawing of the whole vehicle : Refer to drawing No. Steinadler Pro-03-01
1.3.	L1e-L7e	Number of axles and wheels : 2 axles / 4 wheels
1.3.1.	L1e-L7e	Axles with twinned wheels ⁽²³⁾ : Not applicable
1.3.2.	L1e-L7e	Powered axles ⁽²³⁾ : Four-wheel drive: F & R (front and rear)
1.4.	L1e-L7e	Chassis (if any) (overall drawing) : Refer to drawing No. Steinadler Pro-04-01
1.5.	L2e, L5e-B, L6e-B, L7e-A2, L7e-B2, L7e-C	Material used for the bodywork : Steel
1.6.	L1e-L7e	Position and arrangement of the propulsion(s) : Refer to drawing No. Steinadler Pro-05-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
1.7.	L4e, L5e-B, L6e-B, L7e-A2, L7e-B2, L7e-C	Hand of drive : left/right /centre ⁽⁴⁾
1.7.1.	L1e-L7e	Vehicle is equipped to be driven in right/left-hand traffic and in countries that use metric/metric and imperial units ⁽⁴⁾ : Right-hand traffic, metric unit
1.8.		Propulsion unit performance
1.8.1.	L3e, L4e, L5e, L7e-A, L7e-B2	Declared maximum vehicle speed : 70 km/h
1.8.2.	L1e, L2e, L6e, L7e-B1, L7e-C	Maximum design vehicle speed ⁽²²⁾ : Not applicable
1.8.3.	L1e-L7e	Maximum net power combustion engine : Not applicable
1.8.4.	L1e-L7e	Maximum net torque combustion engine : Not applicable
1.8.5.	L1e-L7e	Maximum continuous-rated power electric motor (45/30 ⁽⁴⁾ minutes power ⁽²⁷⁾) : 1.5 kW at 785 min ⁻¹ (Each motor)
1.8.6.	L1e-L7e	Maximum continuous-rated torque electric motor : 18.3 N.m at 785 min ⁻¹ (Each motor)
1.8.7.	L1e-L7e	Maximum continuous total power for propulsion(s) : 6.0 kW at 785 min ⁻¹
1.8.8.	L1e-L7e	Maximum continuous total torque for propulsion(s) : 73.2 N.m at 785 min ⁻¹
1.8.9.	L1e-L7e	Maximum peak power for propulsion(s) : 3.5 kW at 870 min ⁻¹ (Each motor)
2.		MASSES AND DIMENSIONS (In kg and mm.) refer to drawings where applicable
2.1.		Range of vehicle mass (overall)
2.1.1.	L1e-L7e	Mass in running order : 173 kg
2.1.1.1.	L1e-L7e	Distribution of mass in running order between the axles : Front: 96 kg Rear: 77 kg
2.1.2.	L1e-L7e	Actual mass : 280 kg
2.1.2.1.	L1e-L7e	Distribution of actual mass between the axles : Front: 138 kg Rear: 142 kg
2.1.3.	L1e-L7e	Technically permissible maximum laden mass : 310 kg

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
2.1.3.1.	L1e-L7e	Technically permissible maximum mass : 150 kg on front axle
2.1.3.2.	L1e-L7e	Technically permissible maximum mass : 160 kg on rear axle
2.1.3.3.	L4e	Technically permissible maximum mass : Not applicable on sidecar axle
2.1.4.	L1e-L7e	Maximum hill-starting ability at the : 35° slope maximum technically permissible mass declared by the manufacturer
2.1.5.	L1e-L7e	Maximum pay mass declared by : 30 kg manufacturer
2.1.6.	L1e-L7e	Safe load carrying capacity of load : Not applicable platform declared by manufacturer
2.1.7.	L1e-L7e	Technically permissible maximum : Not applicable towable mass in case of ⁽⁴⁾
2.1.7.1.	L1e-L7e	Technically permissible maximum laden : Not applicable mass of the combination
2.1.7.2.	L1e-L7e	Technically permissible maximum mass : Not applicable at the coupling point
2.1.8.	L1e-L7e	Mass of the optional equipment : Not applicable
2.1.9.	L1e-L7e	Mass of the superstructure : Not applicable
2.1.10.	L1e-L7e	Mass of the propulsion battery : 32 kg
2.1.11.	L2e, L4e, L5e, L6e, L7e	Mass of the doors : Not applicable
2.1.12.	L2e-U, L5e-B, L6e-BU, L7e-CU	Mass of the machines or equipment : Not applicable installed on the load platform area
2.1.13.	L1e-L7e	Mass of the gaseous fuel system as well : Not applicable as storage tanks for gaseous fuel
2.1.14.	L1e-L7e	Mass of the storage tanks to store : Not applicable compressed air
2.2.		Range of vehicle dimensions (overall)
2.2.1.	L1e-L7e	Length : 1818 mm
2.2.2.	L1e-L7e	Width : 918 mm
2.2.3.	L1e-L7e	Height : 1325 mm

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
2.2.4.	L1e-L7e	Wheelbase : 1257 mm
2.2.4.1.	L4e	Wheelbase sidecar ⁽²⁸⁾ : Not applicable
2.2.5.		Track width
2.2.5.1.	L1e-L7e if equipped with twinned wheels L2e, L4e, L5e, L6e, L7e	Track width front : 734 mm e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
2.2.5.2.	L1e-L7e if equipped with twinned wheels	Track width rear : 712 mm
2.2.5.3.	L2e, L4e, L5e, L6e, L7e	Track with sidecar : Not applicable
2.2.6.	L7e-B	Front overhang : Not applicable
2.2.7.	L7e-B	Rear overhang : Not applicable
2.2.8.		Load platform dimensions
		From 2.2.8.1. to 2.2.8.3. : Not applicable
2.2.9.		Centre of gravity
		From 2.2.9.1. to 2.2.9.3. : Not applicable
2.2.10.		Miscellaneous dimensions
		From 2.2.10.1. to 2.2.10.10. : Not applicable
3.		GENERAL POWERTRAIN CHARACTERISTICS
3.1.		Manufacturer of the propulsion unit
3.1.1.		<i>Combustion engine</i> : Not applicable
3.1.2.		<i>Electric motor</i>
3.1.2.1.	L1e-L7e	Manufacturer : TAIZHOU QUANSHUN ELECTRIC DRIVE TECHNOLOGY CO., LTD. Make: QSMOTOR
3.1.2.2.	L1e-L7e	Electric motor code (as marked on the engine or other means of identification) : QS60V1500W
3.1.3.		<i>Hybrid application</i> : Not applicable

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
3.2.		Combustion engine : Not applicable
3.3.		Pure electric and hybrid electric propulsion and control
3.3.1.	L1e-L7e	Electric vehicle configuration : pure electric/ hybrid electric/manpower electric ⁽⁴⁾
3.3.2.	L1e-L7e	Brief description and schematic drawing of pure and hybrid electric propulsions and its control system(s) : Refer to drawing No. Steinadler Pro-05-01, Steinadler Pro-06-01, Steinadler Pro-07-01
3.3.3.		<i>Electric propulsion motor</i> e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
3.3.3.1.	L1e-L7e	Number of electric motors for propulsion : 4
3.3.3.2.	L1e-L7e	Type (winding, excitation) : Winding
3.3.3.3.	L1e-L7e	Operating voltage : 74.4 V
3.3.3.4.	L1e-L7e	15/30 ⁽⁴⁾ minutes power ⁽²⁷⁾ : 1.5 kW (Each motor)
3.3.4.		<i>Propulsion batteries</i>
3.3.4.1.	L1e-L7e	Primary propulsion battery
3.3.4.1.1.	L1e-L7e	Number of cells : 20
3.3.4.1.2.	L1e-L7e	Mass : 32 kg
3.3.4.1.3.	L1e-L7e	Capacity : 55 Ah
3.3.4.1.4.	L1e-L7e	Voltage : 74.4 V
3.3.4.1.5.	L1e-L7e	Position in the vehicle : Refer to drawing No. Steinadler Pro-08-01
3.3.4.2.	L1e-L7e	Secondary propulsion battery
3.3.4.2.1.	L1e-L7e	Number of cells : Not applicable
3.3.4.2.2.	L1e-L7e	Mass : Not applicable
3.3.4.2.3.	L1e-L7e	Capacity : Not applicable
3.3.4.2.4.	L1e-L7e	Voltage : Not applicable
3.3.4.2.5.	L1e-L7e	Position in the vehicle : Not applicable
3.3.5.		<i>Hybrid electric vehicle</i> : Not applicable
3.3.6.		<i>Energy storage device</i>
3.3.6.1.	L1e-L7e	Description : (battery, capacitor, flywheel/generator) ⁽⁴⁾
3.3.6.2.	L1e-L7e	Identification number : 55Ah
* 3.3.6.3.	L1e-L7e	Kind of electrochemical couple : Lithium battery

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
3.3.6.4.	L1e-L7e	Energy (for battery: voltage and capacity Ah in 2h, for capacitor: J,..., for flywheel/generator: J,...,) : 74.4 V, 55 Ah
3.3.6.5.	L1e-L7e	Charger : on-board /external/without ⁽⁴⁾ Refer to drawing No. Steinadler Pro-48-01, Steinadler Pro-49-01
3.3.7.		<i>Electric motor (describe each type of electric motor separately)</i>
3.3.7.1.	L1e-L7e	Primary use : Propulsion motor/ generator ⁽⁴⁾
3.3.7.2.	L1e-L7e	When used as propulsion motor: single-/multi-motors (number: 4) ⁽⁴⁾ : single -multi-motors (number: 4) ⁽⁴⁾
3.3.7.3.	L1e-L7e	Working principle : Permanent magnet brushless DC motor
3.3.7.4.	L1e-L7e	Direct current/alternating current /number of phases : Direct current / three phases
3.3.7.5.	L1e-L7e	Separate excitation/series/compound ⁽⁴⁾ : Separate excitation
3.3.7.6.	L1e-L7e	Synchronous/asynchronous ⁽⁴⁾ : Synchronous
3.3.8.		<i>Electric motor control unit</i>
3.3.8.1.	L1e-L7e	Identification number : Main controller: RJ-VCU-EVA20 Sub controller: DEMCS0604QS05L Refer to drawing No. Steinadler Pro-06-01, Steinadler Pro-06-02
3.3.9.		<i>Power controller</i>
3.3.9.1.	L1e-L7e	Identification number : Not applicable
3.4.		Other engines, electric motors or combinations (specific information concerning the parts of these motors)
		From 3.4.1. to 3.4.2.5.1. : Not applicable
3.5.		Drive-train and control ⁽¹³⁾
3.5.1.	L1e-L7e	Brief description and schematic drawing of the vehicle drive-train and its control system (gear shift control, clutch control or any other element of drive-train) : The type of transmission is wheel-hub motor, there is no gear shift control and no clutch control.
3.5.2.		<i>Clutch</i>
3.5.2.1.	L1e-L7e	Brief description and schematic drawing of the clutch and its control system : Not applicable
3.5.3.		<i>Transmission</i>
3.5.3.1.	L1e-L7e	Brief description and schematic drawing of gear shift system(s) and its control : Not applicable

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information																								
3.5.3.2.	L1e-L7e	Drawing of the transmission : Not applicable																								
3.5.3.3.	L1e-L7e	Type (mechanical, hydraulic, electric, manual/manual-automated/automatic/CVT /other (indicate)) ⁽⁴⁾ : Other (wheel-hub motor)																								
3.5.3.4.	L1e-L7e	A brief description of the electrical/ electronic components (if any) : Not applicable																								
3.5.3.5.	L1e-L7e	Location relative to the engine : Not applicable																								
3.5.3.6.	L1e-L7e	Method of control : Not applicable																								
3.5.4.	L1e-L7e	<i>Gear ratios</i>																								
		<table><tr><th colspan="5">Overview gear ratios</th></tr><tr><th>Gear</th><th>Internal transmission ratios (ratios of engine to transmission output shaft revolutions)</th><th>Final drive ratio(s) (ratio of transmission output shaft to driven wheel revolutions)</th><th>Total gear ratios</th><th>Ratio (engine speed/ vehicle speed) for Manual transmission only</th></tr><tr><td>1</td><td>/</td><td>/</td><td>/</td><td>/</td></tr><tr><td>Reverse</td><td>/</td><td>/</td><td>/</td><td>/</td></tr></table>					Overview gear ratios					Gear	Internal transmission ratios (ratios of engine to transmission output shaft revolutions)	Final drive ratio(s) (ratio of transmission output shaft to driven wheel revolutions)	Total gear ratios	Ratio (engine speed/ vehicle speed) for Manual transmission only	1	/	/	/	/	Reverse	/	/	/	/
Overview gear ratios																										
Gear	Internal transmission ratios (ratios of engine to transmission output shaft revolutions)	Final drive ratio(s) (ratio of transmission output shaft to driven wheel revolutions)	Total gear ratios	Ratio (engine speed/ vehicle speed) for Manual transmission only																						
1	/	/	/	/																						
Reverse	/	/	/	/																						
3.5.4.1.	L3e-AxE, L3e-AxT	Final drive ratio : Not applicable																								
3.5.4.2.	L3e-AxE, L3e-AxT	Overall gear ratio in highest gear : Not applicable																								
3.6.		Safe-cornering device e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation																								
3.6.1.	L1e-L7e, equipped with twinned wheels, L2e, L5e, L6e, L7e	Safe-cornering device (Annex VIII to Regulation (EU) No 168/2013 : yes, other (one motor per wheel)																								
3.6.2.	L1e-L7e, equipped with twinned wheels, L2e, L5e, L6e, L7e	Differential lock : yes/no/optional ⁽⁴⁾																								
3.6.3.	L1e-L7e	Brief description and schematic drawing of the safe-cornering device, the differential lock and their control systems : Not applicable																								
3.7.		Suspension and control																								
3.7.1.	L1e-L7e	Brief description and schematic drawing of suspension and its control system : Refer to drawing No. Steinadler Pro-10-01, Steinadler Pro-11-01, Steinadler Pro-12-01																								

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
3.7.2.	L1e-L7e	Drawing of the suspension arrangements : Refer to drawing No. Steinadler Pro-10-01, Steinadler Pro-11-01, Steinadler Pro-12-01
3.7.3.	L1e-L7e	Level adjustment : yes/no/optional ⁽⁴⁾
3.7.4.	L1e-L7e	Brief description of the electrical/ electronic components : Not applicable
3.7.5.	L1e-L7e	Stabilisers : yes/no/optional ⁽⁴⁾
3.7.6.	L1e-L7e	Shock absorbers : yes/no/optional ⁽⁴⁾
3.8.		Passenger-compartment heating system and air-conditioning
3.8.1.		<i>Passenger-compartment heating system</i>
3.8.1.1.	L2e, L5e-B, L6e-B, L7e	An overall drawing of the heating system giving its location on the vehicle (and the arrangement of the sound damping devices (including the position of the heat exchange points)) : Not applicable
3.8.1.2.	L2e, L5e-B, L6e-B, L7e	An overall drawing of the heat-exchanger used in systems utilising the heat from the exhaust gases, or of the parts where that exchange takes place (in the case of heating systems using the heat provided by the engine cooling air) : Not applicable
3.8.1.3.	L2e, L5e-B, L6e-B, L7e	A sectional drawing of the heat-exchanger or parts where heat exchange takes place, together with a statement of the wall thickness, of the materials used and the characteristics of their surface : Not applicable
3.8.1.4.	L2e, L5e-B, L6e-B, L7e	Specifications regarding the method of manufacture and technical data relating to other major components of the heating system, such as the fan : Not applicable
3.8.2.		<i>Air-conditioning</i>
3.8.2.1.	L2e, L5e-B, L6e-B, L7e	Brief description and schematic drawing of air-conditioning and its control system : Not applicable
3.8.2.2.	L2e, L5e-B, L6e-B, L7e	Gas used as refrigerant in the air-conditioning system : Not applicable
3.8.2.3.	L2e, L5e-B, L6e-B, L7e	The air-conditioning system is designed to contain fluorinated greenhouse gases with global warming potential higher than 150. If yes, fill in the following sections : yes/no ⁽⁴⁾

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
3.8.2.3.1.	L2e, L5e-B, L6e-B, L7e	Drawing and brief description of the air-conditioning system, including the reference or part number and material of the leak components : Not applicable
3.8.2.3.2.	L2e, L5e-B, L6e-B, L7e	Leakage of the air-conditioning system : Not applicable
3.8.2.3.3.	L2e, L5e-B, L6e-B, L7e	Reference or part number and material of the components of the system and test information (e.g. test report number, Type-approval number, etc.) : Not applicable
3.8.2.3.4.	L2e, L5e-B, L6e-B, L7e	Overall leakage/year of the entire system : Not applicable
3.9.		Cycles designed to pedal : Not applicable
4.		GENERAL INFORMATION ON ENVIRONMENTAL AND PROPULSION PERFORMANCE
4.0.		General information on environmental and propulsion performance
4.0.1.	L1e-L7e	Environmental step ⁽¹⁶⁾ : Euro 5+ (3/4/5/5+) ⁽⁴⁾
4.0.2.	L1e-L7e	Fuel consumption (provide details for each reference fuel tested) : Not applicable
4.0.3.	L1e-L7e	CO ₂ emissions ⁽²⁵⁾ : Not applicable
4.0.4.	L1e-L7e	Energy consumption ⁽²⁵⁾ : 92 Wh/km
4.0.5.	L1e-L7e	Electric range ⁽²⁵⁾ : 51 km
4.1.		Tailpipe emission-control system : Not applicable
4.2.		Crankcase emission control system
4.2.1.	L1e-L7e	Configuration of crank-case gas recycling system (breather system, positive crank-case ventilation system, other) ⁽⁴⁾ (description and drawings) : Not applicable
4.3.		Evaporative emission control system : Not applicable
4.4.		Additional information on environmental and propulsion unit performance : Not applicable

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
5.		VEHICLE PROPULSION FAMILY
5.1.	L1e-L7e	To define the vehicle propulsion family, : Not applicable the manufacturer shall submit the information required for classification criteria set out in point 3 of Annex XI to Commission Delegated Regulation (EU) No 134/2014, if not already provided in the information document
6.		INFORMATION ON FUNCTIONAL SAFETY
6.1.		Audible warning devices
6.1.1.	L1e-L7e	Summary description of device(s) used and their purpose : Eletro-magnetic with resonator disc, single-tone. Used to warn other traffics and pedestrians. Make: HELLA, MrHorn, APLEX, OSRAM Type: S70 Approval mark: I E57 000051
6.1.2.	L1e-L7e	Drawing(s) showing the location of the audible warning device(s) in relation to the structure of the vehicle : Refer to drawing No. Steinadler Pro-13-01
6.1.3.	L1e-L7e	Details of the method of attachment, including the part of the vehicle structure to which the audible warning device(s) is (are) attached : Refer to drawing No. Steinadler Pro-13-01
6.1.4.	L1e-L7e	Electrical/pneumatic circuit diagram : Refer to drawing No. Steinadler Pro-14-01
6.1.4.1.	L1e-L7e	Voltage : AC/DC ⁽⁴⁾
6.1.4.2.	L1e-L7e	Rated voltage or pressure : 12 V
6.1.5.	L1e-L7e	Drawing of the mounting device : Refer to drawing No. Steinadler Pro-13-01
6.2.		Braking, including anti-lock and combined braking systems
6.2.1.	L1e-L7e	Characteristics of the brakes, including details and drawings of the drums, discs, hoses, make and type of shoe/pad assemblies and/or linings, effective braking areas, radius of drums, shoes or discs, mass of drums, adjustment devices, relevant parts of the axle(s) and suspension, levers, pedals ⁽⁴⁾ : Refer to drawing No. Steinadler Pro-15-01, Steinadler Pro-16-01, Steinadler Pro-17-01, Steinadler Pro-18-01, Steinadler Pro-19-01, Steinadler Pro-20-01, Steinadler Pro-21-01, Steinadler Pro-22-01 e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
6.2.2.	L1e-L7e	Operating diagram, description and/or drawing of the braking system, including details and drawings of the transmission and controls as well as a brief description of the electrical and/or electronic components used in the braking system ⁽⁴⁾ : Refer to drawing No. Steinadler Pro-15-01, Steinadler Pro-16-01, Steinadler Pro-17-01, Steinadler Pro-18-01, Steinadler Pro-19-01, Steinadler Pro-20-01, Steinadler Pro-21-01, Steinadler Pro-22-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information	
6.2.2.1.	L1e-L7e	Front, rear and sidecar brakes, disc and/or drum ⁽⁴⁾	: Front: disc Rear: disc
6.2.2.2.	L1e-L7e	Parking braking system	: Mechanically brake operating on the rear wheels Refer to drawing No. Steinadler Pro-15-01
6.2.2.3.	L1e-L7e	Any additional braking system	: Front secondary brake system Refer to drawing No. Steinadler Pro-18-01 Rear secondary brake system Refer to drawing No. Steinadler Pro-19-01
6.2.3.	L1e-L7e	Vehicle is equipped to tow a trailer with no brake/overrun brake/electric/pneumatic/hydraulic service brakes	: yes/no ⁽⁴⁾
6.2.4.	L1e-L7e	Anti-lock/Combined braking system	
6.2.4.1.	L1e-L7e	Anti-lock braking system	: yes/no/optional ⁽⁴⁾
6.2.4.2.	L1e-L7e	Combined braking system	: yes/no/optional ⁽⁴⁾
6.2.4.3.	L1e-L7e	Anti-lock and combined braking system	: yes/no/optional ⁽⁴⁾
6.2.4.4.	L1e-L7e	Schematic drawing(s)	: Refer to drawing No. Steinadler Pro-15-01
6.2.5.	L1e-L7e	Hydraulic reservoir(s) (volume and location)	: Refer to drawing No. Steinadler Pro-16-01
6.2.6.	L1e-L7e	Particular characteristics of the braking system(s)	
6.2.6.1.	L1e-L7e	Brake shoes and/or pads ⁽⁴⁾	: Refer to drawing No. Steinadler Pro-20-01, Steinadler Pro-21-01
6.2.6.2.	L1e-L7e	Linings and/or pads (indicate make, type, grade of material or identification mark)	: Refer to drawing No. Steinadler Pro-20-01, Steinadler Pro-21-01
6.2.6.3.	L1e-L7e	Brake levers and/or pedals ⁽⁴⁾	: Refer to drawing No. Steinadler Pro-22-01
6.2.6.4.	L1e-L7e	Other devices (where applicable) drawing and description	: Not applicable
6.3.		Electrical safety	
6.3.1.	L1e-L7e	Brief description of the power circuit components installation and drawings/ photographs showing the location of the power circuit components installation	: Refer to drawing No. Steinadler Pro-14-01
6.3.2.	L1e-L7e	Schematic diagram of all electrical functions included in power circuit	: Refer to drawing No. Steinadler Pro-17-01
6.3.3.	L1e-L7e	Working voltage(s) (V)	: Power working voltage: 74.4 V Other electrical components voltage: 12V DC

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Page 13 of 30

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information	
6.3.4.	L1e-L7e	Description of protection against electric-shocks	: Using terminal box that made by high and low Pressure polyethylene material, and nylon plug to protect against electric-shocks. Refer to drawing No. Steinadler Pro-24-01
6.3.5.	L1e-L7e	Fuse and/or circuit breaker	: yes/ no /optional ⁽⁴⁾ , Fuse
6.3.5.1.	L1e-L7e	Diagram showing the functional range	: Refer to drawing No. Steinadler Pro-25-01
6.3.6.	L1e-L7e	Configuration of power wiring harness	: Refer to drawing No. Steinadler Pro-26-01
6.4.		Front and rear protective structures	e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
6.4.1.		<i>Front protective structure</i>	
6.4.1.1.	L1e-L7e	Detailed technical description (including photographs or drawings)	: Refer to drawing No. Steinadler Pro-27-01
6.4.1.2.	L1e-L7e	Materials used	: Steel
6.4.2.		<i>Rear protective structure</i>	
6.4.2.1.	L1e-L7e	Detailed technical description (including photographs or drawings)	: Refer to drawing No. Steinadler Pro-28-01
6.4.2.2.	L1e-L7e	Materials used	: Steel
6.5.		Glazing, windscreen wipers and washers, and defrosting and demisting systems	
6.5.1.		<i>Windscreen</i>	
6.5.1.1.	L2e, L5e, L6e, L7e	Materials used	: Not applicable
6.5.1.2.	L2e, L5e, L6e, L7e	Method of mounting	: Not applicable
6.5.1.3.	L2e, L5e, L6e, L7e	Angle of inclination	: Not applicable
6.5.1.4.	L2e, L5e, L6e, L7e	Windscreen accessories and the position in which they are fitted, together with a brief description of any electrical/ electronic components	: Not applicable
6.5.1.5.	L2e, L5e, L6e, L7e	Drawing of the windscreen with dimensions	: Not applicable
6.5.2.		<i>Other windows</i>	
6.5.2.1.	L2e, L5e, L6e, L7e	Materials used	: Not applicable
6.5.2.2.	L2e, L5e, L6e, L7e	A brief description of the electrical/electronic components (if any) of the window lifting mechanism	: Not applicable

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
6.5.3.		<i>Opening roof glazing</i>
6.5.3.1.	L2e, L5e, L6e, L7e	Materials used : Not applicable e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
6.5.4.		<i>Other glass panes</i>
6.5.4.1.	L2e, L5e, L6e, L7e	Materials used : Not applicable
6.6.		Windscreen wiper(s)
6.6.1.	L2e, L5e, L6e, L7e	Detailed technical description (including photographs or drawings) : Not applicable
6.7.		Windscreen washer
6.7.1.	L2e, L5e, L6e, L7e	Detailed technical description (including photographs or drawings) : Not applicable
6.7.2.	L2e, L5e, L6e, L7e	Capacity of the reservoir : Not applicable
6.8.		Defrosting and demisting
6.8.1.	L2e, L5e, L6e, L7e	Detailed technical description (including photographs or drawings) : Not applicable
6.9.		Driver-operated controls including identification of controls, tell- tales and indicators
6.9.1.	L1e-L7e	Arrangement and identification of controls, tell-tales and indicators : Refer to drawing No. Steinadler Pro-29-01
6.9.2.	L1e-L7e	Photographs and/or drawings of the arrangement of symbols and controls, tell-tales and indicators : Refer to drawing No. Steinadler Pro-29-01
6.9.3.	L1e-L7e	Controls, tell-tales and indicators for which, when fitted, identification is mandatory, including the identification symbols to be used for that purpose : Refer to drawing No. Steinadler Pro-29-01
6.9.4.	L1e-L7e	Summary table: the vehicle is equipped with the following driver-operated controls, including indicators and tell-tales ⁽⁴⁾ : See Table 6.9.4.
6.9.5.	L1e-L7e	Controls, tell-tales and indicators for which, when fitted, identification is optional, and symbols which shall be used if they are to be identified : See Table 6.9.5.
6.10.		Speedometer and odometer
6.10.1.		<i>Speedometer</i>

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information	
6.10.1.1.	L1e-L7e	Photographs and/or drawings of the complete system	: Manufacturer: JIANDE WUXING BICYCLE CO., LTD. Type: DZ52 Refer to drawing No. Steinadler Pro-30-01
6.10.1.2.	L1e-L7e	Vehicle speed range displayed	: 0~99 km/h
6.10.1.3.	L1e-L7e	Tolerance of the measuring mechanism of the speedometer	: $0 \leq (V_1 - V_2) \leq 0.1 * V_2 + 4$ km/h V ₁ : display speed, V ₂ : actual speed
6.10.1.4.	L1e-L7e	Technical constant of the speedometer	: 1 pulse/min = 10.532×10^{-3} km/h
6.10.1.5.	L1e-L7e	Method of operation and description of the drive mechanism	: Directly connected to the main controller, to drive speedometer through the average signal from four sub controller
6.10.1.6.	L1e-L7e	Overall transmission ratio of the drive mechanism	: 48 pulses /1 rear wheel cycle
6.10.2.		<i>Odometer</i>	
6.10.2.1.	L1e-L7e	Tolerance of the measuring mechanism of the odometer	: 0~+5 km
6.10.2.2.	L1e-L7e	Method of operation and description of the drive mechanism	: See item 6.10.1.5.
6.11.		Installation of lighting, light-signalling devices, including automatic switching of lighting	
6.11.1.	L1e-L7e	List of all devices (mentioning the number, make(s), type, component type-approval mark(s), the maximum intensity of the main-beam headlamps, colour, the corresponding tell-tale)	: See Table 6.11.1.
6.11.2.	L1e-L7e	Diagram showing the location of the lighting and light-signalling devices	: Refer to drawing No. Steinadler Pro-31-01
6.11.3.	L1e-L7e	Hazard warning lamps	: Same as direction lamps
6.11.4.	L1e-L7e	Brief description of the electrical and/or electronic components used in the lighting system and in the light-signalling system	: Not applicable
6.11.5.	L1e-L7e	For every lamp and reflector, supply the following information (in writing and/or by diagram)	: See component certificates
6.11.5.1.	L1e-L7e	Drawing showing the extent of the illuminating surface	: See component certificates
6.11.5.2.	L1e-L7e	Method used to define the apparent surface in accordance with point 2.10 of UNECE Regulation No 48 (OJ L 323, 6.12.2011, p. 46)	: See component certificates

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
6.11.5.3.	L1e-L7e	Axis of reference and centre of reference : See component certificates
6.11.5.4.	L1e-L7e	Method of operation of concealable lamps : Not applicable
6.11.6.	L1e-L7e	Description/drawing and type of headlamp levelling device (e.g. automatic, stepwise manually adjustable, continuously manually adjustable) ⁽⁴⁾ : Continuously manually adjustable
6.11.6.1.	L1e-L7e	Control device : Set screw
6.11.6.2.	L1e-L7e	Reference marks : Not applicable
6.11.6.3.	L1e-L7e	Marks assigned for loading conditions : Not applicable
6.12.		Rearward visibility
6.12.1.		<i>Rear-view mirrors (stating for each mirror)</i>
6.12.1.1.	L1e-L7e	Drawing(s) for the identification of the mirror showing the position of the mirror relative to the vehicle structure : Make: XIONGXIN Type: XX-650 Approval mark: L E13 00 9911 Refer to drawing No. Steinadler Pro-32-01
6.12.1.2.	L1e-L7e	Details of the method of attachment including that part of the vehicle structure to which it is attached : Refer to drawing No. Steinadler Pro-32-01
6.12.1.3.	L1e-L7e	A brief description of the electronic components of the adjustment system : Not applicable
6.12.2.	L1e-L7e	<i>Devices for indirect vision other than mirrors</i>
6.12.2.1.	L1e-L7e	Description of the device : Not applicable
6.12.2.2.	L1e-L7e	In the case of a camera-monitor device, the detection distance (mm), contrast, luminance range, glare correction, display performance (black and white/colour ⁽⁴⁾), image repetition frequency, luminance reach of the monitor ⁽⁴⁾ : Not applicable
6.12.2.3.	L1e-L7e	Sufficiently detailed drawings to identify the complete device, including installation instructions; the position for the EU type-approval mark has to be indicated on the drawings : Not applicable e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
6.13.		Rollover protective structure (ROPS) : Not applicable
6.14.		Safety belts and/or other restraints
		From 6.14.1. to 6.14.4. : Not applicable
6.15.		Safety belt anchorages
		From 6.15.1. to 6.15.7. : Not applicable

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
6.16.		Seating positions (saddles and seats)
6.16.1.	L1e-L7e	Number of seating positions : 1 Refer to drawing No. Steinadler Pro-33-01
6.16.1.1.	L2e, L5e, L6e, L7e	Location and arrangement ⁽⁸⁾ : r1:lC (L2e, L5e, L6e, L7e)
6.16.2.	L1e-L7e	Seating position configuration : seat/saddle ⁽⁴⁾
6.16.3.	L1e-L7e	Description and drawings of:
6.16.3.1.	L1e-L7e	The seats and their anchorages : Not applicable
6.16.3.2.	L1e-L7e	The adjustment system : Not applicable
6.16.3.3.	L1e-L7e	The displacement and locking systems : Not applicable
6.16.3.4.	L1e-L7e	The seat-belt anchorages incorporated in the seat structure : Not applicable
6.16.3.5.	L1e-L7e	The parts of the vehicle used as anchorages : Not applicable
6.16.4.	L2e, L4e, L5e-B, L6e-B, L7e	Coordinates or drawing of the R-point(s) of all seating positions
6.16.4.1.	L2e, L4e, L5e-B, L6e-B, L7e	Driver's seat : Not applicable
6.16.4.2.	L2e, L4e, L5e-B, L6e-B, L7e	All other seating positions : Not applicable
6.16.5.	L1e-L7e	Design torso angle e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
6.16.5.1.	L1e-L7e	Driver's seat : Not applicable
6.16.5.2.	L1e-L7e	All other seating positions : Not applicable
6.16.6.	L1e-L7e	Range of seat adjustment
6.16.6.1.	L1e-L7e	Driver's seat : Not applicable
6.16.6.2.	L1e-L7e	All other seating positions : Not applicable
6.17.		Steer-ability, cornering properties and turn-ability
6.17.1.	L1e-L7e	Schematic diagram of steered axle(s) showing steering geometry : Refer to drawing No. Steinadler Pro-34-01
6.17.2.		<i>Transmission and control of steering</i>
6.17.2.1.	L1e-L7e	Configuration of steering transmission (specify for front and rear) : Refer to drawing No. Steinadler Pro-34-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information				
6.17.2.2.	L1e-L7e	Linkage to wheels (including other than mechanical means; specify for front and rear)		:	Front steering axle	
6.17.2.2.1.	L1e-L7e	A brief description of the electrical/ electronic components		:	Not applicable	
6.17.2.3.	L1e-L7e	Diagram of the steering transmission		:	Refer to drawing No. Steinadler Pro-34-01	
6.17.2.4.	L2e, L5e, L6e, L7e	Schematic diagram(s) of the steering control(s)		:	Not applicable	
6.17.2.5.	L2e, L5e, L6e, L7e	Range and method of adjustment of the steering control(s)		:	Not applicable	
6.17.2.6.	L2e, L5e, L6e, L7e	Method of assistance		:	Not applicable	
6.17.3.		Maximum steering angle of the wheels				
6.17.3.1.	L1e-L7e	To the right		:	27 degrees; number of turns of the steering wheel (or equivalent data): Not applicable	
6.17.3.2.	L1e-L7e	To the left		:	26 degrees; number of turns of the steering wheel (or equivalent data): Not applicable	
6.18.		Tyres/wheels combination		e13*168/2013*02582*00		
6.18.1.		Tyres		Société Nationale de Certification et d'Homologation		
6.18.1.1.		Size designation				
		Axle	Tyres size	Rolling Circ. (mm)	Tire pressure (kPa)	
		Front	AT22×7-10 35L	1755	45	
		Rear	AT22×7-10 35L	1755	45	
6.18.1.1.1.	L1e-L7e	Axle 1		:	See above table 6.18.1.1.	
6.18.1.1.2.	L1e-L7e	Axle 2		:	See above table 6.18.1.1.	
6.18.1.1.3.	L4e	Sidecar wheel		:	Not applicable	
6.18.1.2.	L1e-L7e	Minimum load-capacity index with the maximum load on each tyre		:	Front: 18 (75 kg) Rear: 20 (80 kg)	
6.18.1.3.	L1e-L7e	Minimum-speed category symbol compatible with the theoretical maximum design vehicle speed		:	F	
6.18.1.4.	L1e-L7e	Tyre pressure(s) as recommended by the vehicle manufacturer		:	See above table 6.18.1.1.	
6.18.2.		Wheels				
6.18.2.1.	L1e-L7e	Rim size(s)		:	See above table 6.18.1.1.	

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
6.18.2.2.	L1e-L7e	Categories of use compatible with the vehicle : See above table 6.18.1.1.
6.18.2.3.	L1e-L7e	Nominal rolling circumference : See above table 6.18.1.1.
6.19.		Vehicle maximum speed limitation plate and its location on the vehicle From 6.19.1. to 6.19.6. : Not applicable (L7e-B1 and L7e-B2)
6.20.		Vehicle occupant protection, including interior fittings and vehicle doors From 6.20.1. to 6.20.4.3.2. : Not applicable
6.21.		Maximum continuous total power and/or maximum vehicle speed limitation by design
6.21.1.		Propulsion and/or drive-train output governors
6.21.1.1.	L1e-L7e	Number (minimum two, exemption L3e-A3 and L4e-A3) : 2
6.21.1.2.	L1e-L7e	How is the redundancy of governors ensured? : 1. reduction of the maximum power output of one electric motor based on the rotation speed as sensed internally to the electric motor; 2. physical vehicle speed limitation by means of external components such as a maximum achievable revolution speed of an electric motor.
6.21.1.3.	L1e-L7e	Nominal cut-off point no 1
6.21.1.3.1.	L1e-L7e	Engine/motor/drive-train rotation speed at which cut-off starts under load : 1042 min ⁻¹
6.21.1.3.2.	L1e-L7e	Maximum rotation speed at the minimum engine load : 1042 min ⁻¹
6.21.1.4.	L1e-L7e	Nominal cut-off point no 2 e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
6.21.1.4.1.	L1e-L7e	Engine/motor/drive-train rotation speed at which cut-off starts under load ⁽⁴⁾ : 1042 min ⁻¹
6.21.1.4.2.	L1e-L7e	Maximum rotation speed at the minimum engine load : 1042 min ⁻¹
6.21.1.5.	L1e-L7e	The stated purpose of governor(s) : maximum design vehicle speed limitation/ maximum power limitation/engine over-speed protection ⁽⁴⁾
7.		INFORMATION ON VEHICLE CONSTRUCTION
7.1.		Coupling devices and attachments : Not applicable

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
7.2.		Devices to prevent unauthorised use e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
7.2.1.		<i>Protective device</i>
7.2.1.1.	L1e-L7e	Summary description of protective device(s) used : Type 1: lock the steering Refer to drawing No. Steinadler Pro-35-01
7.2.2.		<i>Vehicle immobiliser</i>
7.2.2.1.	L1e-L7e	Technical description of the vehicle immobiliser and of the measures taken against inadvertent activation : Not applicable
7.2.3.		<i>Alarm system</i>
7.2.3.1.	L1e-L7e	Description of the alarm system and of the vehicle parts involved in its installation : Not applicable
7.2.3.2.	L1e-L7e	List of the main components comprising the alarm system : Not applicable
7.3.		Electromagnetic compatibility (EMC)
7.3.1.	L1e-L7e	Requirements under UNECE Regulation No 10 (OJ L 254, 20.9.2012, p. 1) are met with relevant documentation included in the information document : yes/no ⁽⁴⁾
7.3.2.	L1e-L7e	Table or drawing of radio-interference control equipment : Refer to drawing No. Steinadler Pro-23-01
7.3.3.	L1e-L7e	Particulars of the nominal value of the direct-current resistance, and, in the case of resistive ignition cables, of their nominal resistance per metre : 1. 6.00 mm ² (max. resistance: 3.0 Ohm/km) 2. 5.00 mm ² (max. resistance: 13.3 Ohm/km) 3. 1.00 mm ² (max. resistance: 19.5 Ohm/km) 4. 0.75 mm ² (max. resistance: 26.0 Ohm/km) 5. 0.50 mm ² (max. resistance: 39.0 Ohm/km) 5. 0.30 mm ² (max. resistance: 69.2 Ohm/km)
7.4.		External projections

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
7.4.1.	L1e-L7e vehicles with bodywork	General arrangement (drawing or photographs accompanied if necessary by dimensional details and/or text) indicating the position of the attached sections and views, of any parts of the exterior surface which can be regarded as critical for external projections, for example, and where relevant: bumpers, floor line, door and window pillars, air-intake grilles, radiator grille, windscreen wipers, rain gutter channels, handles, slide rails, flaps, door hinges and locks, hooks, eyes, winches, decorative trim, badges, emblems and recesses and any other parts of the exterior surface which can be regarded as critical (e.g. lighting equipment) : Not applicable
7.5.		Fuel storage : Not applicable
7.6.		On-board diagnostics (OBD) functional requirements
7.6.1.		On-board diagnostics system
7.6.1.1.	L1e-L7e	Stage I : yes /no ⁽⁴⁾ and/or
7.6.1.2.	L1e-L7e	Stage II : yes /no ⁽⁴⁾
7.6.2.		OBD system general information
7.6.2.1.	L3e-L7e	Written description and/or drawing of the malfunction indicator (MI) : Refer to drawing no. Steinadler Pro-40-01
7.6.2.2.	L3e-L7e	List and purpose of all components monitored by the OBD system : See item 7.6.2.3.
7.6.2.3.	L3e-L7e	Written description (general working principles) for all OBD stage I circuit (open circuit, shorted low and high, rationality) and electronics (PCU/ECU internal and communication) diagnostics :

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information					
Components	Fault Code	Monitor Strategy	Fault detection criteria	MI activation Criteria	Secondary Parameters	Pre-conditioning	Demonstration test
Throttle	P0120	Accelerator(Handle) position sensor open circuit	Consumption = 0 A	/	/	N.A.	One type I
	P0122	Accelerator(Handle) position sensor circuit low	Accelerator (Handle) signal level less than 1% of the range	/	/	N.A.	One type I
	P0123	Accelerator(Handle) position sensor circuit high	Accelerator (Handle) signal level more than 99% of the range	/	/	N.A.	One type I
Drive motor control module	U0110	Accelerator(Handle) position sensor open circuit	Consumption = 0 A	/	/	N.A.	One type I
Drive motor temperature	P0A2C	Drive motor temperature sensor circuit low	Sensor signal level less than 1% of the range	/	/	N.A.	One type I
	P0A2D	Drive motor temperature sensor circuit high	Sensor signal level more than 99% of the range	/	/	N.A.	One type I
System voltage	P0562	System voltage low	Main supply under voltage	/	/	N.A.	One type I
	P0563	System voltage high	Main supply over voltage	/	/	N.A.	One type I
7.6.2.4.	L3e-L7e	Written description (general working principles) for all OBD stage I diagnostic functionality triggering any operating mode which significantly reduces engine torque in case of fault detection : See item 7.6.2.3. e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation					
7.6.2.5.	L3e-L7e	Written description of the communication protocol(s) supported : ISO 9141-2: 1994					
7.6.2.6.	L3e-L7e	Physical location of diagnostic-connector (add drawings and photographs) : Refer to drawing no. Steinadler Pro-40-01					
7.6.2.7.	L3e-L7e	Written description in case of voluntary compliance with OBD stage II (general working principles) : Not applicable					
7.6.3.		<i>OBD compatibility The following additional information shall be provided by the vehicle manufacturer to enable the manufacture of OBD-compatible replacement or service parts, diagnostic tools and test equipment:</i>					

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
7.6.3.1.	L3e-L7e	A comprehensive document describing all sensed components concerned with the strategy for fault detection and MI activation (fixed number of driving cycles or statistical method). This shall, include a list of relevant secondary sensed parameters for each component monitored by the OBD system. The document shall also list all OBD output codes and formats (with an explanation of each) used in association with individual emission-related powertrain components and individual nonemission- related components, where monitoring the component is used to determine MI activation. This shall contain, in particular, a comprehensive explanation for the data given in service \$05 Test ID \$ 21 to FF and the data given in service \$06 : Not applicable e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation
7.6.3.2.	L3e-L7e	For vehicle types using a communication link in accordance with ISO 15765-4 'Road vehicles, diagnostics on controller area network (CAN) — Part 4: requirements for emissions-related systems', the manufacturer shall provide a comprehensive explanation for the data given in service \$06 Test ID \$00 to FF, for each OBD monitor ID supported : Not applicable
7.6.3.3.	L3e-L7e	The information required above may be provided in table form as described below. : See item 7.6.2.3.
7.6.3.4.	L3e-L7e	Description of ETC diagnostic fault codes : Not applicable
7.6.4.		<i>Communication protocol information The following information shall be referenced to a specific vehicle make, model and variant, or identified using other workable definitions such as VIN or vehicle and systems identification</i>
7.6.4.1.	L3e-L7e	Any protocol information system needed to enable complete diagnostics in addition to the standards prescribed in point 3.8. of Appendix 1 to Annex XII to Commission Delegated Regulation (EU) No 44/2014, such as additional hardware or software protocol information, parameter identification, transfer functions, 'keep alive' requirements, or error conditions : Protocol information are implemented according to ISO 9141-2:1994 Diagnostic service requirements according to ISO 15031-5:2011

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information			
7.6.4.2.	L3e-L7e	Details of how to obtain and interpret all fault codes not in accordance with the standards prescribed in point 3.1 1. of Appendix 1 to Annex XII to Commission Delegated Regulation (EU) No 44/2014 : Not applicable			
7.6.4.3.	L3e-L7e	A list of all available live data parameters including scaling and access information :			
PID	Description		Min. value	Max. value	Units
01	Monitor status since DTCs cleared		/	/	/
02	Freeze DTC		/	/	/
04	Calculated load		0	100	%
05	Motor temperature		-40	215	°C
0C	Motor rpm		0	1042	rpm
11	Accelerator(Handle) position		0	100	%
21	Distance travelled with malfunction indicator lamp(MIL) on		0	65,535	km
42	Control module voltage		0	65,535	V
7.6.4.4.	L3e-L7e	A list of all available functional tests including device activation or control and the means to implement them : Not applicable			
7.6.4.5.	L3e-L7e	Details of how to obtain all component and status information, time stamps, pending DTC and freeze frames : According to ISO 15031-5:2011			
7.6.4.6.	L3e-L7e	PCU/ECU identification and variant coding : Calibration software identification No.: Steinadler Pro Verification No.: 00000001			
7.6.4.7.	L3e-L7e	Details of how to reset service lights : According to ISO 15031-5:2011			
7.6.4.8.	L3e-L7e	Location of diagnostic connector and connector details : Refer to drawing no. Steinadler Pro-37			
7.6.4.9.	L3e-L7e	Engine code identification. : See item 3.1.2.2.			
7.6.5.		Test and diagnosis of OBD monitored components			
7.6.5.1.	L3e-L7e	A description of tests to confirm its functionality, at the component or in the harness : See item 7.6.2.3.			
7.7.		Passenger handholds and footrests e13*168/2013*02582*00 Société Nationale de Certification et d'Homologation			
7.7.1.		Handholds			
7.7.1.1.	L1e-L7e	Configuration : Strap and/or handle ⁽⁴⁾			
7.7.1.2.	L1e-L7e	Photographs and/or drawings showing the location and the construction : Not applicable			

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Item No	(Sub) categories	Detailed information
7.7.2.		<i>Footrests</i>
7.7.2.1.	L1e-L7e	Photographs and/or drawings showing the location and the construction : Refer to drawing No. Steinadler Pro-36-01
7.8.		Registration plate space
7.8.1.	L1e-L7e	Location of rear registration plate (indicate variants where necessary; drawings may be used as appropriate) : Refer to drawing No. Steinadler Pro-37-01
7.8.1.1.	L1e-L7e	Height above road surface, upper edge : Refer to drawing No. Steinadler Pro-37-01
7.8.1.2.	L1e-L7e	Height above road surface, lower edge : Refer to drawing No. Steinadler Pro-37-01
7.8.1.3.	L1e-L7e	Distance of the center line from the longitudinal median plane of the vehicle : 0 mm
7.8.1.4.	L1e-L7e	Dimensions (length x width) : Refer to drawing No. Steinadler Pro-37-01
7.8.1.5.	L1e-L7e	Inclination of the plane to the vertical : Refer to drawing No. Steinadler Pro-37-01
7.8.1.6.	L1e-L7e	Angle of visibility in the horizontal plane : Refer to drawing No. Steinadler Pro-37-01
7.9.		Stands
7.9.1.	L1e, L3e	Configuration : Not applicable
7.9.2.	L1e, L3e	Construction material used : Not applicable
7.9.3.	L1e, L3e	Photographs and drawings showing the location of the stand(s) in relation to the structure of the vehicle : Not applicable
7.9.4.	L1e, L3e	Description of the method to prevent contact of the stand with the ground when the vehicle is being propelled : Not applicable

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Table 6.9.4.

Controls, tell-tales and indicators for which, when fitted, identification is mandatory, and symbols to be used for that purpose							
Symbol No.	Device	Control/indicator available (+)	Identified by symbol (+)	Where (++)	Tell-tale available (+)	Identified by symbol (+)	Where (++)
1	Master light	x	x	c	-	-	-
2	Dipped-beam head lamps	x	x	c	x	x	d
3	Main-beam head lamps	x	x	c	x	x	d
4	Position (side) lamps	-	-	-	x	x	d
5	Front fog lamps	-	-	-	-	-	-
6	Rear fog lamps	-	-	-	-	-	-
7	Headlamp levelling device	-	-	-	-	-	-
8	Parking lamps	-	-	-	-	-	-
9	Direction indicators	x	x	c	x	x	d
10	Hazard warning	x	x	d	x	x	d
11	Windscreen wiper	-	-	-	-	-	-
12	Windscreen washer	-	-	-	-	-	-
13	Windscreen wiper and washer	-	-	-	-	-	-
14	Headlamp cleaning device	-	-	-	-	-	-
15	Windscreen demisting and defrosting	-	-	-	-	-	-
16	Rear window demisting and defrosting	-	-	-	-	-	-
17	Ventilating fan	-	-	-	-	-	-
18	Diesel pre-heat	-	-	-	-	-	-
19	Choke	-	-	-	-	-	-
20	Brake failure	-	-	-	-	-	-
21	Fuel level	-	-	-	-	-	-
22	Battery charging condition	-	-	-	-	-	-
23	Engine coolant temperature	-	-	-	-	-	-
24	Malfunction indicator light (MI)	-	-	-	x	x	d
⁽⁺⁾ x = Yes. - = No or not separately available. o = Optional. ⁽⁺⁺⁾ d = Directly on control, indicator or tell-tale. c = In close vicinity.							

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Table 6.9.5.

Controls, tell-tales and indicators for which, when fitted, identification is optional, and symbols which shall be used if they are to be identified							
Symbol No.	Device	Control/indicator available (+)	Identified by symbol (+)	Where (++)	Tell-tale available (+)	Identified by symbol (+)	Where (++)
1	Parking brake	x	-	-	-	-	-
2	Rear window wiper	-	-	-	-	-	-
3	Rear window washer	-	-	-	-	-	-
4	Rear window wiper and washer	-	-	-	-	-	-
5	Intermittent windscreen wiper	-	-	-	-	-	-
6	Audible warning device (horn)	x	x	c	-	-	-
7	Front hood (bonnet)	-	-	-	-	-	-
8	Rear hood (boot)	-	-	-	-	-	-
9	Seat belt	-	-	-	-	-	-
10	Engine oil pressure	-	-	-	-	-	-
11	Unleaded petrol	-	-	-	-	-	-
12	Ignition switch	x	x	c	-	-	-
13	Reverse (R)	x	x	d	x	x	d
14	Neutral (N)	-	-	-	-	-	-
15	Drive (D)	-	-	-	x	x	d
16	Park (P)	-	-	-	-	-	-
17	Ready	x	x	d	x	x	d
18	Interior heating	-	-	-	-	-	-
19	Seat belt	-	-	-	-	-	-
20	Window lift, power-operated	-	-	-	-	-	-
21	Door(s) ajar	-	-	-	-	-	-
22	Battery capacity	-	-	-	x	x	d
23	Bluetooth indicator	-	-	-	-	-	-
24	Overtaking beam	x	x	c	-	-	-
25	Speed limit gear	x	x	d	x	x	d
26	Engine start / Engine stop	x	x	c	-	-	-
(+) x = Yes. - = No or not separately available. o = Optional. (++) d = Directly on control, indicator or tell-tale. c = In close vicinity.							

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

Table 6.11.1.

Name	Make	Type	Quantity /Color	Tell tale	Approval mark	Max. intensity
Headlamp driving beam	K-LITE & KYI	M234	1/white	Blue	WCR-DS PL MA RL E4 12.5 148R00 30960 149R00	64699 cd
Headlamp passing beam			1/white	Green		/
Front position lamp			1/white	Green		/
Daytime running lamp			1/white	/		
Front direction indicator lamp		M341	2/amber	Green	11 12 E4 148R00 0723	/
Rear direction indicator lamp			2/amber	Green		/
Stop lamp		M162	1/red	/	MR MS LM1 E4 148R00 30676 IB 150R00 30676	/
Rear position lamp			1/red	Green		/
Rear registration plate lamp			1/white	/		/
Rear reflector			1/red	/		/
Side reflector	K-LITE, KYI	KM106	2/amber	/	IA E4 0224744	/

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application Date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

List of drawings:

Drawing No.	Drawing subject
Steinadler Pro-01-01	Location and detail of manufacturer's statutory plate
Steinadler Pro-02-01	Location and details of the vehicle identification number
Steinadler Pro-03-01	Dimension of vehicle
Steinadler Pro-04-01	Chassis
Steinadler Pro-05-01	Position and arrangement of electric motor
Steinadler Pro-06-01	Position and arrangement of controller (Main controller)
Steinadler Pro-06-02	Position and arrangement of controller (Sub controller)
Steinadler Pro-07-01	Control system of pure propulsion
Steinadler Pro-08-01	Position and details of propulsion battery
Steinadler Pro-09-01	Vehicle drive-train and its control system
Steinadler Pro-10-01	Suspension arrangements
Steinadler Pro-11-01	Front suspensions
Steinadler Pro-12-01	Rear suspensions
Steinadler Pro-13-01	Location and details of audible warning device
Steinadler Pro-14-01	Electrical circuit diagram
Steinadler Pro-15-01	Braking system
Steinadler Pro-16-01	Hydraulic reservoir
Steinadler Pro-17-01	Brake hose
Steinadler Pro-18-01	Front brake details
Steinadler Pro-19-01	Rear brake details
Steinadler Pro-20-01	Front brake pads
Steinadler Pro-21-01	Rear brake pads
Steinadler Pro-22-01	Brake lever, pedal and handle
Steinadler Pro-23-01	Location of power circuit components
Steinadler Pro-24-01	Location of high voltage label
Steinadler Pro-25-01	Circuit breaker
Steinadler Pro-26-01	Power wiring harness
Steinadler Pro-27-01	Front protective structure
Steinadler Pro-28-01	Rear protective structure
Steinadler Pro-29-01	Controls I.D., tell-tales and indicators
Steinadler Pro-30-01	Speedometer
Steinadler Pro-31-01	Lighting installation
Steinadler Pro-32-01	Rear-view mirrors and installation
Steinadler Pro-33-01	The seating position and R-point
Steinadler Pro-34-01	Steering geometry
Steinadler Pro-35-01	Anti-theft device
Steinadler Pro-36-01	Construction and location of footrest
Steinadler Pro-37-01	Mounting space of registration plate
Steinadler Pro-38-01	Location and details of charging interface
Steinadler Pro-39-01	Charger
Steinadler Pro-40-01	Location of diagnostic connector


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00


Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Manufacturer's statutory plate
Riveted on the left side of frame
R: x 1000, y 245, z 470



Text height: 4.0 mm

Text depth: 0.5 mm

R: Right side of the vehicle

— x: horizontal distance (mm) from the front-most axle

— y: horizontal distance (mm) from the longitudinal centre line of the vehicle

— z: distance (mm) from the ground

Vehicle Type	Steinadler Pro
Location and details of manufacturer's statutory plate	
Drawing No.	Steinadler Pro-01-01



Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation




- R: right side of the vehicle
- x: horizontal distance (mm) from the front-most axle
- y: horizontal distance (mm) from the longitudinal centre line of the vehicle
- z: distance (mm) from the ground

Vehicle Type	Steinadler Pro
Location and details of vehicle identification number	
Drawing No.	Steinadler Pro-02-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.



Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025



e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Vehicle Type	Steinadler Pro
Dimension of vehicle	
Drawing No.	Steinadler Pro-03-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Vehicle Type	Steinadler Pro
Chassis	
Drawing No.	Steinadler Pro-04-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.


Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025


e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Note: There are total of 4 motors, and the motor for each wheel is the same.



Detail:



Manufacturer: TAIZHOU QUANSHUN ELECTRIC DRIVE TECHNOLOGY CO., LTD.

Make: QSMOTOR

Type and marking: QS60V1500W

Vehicle Type	Steinadler Pro
Position and arrangement of electric motor	
Drawing No.	Steinadler Pro-05-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025


e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Detail:

Marking position




Manufacturer: Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Type & Identification number: RJ-VCU-EVA20

Vehicle Type	Steinadler Pro
Position and arrangement of controller (Main controller)	
Drawing No.	Steinadler Pro-06-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025






e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Detail:

Marking position



Manufacturer: Nanjing Dunen Electric Co., Ltd.

Make: DUNEN

Type & Identification number: DEMCS0604QS05L

Vehicle Type	Steinadler Pro
Position and arrangement of controller (Sub controller)	
Drawing No.	Steinadler Pro-06-02


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



VCU is main controller, MCU is sub controller

Vehicle Type	Steinadler Pro
Control system of pure propulsion	
Drawing No.	Steinadler Pro-07-01





Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Marking position

Lithium battery
Marking: 55Ah

Vehicle Type	Steinadler Pro
Position and details of propulsion battery	
Drawing No.	Steinadler Pro-08-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Vehicle Type	Steinadler Pro
Vehicle drive-train and its control system	
Drawing No.	Steinadler Pro-09-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Vehicle Type	Steinadler Pro
Suspension arrangements	
Drawing No.	Steinadler Pro-10-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00


Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Detail:




Stroke: 40 mm

Vehicle Type	Steinadler Pro
Front suspensions	
Drawing No.	Steinadler Pro-11-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025



Detail:



Stroke: 60 mm

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

Vehicle Type	Steinadler Pro
Rear suspensions	
Drawing No.	Steinadler Pro-12-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00


Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Detail:



Vehicle Type	Steinadler Pro
Location and details of audible warning device	
Drawing No.	Steinadler Pro-13-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Vehicle Type	Steinadler Pro
Electrical circuit diagram	
Drawing No.	Steinadler Pro-14-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation




Vehicle Type	Steinadler Pro
Braking system	
Drawing No.	Steinadler Pro-15-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.


Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025


Right brake lever (Front secondary brake system):



Left brake lever (Rear secondary brake system):



Service brake pedal:



Vehicle Type	Steinadler Pro
Hydraulic reservoir	
Drawing No.	Steinadler Pro-16-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.


Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025


e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation


Brake hose 1




Brake hose 5




Brake hose 2




Brake hose 6




Brake hose 3




Brake hose 7



Brake hose 4



Brake hose 8



Brake pipe inner diameter: 3.2 mm outer diameter: 7.5 mm

Vehicle Type	Steinadler Pro
Brake hose	
Drawing No.	Steinadler Pro-17-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.


Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025


e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation


Brake disc



Brake caliper



A-A



Piston area: $2 \times 490.6 \text{ mm}^2$

Manufacturer: Rui'an Yuqi Automobile and Motorcycle Parts Co., Ltd.
Type: HK25-2

Vehicle Type	Steinadler Pro
Front brake details	
Drawing No.	Steinadler Pro-18-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.


Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025


e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation


Brake disc



Brake caliper



B-B



Piston area: 706.5 mm²

Manufacturer: Rui'an Yuqi Automobile and Motorcycle Parts Co., Ltd.


Type: HK30

Vehicle Type	Steinadler Pro
Rear brake details	
Drawing No.	Steinadler Pro-19-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.


Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025



e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Manufacturer: Rui'an Yuqi Automobile and Motorcycle Parts Co., Ltd.

Type & Marking: R8

Material: Metal mixtures, CaSiO_3

Asbestos free

Effective brake area: $1903 \text{ mm}^2 * 2 = 3806 \text{ mm}^2$

Vehicle Type	Steinadler Pro
Front brake pads	
Drawing No.	Steinadler Pro-20-01




Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Manufacturer: Rui'an Yuqi Automobile and Motorcycle Parts Co., Ltd.

Type: HB4F036

Material: Metal mixtures, CaSiO₃

Asbestos free

Effective brake area: $1310\text{ mm}^2 * 2 = 2620\text{ mm}^2$


Vehicle Type	Steinadler Pro
Rear brake pads	
Drawing No.	Steinadler Pro-21-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00


Application date: 22/02/2025

Right brake lever (Front secondary brake system):




Ratio: 6.16

Left brake lever (Rear secondary brake system):




Ratio: 6.16

Service brake pedal:



Ratio: 10.00

Parking brake handle:




Ratio: 3.17

Vehicle Type	Steinadler Pro
Brake lever, pedal and handle	
Drawing No.	Steinadler Pro-22-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.


Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025



e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Vehicle Type	Steinadler Pro
Location of power circuit components	
Drawing No.	Steinadler Pro-23-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



High voltage label:



Vehicle Type	Steinadler Pro
Location of high voltage label	
Drawing No.	Steinadler Pro-24-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



When the current exceeds 5 A, the overload protector is disconnected.

Vehicle Type	Steinadler Pro
Circuit breaker	
Drawing No.	Steinadler Pro-25-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Power wiring harness(orange)

Remarks: Cables exceeding 60V shall be wrapped in orange.

Vehicle Type	Steinadler Pro
Power wiring harness	
Drawing No.	Steinadler Pro-26-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



$$A+B+C \geq 2/3 Wf$$
$$182+460+182 \geq 2/3 \times 918 = 612$$

Vehicle Type	Steinadler Pro
Front protective structure	
Drawing No.	Steinadler Pro-27-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



$$A+B+C \geq 2/3 W_r$$
$$182+500+182 \geq 2/3 \times 894 = 596$$

Vehicle Type	Steinadler Pro
Rear protective structure	
Drawing No.	Steinadler Pro-28-01



Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Vehicle Type	Steinadler Pro
Controls I.D., tell-tales and indicators	
Drawing No.	Steinadler Pro-29-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Directly connected to the main controller, to drive speedometer through the average signal from four sub controller.


Vehicle Type	Steinadler Pro
Speedometer	
Drawing No.	Steinadler Pro-30-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation



Devices	Height of the illuminated surface from the ground		Luminous surface distance of two lamps	Distance from lamp center to front axle
	Upper	Lower		
Headlamp driving beam	1126 mm	963 mm	/	/
Headlamp passing beam				/
Front position lamp	1126 mm	963 mm	/	/
Daytime running lamp	1126 mm	963 mm	/	/
Stop lamp	753 mm	730 mm	/	/
Rear position lamp	753 mm	730 mm	/	/
Rear registration plate lamp	/	727 mm	/	/
Front direction indicator lamp	935 mm	908 mm	290 mm	/
Rear direction indicator lamp	695 mm	666 mm	365 mm	/
Side reflector	837 mm	757 mm	/	80 mm
Rear reflector	753 mm	730 mm	N/A	/

Vehicle Type	Steinadler Pro
Lighting installation	
Drawing No.	Steinadler Pro-31-01



Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Vehicle Type	Steinadler Pro
Rear-view mirrors and installation	
Drawing No.	Steinadler Pro-32-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Vehicle Type	Steinadler Pro
The seating position and R-point	
Drawing No.	Steinadler Pro-33-01



Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation




Vehicle Type	Steinadler Pro
Steering geometry	
Drawing No.	Steinadler Pro-34-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025



Detail: [e13*168/2013*02582*00](#)
[Société Nationale de Certification et d'Homologation](#)



Vehicle Type	Steinadler Pro
Anti-theft device	
Drawing No.	Steinadler Pro-35-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00


Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Detail:



Vehicle Type	Steinadler Pro
Construction and location of footrest	
Drawing No.	Steinadler Pro-36-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00


Application date: 22/02/2025

e13*168/2013*02582*00


Société Nationale de Certification et d'Homologation



Front registration plate
Size: 280×200



Rear registration plate
Size: 280×200




Vehicle Type	Steinadler Pro
Mounting space of registration plate	
Drawing No.	Steinadler Pro-37-01


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025



Detail: [e13*168/2013*02582*00](#)
[Société Nationale de Certification et d'Homologation](#)



Vehicle Type	Steinadler Pro
Location and details of charging interface	
Drawing No.	Steinadler Pro-38-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation



Manufacturer: Shandong SMT Electronic Technology Co., Ltd.

Make: SM

Type: SMCZ1P-7218A

Vehicle Type	Steinadler Pro
Charger	
Drawing No.	Steinadler Pro-39-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Information document number: 168/2013-Steinadler Pro-00

Application date: 22/02/2025




Table 1 - General contact allocation

	General allocation
1	Discretionary ^a
2	Bus positive line of SAE J1850 ^b
3	Discretionary ^a
4	Chassis ground
5	Signal ground
6	CAN_H line of ISO 15765-4 ^b
7	K line according to ISO 9141-2 and ISO 14230-4 ^b
8	Discretionary ^a
9	Discretionary ^a
10	Bus negative line of SAE J1850 ^b
11	Discretionary ^a
12	Discretionary ^a
13	Discretionary ^a
14	CAN_L line of ISO 15765-4 ^b
15	L line according to ISO 9141-2 and ISO 14230-4 ^b
16	Permanent positive voltage
a Assignment of Contacts 1, 3, 8, 9, 11, 12 and 13 in the vehicle connector is left at the discretion of the vehicle manufacturer. b Note, for Contacts 2, 6, 7, 10, 14 and 15 the related diagnostic communication assignments are shown. These contacts may also be used for alternate assignments in the vehicle connector, See 6.3 and 6.5 for further information.	

Vehicle Type	Steinadler Pro
Location of diagnostic connector	
Drawing No.	Steinadler Pro-40-01

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

MANUFACTURER'S STATEMENT ON ENDURANCE TESTING

(Annex V to Commission Delegated Regulation (EU) number 3/2014)
(A duly completed version of this statement shall be included in the information folder)

The undersigned : Ms. Shanshan Wang, General Manager

Company name and address of the manufacturer : Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Zone B, 528, Huilong South Rd, Rucheng Street, Rugao City,
Jiangsu Province, China

Name and address of the manufacturer's representative : Benling
(if any) Henegouwenlaan 28, 1966RK Heemskerk, Netherlands

Hereby states that the vehicles:

0.1. Make (trade name of the manufacturer) :  (RJTech)

0.2. Type : Steinadler Pro

0.2.1. Variant(s) : 00 e13*168/2013*02582*00

0.2.2. Version(s) : 00 Société Nationale de Certification et d'Homologation

0.2.3. Commercial name(s) (if available) : Steinadler Pro (L7e)

0.3. Category, subcategory and sub-subcategory of vehicle : L7e-A1

for which type-approval is sought shall withstand normal use as intended for at least 30,000 km travelled within five years of first registration, taking into account regular and scheduled maintenance and specific equipment adjustments, as described clearly and unambiguously in the instructions manual delivered with the vehicles.

The undersigned furthermore confirms that the endurance of the systems, parts and equipment critical for functional safety is ensured through appropriate testing and the use of good engineering practice.

This declaration has no bearing on any vehicle warranty.


Place : Jiangsu Province, China

Date : 22/02/2025

Signature :

Name and position in the company : Ms. Shanshan Wang, General Manager





Jiangsu YINGUAN Intelligence Technology Co., Ltd.

MANUFACTURER'S STATEMENT ON STRUCTURE INTEGRITY (Annex XIX to Commission Delegated Regulation (EU) number 3/2014)

The undersigned : Ms. Shanshan Wang, General Manager

Company name and address of the manufacturer : Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Zone B, 528, Huilong South Rd, Rucheng Street, Rugao City,
Jiangsu Province, China

Name and address of the manufacturer's representative : Benling
(if any) Henegouwenlaan 28, 1966RK Heemskerk, Netherlands

Hereby states that the vehicles:

0.1. Make (trade name of the manufacturer) :  (RJTech)

0.2. Type : Steinadler Pro

0.2.1. Variant(s) : 00 e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

0.2.2. Version(s) : 00

0.2.3. Commercial name(s) (if available) : Steinadler Pro (L7e)

0.3. Category, subcategory and sub-subcategory
of vehicle : L7e-A1

shall be constructed in a proper manner and are designed to be sufficiently robust to withstand the intended use over the vehicle's lifetime, taking into account regular and scheduled maintenance and specific equipment adjustments, as described clearly and unambiguously in the instructions manual delivered with the vehicles.


The undersigned furthermore agrees to and guarantees that specific analyses of vehicle structures, components and/or parts using engineering calculations, virtual testing methods and/or structural testing shall be made available in a timely manner to the approval authority and the European Commission upon request in case of a recall due to a serious safety risk.

This declaration applies to all vehicles covered by the type-approval to which this statement is annexed and has no bearing on any vehicle warranty.

Place : Jiangsu Province, China

Date : 22/02/2025

Signature :





Name and position in the company : Ms. Shanshan Wang, General Manager

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

MANUFACTURER'S CERTIFICATE ON ACCESS TO VEHICLE OBD (STAGE I) AND VEHICLE REPAIR AND MAINTENANCE INFORMATION

(Annex III to Regulation (EU) number 168/2013*2024/2847
implemented by Commission Implementing Regulation (EU) no. 901/2014*2020/239)

Reference number : Steinadler Pro-00

The undersigned : Ms. Shanshan Wang, General Manager

Company name and address of the manufacturer : Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Zone B, 528, Huilong South Rd, Rucheng Street, Rugao City,
Jiangsu Province, China

Name and address of the manufacturer's representative : Benling
(if any) Henegouwenlaan 28, 1966RK Heemskerk, Netherlands

Hereby certifies that:

it provides access to vehicle OBD and vehicle repair and maintenance information in compliance with
- Chapter XV of Regulation (EU) number 168/2013 with respect to the types of vehicle, engine and pollution-control device
listed in **Addendum 1** to this certificate.


The following derogation is applied : ~~early-over systems~~⁽¹⁾

The principal website addresses, through which the relevant information may be accessed and which are hereby certified to be in compliance with the above provisions, are listed in **Addendum 2** to this certificate along with the contact details of the manufacturer's representative listed in **Addendum 3** to this certificate, whose signature is below.

Where applicable: The manufacturer hereby also certifies that it has complied with the obligation in Article 57(8) of Regulation (EU) No 168/2013 to provide the relevant information for previous approvals of these vehicle types no later than six months after the date of type-approval.

Place : Jiangsu Province, China

Date : 22/02/2025

Signature : 



Name and position in the company : Ms. Shanshan Wang, General Manager

Addenda:

1. List of the types of vehicle, engine and pollution-control device.
2. Web sites addresses.
3. Contact details.

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

ADDENDUM 1

**to manufacturer's certificate with Reference number: Steinadler Pro-00
on access to vehicle OBD (stage I) and vehicle repair and maintenance information**

List of types of vehicle:

- | | | | |
|--------|---|---|--|
| 0.2. | Type ⁽²⁾ | : | Steinadler Pro |
| 0.2.1. | Variant(s) ⁽²⁾ | : | 00 e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation |
| 0.2.2. | Version(s) ⁽²⁾ | : | 00 |
| 0.2.3. | Commercial name(s) (if available) | : | Steinadler Pro (L7e) |
| 0.3. | Category, subcategory and sub-subcategory of vehicle ⁽³⁾ | : | L7e-A1 |
| 1. | Type-approval number including extension number (if available) | : | e13*168/2013*?????*00 |
| 1.1. | Type-approval issued on (date, if available) | : | Not applicable |

List of the types of engines:

- | | | | |
|------|--|---|-------------------------|
| 3. | Combustion engine /electric motor/
hybrid application ⁽¹⁾ code | : | QS60V1500W (Each motor) |
| 3.1. | Type-approval number (if available) | : | Not applicable |
| 3.2. | Type-approval issued on (date, if available) | : | Not applicable |

List of the types of pollution-control devices:

- | | | | |
|--------|--|---|----------------|
| 0.7. | Make(s) (trade name(s) of manufacturer) | : | Not applicable |
| 0.8. | Type | : | Not applicable |
| 0.8.1. | Commercial name(s) (if available) | : | Not applicable |
| 0.8.2. | Type-approval number including extension number (if available) | : | Not applicable |
| 0.8.3. | Type-approval issued on (date, if available) | : | Not applicable |

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

ADDENDUM 2

**to manufacturer's certificate with Reference number: Steinadler Pro-00
on access to vehicle OBD (stage I) and vehicle repair and maintenance information**

Web site addresses referred to in this certificate:

<https://rjtech-offroad.com/>

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

e13*168/2013*02582*00

ADDENDUM 3

Société Nationale de Certification et d'Homologation

**to manufacturer's certificate with Reference number:Steinadler Pro-00
on access to vehicle OBD (stage I) and vehicle repair and maintenance information**

Contact details of the manufacturer's representative referred to in this certificate:

Name: Benlinq

Address: Henegouwenlaan 28, 1966RK Heemskerk, Netherlands

Name and position in the company: Mous, Bennet Jonathan,

Representative

Tel: +31623305968

E-mail: Benlinq@outlook.com

Tax number: NL004941233B81

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

MANUFACTURER'S DECLARATION ON POWERTRAIN TAMPERING PREVENTION MEASURES (ANTI-TAMPERING)

(Annex II to Commission Delegated Regulation (EU) number 44/2014)

1. Vehicle manufacturer's declaration on powertrain tampering prevention measures (anti-tampering):

- Not to market interchangeable components which could enable propulsion unit performance to exceed levels applicable to the relevant (sub)category,
- Manufacturer-facilitated modifications shall not increase the propulsion unit performance of the vehicle,
- Modifications and interchangeability of parts and components

Manufacturer's declaration not to market interchangeable components which could enable propulsion unit performance to exceed levels applicable to the relevant (sub) category

0.4. Company name and address of the manufacturer : Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Zone B, 528, Huilong South Rd, Rucheng Street, Rugao City,
Jiangsu Province, China

0.4.2. Name and address of the manufacturer's representative (if any) : Benling
Henegouwenlaan 28, 1966RK Heemskerk, Netherlands

Hereby declares that the vehicles:

0.1. Make (trade name of the manufacturer) :  (RJTech)

0.2. Type : Steinadler Pro

0.2.1. Variant(s) : 00 e13*168/2013*02582*00
Société Nationale de Certification et d'Homologation

0.2.2. Version(s) : 00

0.2.3. Commercial name(s) (if available) : Steinadler Pro (L7e)

0.3. Category, subcategory and sub-subcategory of vehicle : L7e-A1

Jiangsu YINGUAN Intelligence Technology Co., Ltd.

Will not market interchangeable components which could enable propulsion unit performance to exceed levels applicable to the relevant (sub) category,

and that

The manufacturer-facilitated modifications of the following characteristics:

- ~~(a) Spark delivery of the ignition system,~~
- ~~(b) Fuel feed and delivery system,~~
- ~~(c) Air intake system including air filter(s) (modification or removal),~~
- (d) Propulsion battery configuration or electric power to the electric motor(s),
- (e) Drive-train,
- (f) And the control unit(s) that control(s) the propulsion unit performance of the powertrain.

shall comply with the requirements set out in point 2.6. of Annex II to Commission Delegated Regulation (EU) No 44/2014

Jiangsu Province, China

Place

22/02/2025

Date



e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Signature

Ms. Shanshan Wang, General Manager

Date


Jiangsu YINGUAN Intelligence Technology Co., Ltd.

STATEMENT CONCERNING AUTHORITY OF SIGNATURE ON COC PAPER

We, Jiangsu YINGUAN Intelligence Technology Co., Ltd., declare that the undersigned, Shanshan Wang, the General Manager of our company, will be the authorized person to sign the CoC paper of the vehicles.

Type: Steinadler Pro

Specification of signature of CoC:



Ms. Shanshan Wang, General Manager



Jiangsu YINGUAN Intelligence Technology Co., Ltd.

e13*168/2013*02582*00

Société Nationale de Certification et d'Homologation

Date: 22/02/2025

Place: Jiangsu Province, China

COMPLETE VEHICLE

EU CERTIFICATE OF CONFORMITY

The undersigned, Shanshan Wang, General Manager
Hereby certifies that the following complete vehicle:

- 0.1. Make (trade name of the manufacturer): **RJTech**
- 0.2. Type: **Steinadler Pro**
- 0.2.1. Variant: **00**
- 0.2.2. Version: **00**
- 0.2.3. Commercial name (if available): **Steinadler Pro (L7e)**
- 0.3. Category, subcategory and sub-subcategory of vehicle: **L7e-A1**
- 0.4. Company name and address of manufacturer:
Jiangsu YINGUAN Intelligence Technology Co., Ltd.
Zone B, 528, Huilong South Rd, Rucheng Street, Rugao City, Jiangsu Province, China
- 0.4.2. Name and address of manufacturer's authorized representative (if any):
Benlinq
Henegouwenlaan 28, 1966RK Heemskerk, Netherlands
- 0.5.1. Location of the manufacturer's statutory plate(s): **R, x 1000, y 245, z 470**
- 0.5.2. Method of attachment of the manufacturer's statutory plate(s): **Riveted on the chassis**
- 0.6. Location of the vehicle identification number: **R, x 460, y 240, z 240**
1. Vehicle identification number: **☆H2XAAAVC??1?????☆**


Conforms in all respects to the type described in EU type-approval e13*168/2013*????*00 (type-approval number including extension number) issued on XX/XX/XXXX (date of issue) and can be permanently registered in Member States having right/left-hand traffic and using metric/imperial unit for the speedometer.

Jiangsu Province, China

XX/XX/XXXX

Place

Date



(signature)



General construction characteristics

- 1.3. Number of axles: **2** and wheels: **4**
- 1.3.1. Axles with twinned wheels : **N.A**
- 1.3.2. Powered axles: **F & R**
- 6.2.4. Advanced braking system: **ABS / CBS / Both ABS and CBS / None**

Main dimensions

- 2.2.1. Length: **1818 mm**
- 2.2.2. Width: **918 mm**
- 2.2.3. Height: **1325 mm**
- 2.2.4. Wheelbase: **1257 mm**
- 2.2.4.1. Wheelbase sidecar: **N.A.**
- 2.2.5. Track width: **N.A.**
- 2.2.5.1. Track width front: **734 mm**
- 2.2.5.2. Track width rear: **712 mm**
- 2.2.5.3. Track width sidecar: **N.A.**
- 2.2.10.6. Ground clearance between the axles: **N.A.**
- 2.2.15. Wheelbase to ground clearance ratio: **N.A.**
- 2.2.17. Seat height: **N.A.**

Masses

- 2.1.1. Mass in running order: **173 kg**
- 2.1.2. Actual mass: **280 kg**
- 2.1.3. Technically permissible maximum laden mass: **310 kg**
- 2.1.3.1. Technically permissible maximum mass on front axle: **150 kg**
- 2.1.3.2. Technically permissible maximum mass on rear axle: **160 kg**
- 2.1.3.3. Technically permissible maximum mass on sidecar axle: **N.A.**
- 2.1.7. Technically permissible maximum towable mass:
- Braked: **N.A.** Unbraked: **N.A.**
- 2.1.7.1. Technically permissible maximum laden mass of the combination: **N.A.**
- 2.1.7.2. Technically permissible maximum mass at the coupling point: **N.A.**

Powertrain

- 3.1.1.1. Manufacturer: **N.A.**
- 3.1.1.2. Engine code (as marked on the engine or other means of identification): **N.A.**
- 3.2.1.2. Working principle of the combustion engine: **internal combustion engine (ICE)/positive ignition/compression ignition/external combustion engine (ECE)/turbine/compressed air**
- 3.2.1.4.1. Number of cylinders: **N.A.**
- 3.2.1.4.2. Arrangement of cylinders: **L / V / O / S**
- 3.2.1.5. Engine capacity: **N.A.**
- 1.9. Maximum net power: **N.A.**
- 1.10. Ratio maximum net power/mass of the vehicle in running order: **N.A.**
- 3.2.3.1. Fuel type: **N.A.**
- 3.2.3.2. Vehicle fuel combination: **mono-fuel/bi-fuel/flex-fuel**
- 3.2.3.2.1. Maximum amount of bio-fuel acceptable in fuel: **N.A.**

3.1.2.1. Manufacturer: TAIZHOU QUANSHUN ELECTRIC DRIVE TECHNOLOGY CO., LTD.
 3.1.2.2. Electric motor code (as marked on the engine or other means of identification):
 FR: QS60V1500W????? ?????? FL: QS60V1500W????? ??????
 RR: QS60V1500W????? ?????? RL: QS60V1500W????? ??????
 3.3.3.4. 45/30 minutes power: 6 kW (1.5 kW × 4)
 3.1.3.1. Manufacturer: N.A.
 3.1.3.2. Application code (as marked on the engine or other means of identification): N.A.
 3.3.1. Electric vehicle configuration: pure electric/hybrid electric/manpower electric
 3.3.5.2. Category of hybrid electric vehicle: off-vehicle charging/not off-vehicle charging
 3.9.2. Maximum assistance factor: N.A.

Maximum speed

1.8. Maximum speed of vehicle: 70 km/h
 3.9.3. Maximum vehicle speed for which the electric motor gives assistance: N.A.

Drive-train and control

3.5.3.9. Transmission (type): W
 3.5.4. Gear ratios: N.A.
 3.5.4.1. Final drive ratio: N.A.
 3.5.4.2. Overall gear ratio in highest gear: N.A.

Installation of tyres

6.18.1.1. Tyre size designation:
 Axle 1: AT22×7-10 35L Axle 2: AT22×7-10 35L
 Minimum Load capacity index:
 Axle 1: 18 Axle 2: 20
 Minimum speed category symbol:
 Axle 1: F Axle 2: F
 Recommended pressure:
 Axle 1: 45 kPa Axle 2: 45 kPa
 Rim size:
 Axle 1: 5.5×10 Axle 2: 5.5×10
 Sidecar wheel: N.A.

Bodywork

e13*168/2013*02582*00
 Société Nationale de Certification et d'Homologation

6.20.2.1. Door configuration and number of doors: N.A.
 6.16.1. Number of seating position: 1
 6.16.1.1. Location and arrangement: r1, 1C

Coupling devices

7.2.8. Type-approval number of coupling-device : N.A.

Environmental performance

4.0.1. Environmental step: Euro 5+ (3/4/5/5+)⁽⁴⁾
 4.0.6. Sound level measured according to Reg. (EU) 134/2014 including amendment Reg.(EU) 2023/2724: N.A.
 4.0.6.1. Stationary: N.A.
 4.0.6.2. Drive-by : N.A.
 4.0.6.3. Limit value for L_{urban}: N.A.

3.2.15. Exhaust emissions measured according to Reg. (EU) 134/2014 including amendment Reg.(EU) 2023/2724: N.A.

3.2.15.1. Type I test: tailpipe emissions after cold start, including the deterioration factor, if applicable:

CO: N.A.
 THC: N.A.
 NMHC: N.A.
 NOx: N.A.
 THC+NOx: N.A.
 PM: N.A.

3.2.15.2. Type II test: tailpipe emissions at (increased) idle and free acceleration:
 HC: N.A. ppm at normal idling speed and: N.A. ppm at high idle speed
 CO: N.A. %vol at normal idling speed and: N.A. %vol at high idle speed

3.2.15.3. Smoke corrected absorption coefficient: N.A.

Energy efficiency

4.0.2. Fuel consumption: N.A.
 4.0.3. CO₂ emissions: N.A.
 4.0.4. Energy consumption: 92 Wh/km
 4.0.5. Electric range: 51 km

Conversion of the performance of the vehicle:

8.1. Vehicle appropriate for converting its performance level between subcategories (L3e/L4e)-A2 and (L3e/L4e)-A3 and vice versa: yes/no

Additional information:

9.1. Remarks: N.A.
 9.2. Exemptions: N.A.